

AN INTRODUCTION TO

DIGITAL MULTIMEDIA

SECOND EDITION



T. M. SAVAGE
K. E. VOGEL

AN INTRODUCTION TO

DIGITAL MULTIMEDIA

SECOND EDITION



JONES & BARTLETT
LEARNING

T. M. SAVAGE

K. E. VOGEL

Both of
*University of
New Hampshire
at Manchester*

World Headquarters
Jones & Bartlett Learning
5 Wall Street
Burlington, MA 01803
978-443-5000
info@jblearning.com
www.jblearning.com

Jones & Bartlett Learning books and products are available through most bookstores and online booksellers. To contact Jones & Bartlett Learning directly, call 800-832-0034, fax 978-443-8000, or visit our website, www.jblearning.com.

Substantial discounts on bulk quantities of Jones & Bartlett Learning publications are available to corporations, professional associations, and other qualified organizations. For details and specific discount information, contact the special sales department at Jones & Bartlett Learning via the above contact information or send an email to specialsales@jblearning.com.

Copyright © 2014 by Jones & Bartlett Learning, LLC, an Ascend Learning Company

All rights reserved. No part of the material protected by this copyright may be reproduced or utilized in any form, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without written permission from the copyright owner.

An Introduction to Digital Multimedia, Second Edition is an independent publication and has not been authorized, sponsored, or otherwise approved by the owners of the trademarks or service marks referenced in this product.

Chapter 4: 4.9a, 4.13, 4.14b; Chapter 6: 6.1, 6.7, 6.10, p. 128, 6.13, 6.14, 6.15, 6.24; Chapter 9: 9.5, 9.6, 9.7, 9.8; Chapter 10: 10.3, 10.4; Chapter 11: 11.4 Adobe product screenshots reprinted with permission from Adobe Systems Incorporated.

Chapter 1: 1.6; Chapter 4: 4.1, 4.2, 4.3, 4.4, 4.5, 4.12, 4.14a; Chapter 7: 7.9; Chapter 8: 8.4, 8.5, 8.6, 8.7; Chapter 10: 10.1 screenshots reprinted with permission from Apple Inc.

Chapter 4: 4.6, 4.8; Chapter 5: 5.10, 5.11; Chapter 6: 6.23; Chapter 10: 10.2 screenshots used with permission from Microsoft.

Chapter 4: 4.9b screenshot is © Corel Corporation, reprinted by permission.

The screenshots in this product are for educational and instructive purposes only. All trademarks displayed are the trademarks of the parties noted therein. Such use of trademarks is not an endorsement by said parties of Jones & Bartlett Learning, its products, or its services, nor should such use be deemed an endorsement by Jones & Bartlett Learning of said third party's products or services.

Production Credits

Executive Publisher: Kevin Sullivan

Senior Developmental Editor: Amy Bloom

Director of Production: Amy Rose

Production Assistant: Eileen Worthley

Marketing Manager: Lindsay White

V.P., Manufacturing and Inventory Control: Therese Connell

Composition: Northeast Compositors

Cover Design: Kristin E. Parker

Cover and Chapter Opener Images: Butterfly © Neo Edmund/Shutterstock, Inc.; Smartphone/hands/butterflies

© Khomulo Anna/Shutterstock, Inc.; Grid background © Terry Chan/Shutterstock, Inc.

Printing and Binding: Edwards Brothers Malloy

Cover Printing: Edwards Brothers Malloy

Library of Congress Cataloging-in-Publication Data

Savage, Terry Michael, 1946-

An introduction to digital multimedia / T.M. Savage and K.E. Vogel. -- Second edition.

pages cm

Includes bibliographical references and index.

ISBN-13: 978-1-4496-8839-4 (pbk.)

ISBN-10: 1-4496-8839-X (pbk.)

1. Multimedia systems. 2. Digital media. I. Vogel, Karla E. II. Title.

QA76.575.S29 2014

006.7--dc23

2012038834


6048

Printed in the United States of America

17 16 15 14 13 10 9 8 7 6 5 4 3 2 1



Table of Contents



Preface	iii
Digital Multimedia Timeline	xi
1 THE MULTIMEDIA REVOLUTION	1
1.1 MULTIMEDIA DEFINED	2
1.2 ORIGINS OF MULTIMEDIA	4
1.3 SECOND-GENERATION INNOVATORS	9
1.4 LEGACY OF THE MULTIMEDIA PIONEERS	14
1.5 MULTIMEDIA TODAY	15
2 DIGITAL DATA	19
2.1 SYMBOLS, DATA, AND INFORMATION	20
2.2 DIGITAL DATA: BITS, BYTES, AND CODES	21
2.3 DIGITAL FILES	23
2.4 DIGITIZATION	25
2.5 DIGITAL ENCODING OF MEDIA	28
2.6 FILE COMPRESSION	29
2.7 ERROR DETECTION AND CORRECTION	31
2.8 ADVANTAGES OF DIGITAL DATA	32
2.9 DIGITAL CHALLENGES	33
2.10 SUMMARY	35

3	COMPUTER HARDWARE	39
3.1	COMPUTER SYSTEMS	40
3.2	COMPUTER PLATFORMS	42
3.3	COMPUTER HARDWARE BASICS	43
3.4	NETWORKS	72
3.5	SUMMARY	74
4	COMPUTER SOFTWARE	79
4.1	CATEGORIES OF SOFTWARE	80
4.2	OPERATING SYSTEMS	80
4.3	PROGRAMMING LANGUAGES	88
4.4	APPLICATION SOFTWARE	91
4.5	SUMMARY	99
5	TEXT	101
5.1	THE TEXT TRADITION	103
5.2	COMPUTER TEXT	107
5.3	FONT TECHNOLOGIES	109
5.4	MULTIMEDIA TEXT	111
5.5	ADDING TEXT TO A MULTIMEDIA APPLICATION	115
5.6	GUIDELINES FOR THE USE OF TEXT	116
5.7	SUMMARY	118
6	GRAPHICS	121
6.1	TRADITIONAL GRAPHICS	123
6.2	2-D COMPUTER GRAPHICS	125
6.3	VECTOR-DRAWN GRAPHICS	137
6.4	BITMAPPED AND VECTOR GRAPHICS COMPARED	140
6.5	3-D COMPUTER GRAPHICS	140
6.6	GUIDELINES FOR THE USE OF GRAPHICS	146
6.7	SUMMARY	147
7	SOUND	151
7.1	THE NATURE OF SOUND	153
7.2	TRADITIONAL SOUND REPRODUCTION	154
7.3	DIGITAL SOUND	154
7.4	SAMPLED AND SYNTHESIZED SOUND COMPARED	162
7.5	COMBINING SAMPLED AND SYNTHESIZED SOUND	164
7.6	ADVANTAGES OF DIGITAL SOUND	165

7.7	SOUND AND THE INTERNET	165
7.8	GUIDELINES FOR THE USE OF SOUND	166
7.9	SUMMARY	167
8	VIDEO	171
8.1	MOVING PICTURES	172
8.2	DIGITAL VIDEO	173
8.3	SOURCES OF DIGITAL VIDEO	177
8.4	GUIDELINES FOR VIDEO	188
8.5	SUMMARY	189
9	ANIMATION	193
9.1	THE BRAVE NEW WORLD OF DIGITAL ANIMATION	194
9.2	ANIMATION BASICS	195
9.3	TRADITIONAL ANIMATION	196
9.4	CEL ANIMATION	198
9.5	DIGITAL ANIMATION	200
9.6	ANIMATION TIPS AND GUIDELINES	207
9.7	SUMMARY	208
10	AUTHORING	211
10.1	AUTHORING APPLICATIONS	212
10.2	THE AUTHORING PROCESS	215
10.3	CHOOSING AN AUTHORING APPLICATION	222
10.4	SUMMARY	223
11	MULTIMEDIA DEVELOPMENT	225
11.1	THE DEVELOPMENT TEAM	226
11.2	TEAM MEMBERS	227
11.3	THE DEVELOPMENT PLAN	232
11.4	SUMMARY	238
12	PROFESSIONAL ISSUES IN MULTIMEDIA DEVELOPMENT	241
12.1	PROFESSIONS AND PROFESSIONAL RESPONSIBILITY	242
12.2	THE COPYRIGHT TRADITION: RIGHTS, REMEDIES, AND EXCEPTIONS	247
12.3	COPYRIGHT IN THE AGE OF DIGITAL MEDIA	250
12.4	DIGITAL RIGHTS MANAGEMENT	251
12.5	CONCLUSION	261

APPENDICES.....	267
A. CD DATA FORMAT AND DISC STANDARDS	267
B. THE SCANNING PROCESS	271
C. SOFTWARE ENGINEERING CODE OF ETHICS AND PROFESSIONAL PRACTICE	275
D. DIGITAL MULTIMEDIA AND ANALOG VIDEO	283
GLOSSARY	289
INDEX.....	325



Digital Multimedia Timeline



The Vision:

- 1843 Ada Byron (Lady Lovelace) predicts that the calculating machine proposed by Charles Babbage (Analytical Engine) might be used to compose music and produce graphics as well as be utilized in scientific inquiry. [www.ideafinder.com/history/inventors/lovelace.htm]
- 1914 Winsor McCay introduces *Gertie the Dinosaur*, an animated film consisting of 10,300 separate drawings. It was the first film animation to be created using keyframe animation techniques.
- 1915 Max Fleischer invents rotoscoping, an animation technique where the artist traces over live-action film movement, frame by frame. Computers have replaced the work of the artist in tracing over the live action.
- 1915 The first modern film is released by D.W. Griffith. *The Birth of a Nation* introduced moving shots and close-ups to movie production.
- 1928 The first cartoon with synchronized sound is released by Disney. *Steamboat Willie* gave birth to Mickey Mouse on November 18th.
- 1936 Alan Turing conceives the Universal Turing Machine, an abstract machine that could complete the tasks of any other information processing machine. Turing's work established the theoretical foundation of modern general-purpose computers.
- 1940 *Pat the Bunny* by Dorothy Kunhardt uses multimedia and interactivity to promote love of reading and learning in young children. The book includes rabbit fur, flowers to smell, mirrors, and a peek-a-boo blanket to generate interactivity with the story. (Random House Golden Books)
- 1945 Vannevar Bush publishes "As We May Think" in the *Atlantic Monthly*. In the article, Bush proposes a new way to organize information "as we think" and manage that information using multimedia input/output to the "Memex." The system he proposed would have microfilm, screen viewers, cameras, a vocoder, and electromechanical controls. This and a subsequent article predicted the technologies of hypertext, personal computers, speech recognition, expert systems, online encyclopedias, and the Internet.

- 1960s NLS, or oNLine System, is designed by Douglas Engelbart at Stanford Research Institute. NLS was the first practical use of hypertext, the mouse, raster-scan video monitors, screen windowing, and presentation programs. These developments pre-dated the personal computer, but contributed to modern graphical computer applications. (www.wikipedia.org, NLS computer system)
- 1960 J.C.R. Licklider publishes “Man-Computer Symbiosis” in which he proposes that computers should be developed with the goal of “enabling men and computers to cooperate in making decisions and controlling complex situations without inflexible dependence on predetermined programs” (Packer & Jordan 2001, 56).
- 1963 Ivan Southerland creates Sketchpad, a computer program that is considered the ancestor to modern computer-aided drafting programs and a breakthrough in computer graphics. The Graphical User Interface is developed from Sketchpad. (www.wikipedia.org, Sketchpad)
- 1966 Ivan Sutherland invents a head-mounted display to immerse the viewer in a visually simulated 3-D environment. He describes his “ultimate display” as a “room within which the computer can control the existence of matter” (Packer & Jordan 2001, 256).
- 1967 Ted Nelson invents the word *hypertext* for his nonsequential method of writing. Later he called the quest for relating all things Project Xanadu. His work continues as XanaduSpace, free software that allows the user to work with parallel documents. (www.xanadu.com/)
- 1970s Alan Kay and Adele Goldberg reveal the prototype for the Dynabook. The precursor of the multimedia laptop computer, it was conceived as “a dynamic medium for creative thought,” capable of synthesizing all media—pictures, animation, sound, and text—through a personal computer. They also developed “Smalltalk,” an object-oriented software language that led to the invention of the GUI (Packer & Jordan 2001, 170).
- 1970s The Aspen Movie Map project allows the viewer to navigate through an interactive video-disc view of Aspen, Colorado. Developed by Scott Fisher, this type of “surrogate travel” suggests the current notion of virtual reality (Packer & Jordan 2001, 260).
- 1972 PONG, the first commercial video game, is released by Atari. The Magnavox Odyssey, the first home video game system is released as well.
- 1974 The Intel 8080 microprocessor is released. MITS releases the first successful personal computer, the Altair 8800, with one KB of memory and available by mail for \$397.
- 1975 Bill Gates founds Microsoft as a software publishing enterprise.

Multimedia Matures

- 1976 Steven Jobs and Steve Wozniak launch Apple Computing. The Apple II in 1977 is the first to use color graphics.
- 1977 Myron Krueger explores the computer as a component in interactive art. In his “responsive environments,” the artist is a composer of intelligent real-time computer media spaces.
- 1979 Richard Bolt creates a “Spatial Data Management” system in which the user is engaged with data in forms of vision, sound, and touch. Working at the MIT Arch-MAC group with Negroponte, his spatial data-management system was the first hypermedia system to organize information in a 3-D virtual environment he called “dataland” (Packer & Jordan 2001, 186).
- 1981 IBM releases the first PC, which runs the new MS-DOS operating system.

1983	Compact Disc Technology is introduced in the United States. The standard was proposed by Philips & Sony in 1980.
1984	Apple introduces the Macintosh computer with a GUI operating system, mouse, 128 KB RAM, and 3.5 disk drive, for \$2495.
1985	Commodore Amiga combines advanced graphics, sound, and video capability to create the first true multimedia computer.
1988	Macromedia Director is released as the authoring software to produce desktop multimedia applications.
1991	Tim Berners-Lee distributes the first web browser and publishes the HTTP and HTML standards. His software was initially developed to unite research, documents, programs, laboratories, and scientists in an open hypermedia environment at CERN in Switzerland (Packer & Jordan 2001, 209).
1991	The MP3 digital audio compression format is invented.
1992	Text-based Virtual Realities create social phenomena called Mudding. A Multi-User Dungeon is a software program that accepts networked connections and gives each user real-time access to a shared database of “rooms,” “exits,” and other objects to manipulate in the telling of a shared adventure. LambdaMOO was the first popular MUD (Packer & Jordan 2001, 353).
1993	CAVE (Cave Automatic Virtual Environment) is an environment that combines interactive, computer-generated imagery and 3-D audio with physical space. Constructed by Sandin, DeFanti, and Cruz-Neira, the CAVE frees the user from the head-mounted display and dataglove of earlier environments (Packer & Jordan 2001, 287).
1993	Broderbund releases Myst, the first successful interactive computer game.
1995	<i>Toy Story</i> is released by Disney and Pixar. It is the first feature-length movie developed solely from digital animation techniques. The 77-minute film took 4 years to make and over 800,000 hours to render.

Multimedia Lifestyle

1994–96	Digital cameras become affordable and widely available. Apple QuickTake was the first digital camera for the consumer marketed to work with a home computer through a serial cable. Kodak, Casio, and Sony soon followed.
1995	DVD specifications are finalized for DVD-Movie player and DVD-ROM computer applications.
2000	The Play Station 2 video game console is developed by Sony.
2001	<i>Shrek</i> is released by DreamWorks. Over 275 artists, computer animators, and engineers spent three years completing the film, which was the most visually rich and technically challenging computer-animated film of the day.
2001	Steve Jobs stuns MacWorld in Oct. 2001 with the first iPod. The original 5-GB model could store 1000 tunes in your pocket. The iPod also came with iTunes and a new way of buying music by the song.
2003	Linden Research, Inc. introduces an Internet-based virtual world named Second Life. Users adopt avatars and interact with each other in a type of “metaverse” where they own land, create, and trade items and services with each other.

2003	Apple launches the iTunes Music Store with 200,000 songs at 99 cents each. By 2007, iTunes had sold 2 billion songs, 50 million TV episodes, and 1.3 million full-featured movies.
2005	YouTube changes the landscape for film production. Videos can be uploaded, viewed, and shared from this website. News, entertainment, and personal expression are published by amateur videographers and professionals alike. Founded by three former PayPal employees, it was sold to Google in 2006.
2006	Nintendo introduces the Wii, a new game console that features a wireless controller used as a pointing device. The Wii Remote can detect acceleration in three dimensions. The Wii introduces new forms of interactivity directed to a single game experience.
2007	Google introduces Street View, a feature of Google Maps that provides 360° panoramic street-level views of selected neighborhoods. Street View collects photos taken from a car that travels the streets of selected cities. Users can navigate from any direction and a variety of angles.
2007	Steve Jobs introduces the iPhone at January MacWorld. The iPhone combines a mobile phone, widescreen iPod with touch controls, and Internet communications. New interface software includes cover flow, multitouch display, and a predictive keyboard.
2009	Fujifilm releases the first consumer-grade stereoscopic digital camera designed to recreate the perception of 3-D depth.
2009	iTunes songs are DRM-free.
2011	Panasonic releases the first 3-D camcorder capable of 1920 × 1080/60p HD.

Mobile Multimedia


2007	The original Amazon Kindle eReader is introduced. It enabled users to search, download, and read books and magazines hosted by Amazon.com.
2008	The first commercial version of Android is released. Android is a mobile operating system developed by Google and the Open Handset Alliance. Android is a leading smartphone platform and the operating system is widely used on tablet computers.
2008	Apple expands the iTunes store to include Apps. The App Store opened as the iPhone 3G went on sale. In the first weekend, 100 million apps were downloaded.
2009	Barnes and Noble releases the Nook, a brand of eReader based on the Android platform. The original Nook included both Wi-Fi and AT&T 3G wireless connectivity.
2010	Apple releases the first iPad, a tablet computer, which supports audio-visual media including books, music, games, web content and apps. During the first year, Apple sold 14.8 million iPads worldwide.
2010	Apple releases iBooks, making electronic books available for iOS. The iBooks reader application is available free through the App Store.
2012	Microsoft launches the Surface tablet that incorporates Windows 8 and Microsoft's tabletop UI.

Resources

- Ament, Phil. "Ada Lovelace." Nov. 23, 2005. The Great Idea Finder. Dec.13, 2007 <http://www.idealfinder.com>.
- Barabash, Craig and Janice Kylo. "History of Multimedia." Dec. 13, 2007. <http://www.ucalgary.ca/~edtech/688/hist.htm>.
- Butzgy, Mike. "Writing for Multimedia: Great Moments in Multimedia History." 2004. Dec. 14, 2007 <http://writing.atomicmartinis.com/moments.htm>.
- Montgomery, Tim. "The Unofficial DreamWorks Animation Archive." Jan. 16, 2007. Dec. 14, 2007 <http://animationarchive.net/>.
- Packer, Randall, and Ken Jordan, editors. *Multimedia from Wagner to Virtual Reality*. 2001, New York: W.W. Norton & Company.
- Wikipedia. "SketchPad." Nov. 16, 2007. Dec. 14, 2007 <http://wikipedia.com>.
- Wikipedia. "NLS (computer system)." Jan. 8, 2008. Dec. 14, 2007 <http://wikipedia.com>.
- Zakon, R.H. "Hobbes' Internet Timeline v8.2." 1998. Dec.13, 2007 <http://www.zakon.org/robert/intyernet/timeline/>.

Chapter 1

The Multimedia Revolution



Topics you will explore include:

- Multimedia Revolution
- Multimedia Defined
- Forms of Multimedia
 - Noninteractive
 - Interactive
 - Basic
 - Hypermedia
 - Adaptive
 - Immersive
- Visionaries of Multimedia Computing
 - Vannevar Bush
 - Alan Turing
 - Douglas Engelbart
 - Theodore Nelson
 - Alan Kay
 - Steve Jobs
 - Tim Berners-Lee
- Potential of Digital Media

“Any sufficiently advanced technology is indistinguishable from magic.”

Arthur C. Clarke

Multimedia computing has produced a revolution. We shop, study, research, play, and communicate differently because of it. Like other advanced technologies, multimedia is, as Clarke would say, magical.

How else should we describe a little box that gets smaller but more powerful each year, and that pours forth an endless stream of words and sounds of pictures and movies? The multimedia computer captures all manner of worldly experience and even presents us with worlds of its own.

As dramatic as the impact of multimedia has been, its story is far from finished. We have good reason to anticipate ever more powerful multimedia systems. Multimedia is not only advanced; it is advancing. The revolution will continue.

Revolutions displace traditional beliefs and practices. They also create entirely new activities and products. The Industrial Revolution displaced traditional craftsmanship; goods that had been produced by hand in small shops were now made in factories by machines. It also produced new materials and products—steel, plastic, automobiles, and airplanes—that radically changed the ways in which people conducted their lives. The multimedia revolution is also displacing tradition and ushering in new products and activities. In this chapter we explore the nature of contemporary multimedia as well as the innovations of the pioneers whose visions shaped its evolution.

After completing this chapter, you should understand:

- The defining elements of modern multimedia, including its different forms
 - Noninteractive
 - Interactive
 - Basic
 - Hypermedia
 - Adaptive
 - Immersive
- Key contributions to the development of multimedia by
 - Vannevar Bush
 - Alan Turing
 - Douglas Engelbart
 - Theodore Nelson
 - Alan Kay
 - Steve Jobs
 - Tim Berners-Lee
- The nature and potential of modern multimedia

1.1 Multimedia Defined

Contemporary **multimedia** is defined as the development, integration, and delivery of any combination of text, graphics, animation, sound, or video through a digital processing device.

The key phrase in this definition is “digital processing device.” It was the digital computer and its many variants such as tablets, smartphones, and PDAs that transformed tradition and produced “new media.” The computer displaced traditional techniques for creating and editing all forms of media. Word processing displaced the typewriter, the CD transformed sound and music production, and digital cameras and editing software have replaced film and the darkroom. The reason for this transformation is simple: computers can now create media that rival the quality of traditional products and they can do so more efficiently and more economically. Analog media, like traditional craftsmanship, will continue to exist, but their dominance in the marketplace is at an end. Media professionals are building their careers with digital technology.

The term *computer* derives from the human calculators who performed complex mathematical operations before these functions were completely automated. For many years, most people thought computers would only be used for calculation and sorting data.

The multimedia revolution is not just about performing traditional tasks in new ways. It is also about creating new approaches to communication, commerce, education, and entertainment. Cell phones become text messengers, cameras, and video displays. E-commerce gives shoppers instant access to countless products and services complete with pictures, demos, reviews, and price comparisons. Classrooms lose their walls as digital media—graphics, animation, sound, and video—stream through electronic networks. New forms of entertainment, such as podcasts, video games, online poker tournaments, and interactive film, have transformed that industry as well. In these cases, and in many more, digital multimedia is changing the world by making it possible for users to interact with information in new ways.

So important are these new forms of interactivity that multimedia applications are often differentiated based on the degree and quality of interaction they support. Some applications are designed to allow little or no interactivity; others encourage as much interaction as possible.

In **noninteractive multimedia**, the user has no control over the flow of information. The developer establishes a sequence of media elements and determines the manner in which they will be presented. An information kiosk at a museum might regularly repeat a series of slides describing the day’s events. Such applications are often a simple and effective way to draw attention to announcements, products, or services without requiring any action of the part of the viewer. Digitally animated films, such as *Toy Story* or *Shrek*, are much more sophisticated and are engaging examples of noninteractive multimedia. The greatest promise and power of multimedia, however, lies in its ability to transform passive recipients of information into active agents.

In **interactive multimedia**, users are able to control the flow of information. There are several types of interactive multimedia. The first provides **basic interactivity**. Basic interactions include menu selections, buttons to advance screens, VCR-like controls, clickable objects, links, and text boxes for questions or responses. **Hypermedia** is a more advanced form of interactive media in which the developer provides a structure of related information and the means for a user to access that information. An online anatomy tutorial, for example, organizes information based on physiological relationships and may enhance a user’s understanding through hyperlinks to related text, drawings, animations, or video.

Still more advanced forms of interactive multimedia adapt the presentation of information to the needs or interests of users. Such applications range from relatively simple merchandizing programs that offer suggestions for purchases based on past interactions to advanced tutorials that adjust lessons based on student performance. These applications embody aspects of intelligence and decision making and are described as **adaptive multimedia** or **intellimedia**. The range of these forms of multimedia is likely to expand significantly with continued development in another major area of computer research—artificial intelligence.

Another powerful form of multimedia interactivity is found in advanced simulations and games that create their own **virtual reality**. Virtual realities are not simply responsive to users; they are *immersive*. An **immersive multimedia** application draws its users into an alternate world, engaging them intellectually, emotionally, and even viscerally. Advanced flight simulators so thoroughly immerse pilots in a world of virtual flight that they routinely serve as substitutes for training in actual aircraft. Video games can draw players into other worlds for hours or even days on end.

Multimedia will continue to shape our world, and each of us can benefit from knowing more about what it is, where it came from, how it works, and where it is likely to go. Individual involvement in the creation of multimedia will vary widely. For some, multimedia production may mean little more than attaching photos to email. Others will create presentations or build their own websites. Yet others will become specialists in one of the many areas of professional multimedia development. All will find that advancing digital technology continually puts more power in their hands—power to shape media to their own purposes.

Using this power effectively requires an understanding of the basic concepts that underlie multimedia hardware and software. It also requires a basic knowledge of the practices and principles of a wide range of media. Multimedia is, first and foremost, interdisciplinary. By definition, it draws on the multiple traditions, talents, and perspectives of text, graphics, sound, video, and animation. To use these varied resources effectively, multimedia developers need an awareness of the traditions and best practices of each. In chapters to come, we will explore each of these topics.

Taking advantage of the power of multimedia also means looking to the future and actively considering the new possibilities of digital technology. To try to envision the future, it helps to revisit the visionaries of the past. These were the pioneering theorists who glimpsed the promise of multimedia long before there were multimedia computers. Their stories will help us understand the reasons for many of the features of multimedia computers—hyperlinks, mice, windows, graphical user interfaces—and also the reasons to expect more innovations in the future.

1.2 Origins of Multimedia

In a sense, multimedia can be traced to the beginnings of civilization. Early humans had a clear appreciation of the value of reinforcing their messages with different kinds of sensations. Cave paintings at Lascaux in southern France were given an air of mystery through the psychological and sensory effects of the passageways—deep, dark, and

cold—that led the visitor away from an ordinary world to an otherworldly realm (Packer and Jordan 2001, xx–xxi).

Early theatrical performances greatly extended this interest in multisensory experience. Ancient Greek actors performed to the accompaniment of music and the chanting and singing of a chorus. Elaborately painted stage scenery, apparently with convincing three-dimensional effects, and stage props (furniture, weapons, even chariots) formed a backdrop for performances. The Greeks also made use of various machines to heighten the intensity of the dramatic performance. One (the *keranoskopeion*) simulated lightning; another (the *bronteion*) produced the rumble of thunder.

Multimedia further evolved as new technologies arose to represent various forms of sensory experience. By the early 20th century, it was possible to add sound to previously silent films, and movies became multimedia. As new capabilities were added later in the century (including color, stereo, and surround sound), and as filmmakers learned to exploit the potential of their tools (close-ups, fades, flashbacks, cut-aways, and special effects), the movie developed a formidable expressive power.

By the mid-1900s, the pace of technological development increased dramatically. A very different kind of machine emerged, and a few individuals began to glimpse the possibility of using it to dramatically extend the scope of multimedia.

Vannevar Bush and the Memex Machines

Few men were as well poised as **Vannevar Bush** (1890–1974) to understand the revolutionary potential of the emerging technologies. Bush was the director of the U.S. Office of Scientific Research and Development during World War II and oversaw the work of some six thousand scientists on projects ranging from radar to the atomic bomb. He was also an experienced and talented scientist in his own right, having developed, among other things, the Differential Analyzer, a massive electromechanical analog computer for solving differential equations.

In 1945, Bush wrote “As We May Think.” In this now-classic article, he proposed the creation of a new kind of machine to make the work of scientists more efficient and to make more effective use of the huge and “growing mountain of research.” The machine would accomplish this by overcoming human weaknesses and building on human strengths. Bush’s hypothetical machine was called Memex and multimedia was central to its design.

Memex I

One important human limitation is memory. We are limited in how much we can remember and our memories are neither completely reliable nor permanent. In Bush’s first vision, **Memex** (or “memory extender”) would solve these problems with microfilm. He envisioned a complete *Encyclopedia Britannica* stored in the space of a matchbox. Many other texts, photos, and handwritten notes would readily fit in the space of his desk-like machine. The capacity of Memex would be huge—one could add five thousand pages a day and it would still take hundreds of years to fill the machine. The contents of the Memex would be completely accurate and they would last forever.

Another human limitation is data recording. This is often a slow and laborious process. Bush proposed several multimedia devices to aid in collecting and recording data for the Memex. These included a “vocoder,” which would produce written input from the spoken word, and a “Cyclops Camera” to be worn on the forehead and controlled by a wire running to a hand (Figure 1.1). The camera would allow a researcher to immediately photograph anything of interest. Pictures would be rapidly developed using a dry-photography technique and could also be connected to the written record in the machine.



Figure 1.1 Sketch of Cyclops Camera.

Time-consuming repetitive thought processes, such as arithmetical calculations, also limit human intellectual productivity. Bush’s machine would take over these tasks by automatically performing mathematical calculations and carrying out simple forms of logical reasoning. Memex I would not be capable of “mature thought”; however, by freeing its user of the burdens of calculations and simple inferences, it could make more time available for creative, original thinking.

In a number of ways, then, Bush believed that his machine could compensate for the limitations of human intellect. Memex could also revolutionize the way information was stored and accessed by taking advantage of one of the strengths of the human mind.

The human mind, he argued, operates by association: “With one item in its grasp, it snaps instantly to the next that is suggested by the association of thoughts, in accordance with some intricate web of trails carried by the cells of the brain” (Bush, in Nyce and Kahn 1991, 101). Traditional systems of organizing information rely on alphabetical or numerical lists. These have nothing to do with the way information is generated or used in the mind. As a result, it is often difficult to find related facts and beliefs. Bush’s Memex, in contrast, would organize its information based on associations, or as we actually think.

To form an association between two items of knowledge (facts, beliefs, theories, etc.), the Memex user would simply display them together and tap a key. The items would



Figure 1.2 Visionary sketch of Memex (note mechanical details).

then be joined. Repeating this process with other items would produce a “**trail**” of associations that could then be preserved, copied, shared, modified, and linked to other trails. The next time a particular item was accessed, all of its connections to related information would also be available. The pattern of associations Bush had in mind would be vast and complex. In fact, he described Memex as “an enlarged intimate supplement” to its user’s memory, one that “stores all his books, records, and communications, and which is mechanized so that it may be consulted with exceeding speed and flexibility” (Bush, in Nyce and Kahn 1991, 102) (Figure 1.2).

“As We May Think” also covered some of the operational details of the Memex—levers to advance pages, keys to return to the first page, the ability to annotate sources, the advantages of vacuum tubes over mechanical switches, and so on. In general, however, his article was a kind of “*imaginering*” in which new conceptual possibilities rather than

blueprints for actual machines were his concern. He had ignored, as he said, all sorts of “technical difficulties” but he insisted that he also had ignored “means as yet unknown” that would dramatically accelerate progress toward the actual construction of a Memex. Between 1945 and 1959, a number of such advances did occur and these occasioned another article by Bush called “Memex II.”

Memex II

Memex II was very similar to the original Memex. Bush still emphasized the importance of association as a means of indexing knowledge, and he still thought of his machine as a device to assist individuals in accessing and manipulating different forms of information. Technical developments suggested, however, that the original dream was much closer to realization and that it could be extended in various ways. Many innovations had impressed Bush, but the most significant were magnetic tape, the transistor, and the digital computer.

Magnetic tape was a more suitable storage medium than the dry photography of Memex I. It could be written to, or erased, almost instantaneously and it could hold more information. Magnetic tape also had greater multimedia capability—in addition to recording text or still images, it could hold “scenes, speech, and music” as well as movies and television.

Memex I aided its owner by storing and retrieving information by association and by automatically performing repetitive, time-consuming mental tasks. Memex II envisioned an extension of these benefits with large, professionally maintained associational databases. These databases could be purchased on tape or even delivered remotely via facsimile transmission. Bush’s trails of associations would now be more sophisticated (color-coded to reflect their age, for instance) and reinforced by repetition, much as the mind can reinforce its memories.

More significant, however, were the ways in which an improved Memex might be combined with a digital computer. The Memex could efficiently organize enormous amounts of information, and it could perform basic logical operations on that information. To realize its full potential, however, Bush believed that “Memex needs to graduate from its slavish following of discreet trails . . . and to incorporate a better way in which to examine and compare the information it holds” (Bush, in Nyce and Kahn 1991, 180). The computer seemed to Bush to offer the possibility of such a “better way.” Memex II could be used in many different disciplines. As an example, Bush sketched a system in which this new, hybrid machine would use evaluation functions to continually revise its recommendations for medical diagnoses and treatment plans to physicians. His machine would learn from experience, effectively incorporate incomplete or even contradictory information, and thus even demonstrate a form of judgment. Doctors could use Memex to supplement their own memories of particular cases and to receive diagnostic advice based on the machine’s database of previous cases and treatments.

Bush stressed that such machines would always be subordinate to their human owners and he thought that there would be areas of human creative endeavor that “will always be barred to the machine” (Bush, in Nyce and Kahn 1991, 183). But he also recognized the

significance of early work in artificial intelligence (AI) and he even anticipated, at least in general outline, such future AI initiatives as expert systems.

AI and Expert Systems

Artificial intelligence is a field of computer science dedicated to developing computer systems that behave as if they have human intelligence. **Expert systems** were AI initiatives of the 1970s and 1980s. These systems incorporated the knowledge of content experts such as physicians or engineers. One of the first, *Mycin*, aided in the diagnosis of blood diseases.

Bush's work is remarkable for its early insights into the ways in which multimedia machines might improve the collection and use of information. He knew that advancing technology provided an opportunity to shape new tools to serve human needs and his work remains a model of the creative possibilities of "imagineering." The revolution Bush foresaw continues, and it continues for a reason that he glimpsed but did not fully articulate. The machine that he saw as a useful addition to his Memex came to dominate all information systems and, for that matter, virtually every aspect of modern life. The source of the extraordinary development, and

continuing potential, of the digital computer is to be found powerfully expressed in the work of another 20th-century theoretician, the British mathematician Alan Turing.

Alan Turing and the Universal Machine

Alan Turing (1912–1954) was an important contributor to the development of the modern computer. Turing made practical contributions to computing, including work on a special-purpose computational machine, the Colossus, used to break the German Enigma code in World War II. His most significant contribution was theoretical, however. He made it in 1936, well before there were any digital computers at all. In that year, Turing published a paper with the formidable title, "On Computable Numbers with an Application to the Entscheidungsproblem." The paper was concerned with the problem of proving whether or not there could be an effective procedure (that is, a step-by-step process) to answer all questions of mathematics.

He concluded that there would always be mathematical problems that could not possibly be solved. In order to demonstrate this, Turing needed a clear definition of "effective procedure." He found his definition in the operation of a kind of abstract machine, which has come to be known as a *Turing machine*.

A Turing machine is an imaginary device with three main components: first, an infinitely long tape consisting of a single row of squares; second, a read/write head that can move along the tape one square at a time; and third, a set of instructions. The machine can read and write a number of symbols and can be changed from one to another "state." What the machine does at any particular time is determined by the state it is in, the contents of the tape, and the rules it is given to follow. Once set in motion, the machine scans the square above its read/write head, compares the contents of the square to its instructions, performs the relevant operation (writing, erasing, leaving blank) and moves left or right to start the process once again on another square. When the machine reaches a state in which no more instructions apply, it halts. The marks remaining on the tape then represent the response to the task at hand.

Turing's analysis suggested that "Turing machine computable" and "effective procedure" mean the same thing; any time we have an effective procedure we can always design a specific Turing machine to carry it out. If we know how to calculate the area of a sphere, we can create (at least in our imagination) a Turing machine to perform this task. If we know how to plot the trajectory of an artillery shell, we can create another Turing

machine that will carry out this task, and so on. Every effective procedure will have a corresponding Turing machine.

Such single-purpose machines were, however, only part of Turing's analysis. He also demonstrated that it was possible to build *one* machine that could imitate any and every single-purpose machine. This new machine, the so-called **universal Turing machine**, stood ready to carry out (at least in theory) any conceivable effective procedure.

The universal Turing machine differs from a simple Turing machine in that it is able to accept a description of another machine and imitate the latter's behavior. The universal Turing machine, in short, is universal because it can imitate *any* Turing machine. If we can build a machine to add and another to alphabetize lists, we can also build a third that can perform both tasks. In fact, the third can perform the tasks done by any Turing machine at all. This means that there is a single machine that can carry out *any* effective procedure.

Turing showed how such a universal machine could be built—how data and instructions could be given to it, how the machine might process the data, and how it could then return an answer. The modern electronic computer is a practical embodiment of Turing's universal machine. The programs we install on our computers in effect turn them into a variety of special-purpose machines—machines to solve equations, process words, edit photos, compose songs, create video, and so on. Our computers have important limitations, of course: they always seem to need more memory, processing speed, and bandwidth. But the question naturally arises: What might we do with a computer if we could have all the computational power we might want?

Turing's central contribution was to answer this question. His answer was that such a computer could perform *any* information-processing task for which we (or the computer itself) can devise a set of rules.

The radical implications of his answer were not lost on Turing himself. Later he would argue that computers would one day think for themselves and that the answers to any question posed to them would be indistinguishable from the answers of human beings. He even proposed an exercise, the so-called **Turing test**, that he thought would prove this.

Multisensory experience would also eventually be possible for Turing's machines. He envisioned such future creations moving about, gaining their experience from direct interaction with the world, and learning in much the same way as humans learn. This dream, of course, presupposes a very sophisticated form of multimedia computing and one that many would reject for a variety of reasons. Objections aside, however, Turing's enduring legacy was his demonstration of the remarkable power and versatility of the computer—if we can think of a way to do it, a computer *can* do it. Computationally, there is every reason to dream and there is no end to the magic.

An *effective* procedure is a step-by-step process guaranteed to produce a particular result. For instance, the rules of long division provide an effective procedure for calculating the result of dividing one number by another. If we follow each step properly, we are guaranteed a correct answer.

1.3 Second-Generation Innovators

Bush and Turing belonged to a generation of theorists with the imagination and foresight to predict what they could not yet actually do. By the 1960s, the evolution of digital

computers led a new generation of theorists to propose innovative practical uses for these new machines.

Douglas Engelbart: New Forms of Human–Machine Interaction

Like Bush, **Douglas Engelbart** was convinced that computers could be used to improve human problem solving. In his 1962 article, “Augmenting Human Intellect: A Conceptual Approach,” he proposed the immediate development of practical devices to increase “the intellectual power of society’s problem solvers” (Packer and Jordan 2001, 90). Engelbart fully understood the wide-ranging potential of computers and immediately proposed applications beyond their customary mathematical and sorting operations. In fact, he argued that anyone who uses any form of symbol (“the English language, pictographs, formal logic or mathematics”) “should be able to benefit significantly” (69). Among the innovations he proposed in his article were word processing (“think of it as a high-speed electric typewriter with some special features” [74]) and computer-aided architectural design.

Engelbart insisted that there was no need to wait for an improved understanding of the human mind or for more powerful computers: progress on augmentation systems could be made immediately. He then acted on his own advice. With funding from the Advanced Research Projects Agency (ARPA), he established a team of researchers at the



Figure 1.3 Engelbart’s mouse.

Stanford Research Institute, and by 1968 he was able to demonstrate (at the Fall Joint Computer Conference in San Francisco) several significant innovations in human–computer interactivity. These included the mouse (Figure 1.3), windows for text editing, and electronic mail. These components were integrated into a system that he called the NLS, or oNLine-System. Engelbart had pointed the way to a new, intuitive interface with computers and to new ways in which computers could be used to communicate with others.

Theodore Nelson: Hypertext and Hypermedia

Ted Nelson was a pioneering theorist of early computer communications. He coined the terms *hypertext* and *hypermedia* in 1963 to represent his vision of a new form of information storage and retrieval. **Hypertext** is interactive text that is linked to other information. Engelbart’s mouse might now be used to click on a word, causing the computer to transport the user to another screen of text containing a definition, explanation, or other related information. Hypermedia extends this interactivity to other media, such as images, sounds, or animations.




Figure 1.4 Nelson’s sketch of a “cross tangle of ideas.”

Nelson’s vision was directly and deeply influenced by Vannevar Bush’s 1945 article, “As We May Think” and by Douglas Engelbart’s explorations of interactive computing. Like Bush, Nelson emphasized the associational qualities of human thought, but he also carried this vision further than Bush. For Nelson, knowledge was intrinsically unstructured, “a vasty cross-tangle of ideas and evidential materials, not a pyramid of truth” (Packer and Jordan 2001, 157) (Figure 1.4). “Professionalism,” he suggested, “has created a world-wide cult of mutual

incomprehensibility and disconnected special goals. Now we need to get everybody back together again” (161).

The computer, he argued, would be central to this task. Engelbart's NLS, with its keyboards, screens, mouse, and network connections, impressed Nelson as a "wonder and a glory" (162). NLS showed how the computer could revolutionize the creation and transmission of knowledge. Nelson began to plan a vast knowledge resource that would create "a community of common access to a shared heritage" (161). He called his proposed worldwide, cultural resource **Xanadu** after the "magic place of literary memory" (155) described in a poem by Samuel Taylor Coleridge. No longer focused on the needs of scientists and other specialists, the Xanadu project would create a dynamic, ever-expanding, hypertext library available to everyone. Xanadu would also support collaborative editing, track text changes throughout the revision process, and provide a means of crediting authors and distributing royalties. While Xanadu itself has not been completed, it serves as a model of the form Bush's original dream might take in an age of universal Internet access.

In Nelson's vision, hypertext and hypermedia would transform the uses of machines, placing them in the service of humans the world over. As he expressed it in 1974: "Now that we *have* all these wonderful devices, it should be the goal of society to put them in the service of truth and learning" (161).

Alan Kay: The GUI and the Multimedia Computer

Among the members of the enthusiastic audience for Engelbart's 1968 presentation was **Alan Kay**. Kay was introduced to the field of interactive computer graphics as a graduate student at the University of Utah. His doctoral dissertation dealt with a personal information device very similar to the modern laptop computer.

In the early 1970s, Kay joined Xerox PARC (the Palo Alto Research Center) and founded the Learning Research Group. Here he combined his interest in computer technology with explorations of various learning theories. His goal was to design a computer to support the ways in which people actually perceive, learn, and create. He named his proposed machine the **Dynabook** and he thought of it as a "personal computer" (Figure 1.5). But "personal" did not mean "personally owned" for Kay—it meant "intimate," closely tied to the mind and interests of its user. And the users were not going to be computer specialists—anyone should be able to use the Dynabook. This meant that Kay needed to find an intuitive, natural way for people to interact with computers.

Kay's solution is known as a **GUI** (pronounced "gooey") or Graphical User Interface. A GUI uses graphic symbols to represent the components and processes of computers—a picture of a typed page to represent a text file, a folder to represent a directory, and so on. These elements are selected and used with a combination of input devices such as a mouse and keyboard. Today the graphical user interface is nearly universal and is often taken for granted, as if it was the inevitable result of advancing technology. In fact, Kay produced the GUI by adapting technology to the insights of various learning theorists including Jean Piaget, Seymour Papert, and Jerome Bruner. The interface Kay designed was intuitive because it grew out of basic principles of human learning.



Figure 1.5 Sketch of proposed Dynabook.

The Dynabook was also intended to support a wide range of creative activities. Kay envisioned the computer as a powerful aid to writing, painting, and music composition. His research group designed programs to support each of these areas, allowing the machine to display graphics and play music as well as process numbers and text. In fact, the Dynabook was to be a full-blown multimedia computer—he called it a **meta-medium**, a machine that could embody any medium. The Dynabook would also be **modeless**. Users would be able to move seamlessly among different media, not thinking of themselves as confined to writing, painting, or animating mode. They could switch instantly to a different medium and activity by simply clicking on another window.

The Dynabook became the model for intuitive, accessible multimedia computing, and although it was never put into production, it greatly influenced the first commercial GUI computer, the Xerox Alto produced in 1973.

Steve Jobs: The Multimedia Hardware Revolution

Imagine having your own self-contained knowledge manipulator in a portable package the size and shape of an ordinary notebook. Suppose it had enough power to outrace your senses of sight and hearing, enough capacity to store for later retrieval thousands of page-equivalents of reference materials, poems, letters, recipes, records, drawings, animations, musical scores, waveforms, dynamic simulations, and anything else you would like to remember and change (Kay and Goldberg 2003, 394).

For the population at large, the vision Kay presented of a new form of multimedia computer was, in 1977, little more than an enticing dream. Steve Jobs and the Apple computer would change that.

Steve Jobs (1955–2011) and Steve Wozniak founded Apple in 1976. In 1979, Jobs visited Xerox PARC and was immediately “saturated,” as he would later say, by the idea of the graphical user interface. Jobs saw in the GUI a potential revolution, one that “empowered people to use the computer without having to understand arcane computer commands” (Jobs 1995). By 1984, this “humanistic” idea had been given technical expression in the Apple Macintosh.

The Macintosh was conceived and marketed as a direct challenge to the IBM personal computer (PC). In the 1980s, IBM used the Microsoft DOS operating system. Computer users typed cryptic commands to instruct the machines to perform such tasks as loading programs, saving files, or accessing storage devices. This “command-line” interface required users to learn the language of the computer, a language that few found intuitive.

The GUI, as it was further developed and refined at Apple, allowed users to control the computer through icons with familiar human associations—desktops, file folders, trash cans, and the like. These graphical symbols were only one aspect of Apple’s multimedia vision. The Mac was also the first mass-produced personal computer with built-in sound support. In fact, the first Macintosh actually introduced itself to the audience by speaking.

Jobs’s vision of “communication appliances” that could serve the needs of a wide range of people could now be put into practice. Musicians, graphical artists, publishers, scientists, and engineers soon were using Macs.

Millions of Macs would eventually be sold. The GUI and multimedia functionality had become mass-market innovations. In 1985, Microsoft announced Windows 1.0, a

graphical user interface added to the DOS operating system. The release of Windows led to an extended legal controversy between Apple and Microsoft, with Apple alleging infringement of its rights to the GUI. Apple would ultimately fail to prevent the proliferation of the Windows operating system, ironically fulfilling Jobs's own ambitions for the Macintosh:

Macintosh was basically this relatively small company . . . taking on the goliath, IBM, and saying "Wait a minute, your way is wrong . . . and we are going to show you the right way to do it and here it is. It's called Macintosh and it is so much better. It is going to beat you and you're going to do it." (Jobs 1995)

And so they did. Today we need no longer speak of "multimedia computers" for the simple reason that computing routinely incorporates all media.

Tim Berners-Lee: From Hypertext to the World Wide Web

In the 1980s, the British engineer **Tim Berners-Lee** began actively exploring the practical application of hypertext and hypermedia. Berners-Lee worked at CERN, the European particle physics laboratory at Geneva, Switzerland. CERN, like most large organizations, was structured hierarchically, but it actually functioned, as Berners-Lee saw it, as "a multiply connected 'web' whose interconnections evolve with time" (Packer and Jordan 2001, 192). Communication crossed departments and the most productive thinking often occurred in informal settings such as hallways. This fluid structure, with its unconstrained flow of information among researchers, was an important source of the creative environment of the lab. When combined with a high turnover rate, however, it could also be a source of frustration—information was sometimes lost and only recovered "after a detective investigation in an emergency" (192).

Berners-Lee noted that the needed information often existed; it simply could not be located. Like Bush and Nelson before him, he was struck by the inadequacy of conventional modes of storing and accessing information. Hierarchical patterns, such as tree structures, simply could not accommodate the multiple interconnections that often accompanied the lab's research findings. A new structure was required, one that would "not place its own restraints on the information" (193).

The solution he proposed was a "'web' of notes with links (like references) between them" (193). The items to be linked he termed *nodes*. Nodes could be virtually anything: any form of text, graphics, or other media. Borrowing a term from Ted Nelson, Berners-Lee spoke of his proposed system as hypermedia.

In the late 1980s, various commercial products, such as HyperCard by Apple, made it possible to create hypermedia applications on individual computers (Figure 1.6). Berners-Lee had broader objectives in mind, however. The first of these was "remote access across networks"—hypermedia resources should be broadly distributed. Since different systems were used on the network at CERN (Unix, Macintosh, etc.), "heterogeneity" was another requirement: the same hypermedia resources should be accessible regardless of computer platform. "Private links" were another specification: "One must be able to add one's own private links to and from public information. One must also be able to annotate links, as well as nodes, privately" (Berners-Lee 2001, 198–199). Finally, in keeping with his conception of a flexible web of information, Berners-Lee insisted upon "non-centralization." "Information systems," he insisted, "start small and grow. They also start isolated

and then merge. A new system must allow existing systems to be linked together without requiring any central control or coordination” (198).




Figure 1.6 HyperCard.

Berners-Lee had identified the essential conditions for the emergence of a revolutionary form of information system—a system accessible from any computer, anywhere; a system to which anyone could add information at any time; a system that could incorporate and interrelate multiple media; and a system that could take on a life of its own, developing organically without any central guidance or control exercised over servers, documents, or links.

With the response at CERN less than enthusiastic, Berners-Lee developed the essential elements of what would become the World Wide Web on his own. In 1990, he developed the software needed for *servers* (the computers that

store and distribute information). He also created the first *browser* programs to be used on the individual machines connected to the server (*clients*). In the following year, he began distributing his software to scientists over the Internet. These first programs were written for a specific computer called the Next. This was the machine used by Berners-Lee and many of his colleagues at CERN. In 1993, graduate students at the University of Illinois developed Mosaic, a version of the browser for use on the Macintosh and the PC. Mosaic opened the Web to millions of computer users the world over. The explosive growth of the Web was underway.

The Web made a dramatic contribution to the development of multimedia computing. In the 1980s, the arrival of CD-ROMs had offered the first practical solution to the problem of storing and delivering large multimedia files. CD-ROMs could hold the information of hundreds of floppy disks. They could be reproduced inexpensively and shipped easily. They were limited, however, in two critical respects—they were expensive to master and they needed to be formatted differently for different computer platforms. The Web immediately addressed the issue of cross-platform compatibility; all computers connected to the network could (with appropriate software) read the same information. It also dealt with expense, as multimedia websites could be inexpensively created and distributed nearly instantaneously.

Multimedia computing soon became a worldwide phenomenon with endless possibilities.

1.4 Legacy of the Multimedia Pioneers

The multimedia revolution was born in Bush’s recognition that something was bound to come of the dramatic technical innovations of the 20th century. Microfilm, magnetic storage, vacuum tubes, and transistors would lead to new tools that would transform

our understanding of the world. His Memex promised to both empower and change us, altering what we could do, and how we think.

Bush also understood that the tools that shape understanding could, in turn, be shaped by understanding. His enduring legacy is the inspiration he provided to others to actively design new technologies to meet human needs and interests.

The machine that would eventually make Bush's vision possible was the digital computer. In Alan Turing's pioneering theoretical work, the defining feature of this fundamentally new kind of device was made clear—the computer was a *universal* machine. This meant, among other things, that the computer was a device of unprecedented flexibility.

Douglas Engelbart used this flexibility to develop novel forms of human–computer interactivity. His mouse, windows, and electronic mail made computers more accessible and useful, furthering his goal of “augmenting human intellect” and improving communication. Drawing on Engelbart's vision, Alan Kay developed the GUI and the first multimedia computer. Steve Jobs and Apple Computer made Kay's vision a practical reality by creating the Macintosh.

Theodore Nelson further developed Bush's early vision of associational indexing in the form of hypertext and hypermedia. Nelson's work was, in turn, given powerful expression in Tim Berners-Lee's development of the foundations for the World Wide Web.

1.5 Multimedia Today

Many elements of the visionary proposals of Bush and his successors, such as links, associational searches, mice, and GUIs, are now practical realities. Today's multimedia revolution takes these developments even further, transforming all forms of communication. In Bush's vision the elements of scientific knowledge could be linked and shared; in the multimedia communications revolution individuals are linked and multiple media become tools of individual expression. Social media—Facebook, Twitter, YouTube, and others—allow instant sharing of words, photos, and videos. Powerful, easy-to-use editing software makes it possible for virtually anyone to create new combinations of pre-existing songs, photos, and videos. The resulting **mashups** expand the possibilities of creative expression while also challenging traditional copyright protections.

These are dramatic, far-reaching developments, but the revolution that the multimedia pioneers foresaw is far from complete. They knew that human ingenuity could actively shape an emerging technology. They glimpsed new possibilities as they considered the fundamental properties of computers, information, and people and they developed machines and systems to match this potential. As they well understood, however, a universal machine has unlimited possibilities, possibilities to be further defined by a new generation of multimedia innovators. Perhaps their greatest legacy is the inspiration they provide to continue the “imagineering.” There are also specific reasons, inherent in contemporary social and technological changes, to anticipate a further development of the potential of digital multimedia. These include:

- A continuing technical revolution in hardware and software. Refinements in existing technologies and the development of new modes of computing will continue to increase computing power while lowering costs. Greater computing power will continue to spread to an ever-wider array of users.

- Continued integration of computers in other devices. “Smart” products of all kinds will lead to refinements in sensors and processing that will improve our understanding and control of existing media and lead to the creation of others. Multimedia will include new interactive possibilities with text, images, video, and animation and with the devices that produce them. New possibilities, including smell and tactile experience, will be added to the multimedia experience.
- The “digital merger” of disparate technologies and industries. The merger of film, television, radio, telephone, and the Internet is driving a growing appetite for multimedia communication. No longer is a phone simply an instrument for conveying sound; no longer is catalog shopping a simple engagement with a printed page. As technologies and industries are joined, they generate a corresponding merger and integration of media.
- Further development of wireless communications. As wireless networks become more powerful and more widely available, the use of mobile multimedia devices will increase. This in turn will generate an expanding market for multimedia “apps” of all types.
- The expansion of creative opportunity. The most important source of the continuing revolution in multimedia is the creative potential generated by the worldwide distribution of computing power to an ever-wider array of individuals. The great revolutions of the past developed in circumstances that created a synergy of disparate visions and experiences. Digital communications have dramatically increased both the speed and the reach of interpersonal contact across all cultures, while simultaneously providing a common tool of virtually unlimited flexibility.

In the following chapters, we will explore the fundamental concepts and the practical tools needed to participate in the ongoing magic of the multimedia revolution. As we use those tools, we should remember the dreams of those who helped to shape them. We, too, have the power to shape tools to our purposes, to improve traditional modes of communication, and to create entirely new ones.

Key Terms

Adaptive multimedia
 Alan Kay
 Alan Turing
 Artificial Intelligence
 Basic interactivity
 Douglas Engelbart
 Dynabook
 Expert systems
 GUI
 Hypermedia
 Hypertext
 Immersive multimedia

Intellimedia
 Interactive multimedia
 Mashup
 Memex
 Metamedium
 Modeless
 Multimedia
 Noninteractive multimedia
 Steve Jobs
 Ted Nelson
 Tim Berners-Lee
 Trails

Turing test
 Universal Turing machine
 Vannevar Bush

Virtual reality
 Xanadu

References

- Berners-Lee, Tim. 2001. Information management: A proposal. In *Multimedia*, edited by Randall Packer and Ken Jordan. New York: W. W. Norton.
- Bush, Vannevar. 1991. As we may think. In *From Memex to hypertext*, edited by James Nyce and Paul Kahn. Boston: Academic Press. First published in *Atlantic Monthly* (1945) 176(1):641–649.
- . 1991. Memex II. In *From Memex to hypertext*, edited by James Nyce and Paul Kahn. Boston: Academic Press.
- Engelbart, Douglas. 2001. Augmenting human intellect: A conceptual approach. In *Multimedia*, edited by Randall Packer and Ken Jordan. New York: W. W. Norton.
- Jobs, Steve. 1995. Interview by Daniel Morrow, April 20. <http://americanhistory.si.edu/collections/comphist/sj1.html>
- Kay, Alan. 2001. User interface: A personal view. In *Multimedia*, edited by Randall Packer and Ken Jordan. New York: W. W. Norton.
- Kay, Alan, and Adele Goldberg. 2003. Personal dynamic media. In *The new media reader*, edited by Noah Wardrip-Friun and Nick Montfort. Boston: MIT Press.
- Nelson, T. 2001. Computer lib/Dream machines. In *Multimedia*, edited by Randall Packer and Ken Jordan. New York: W. W. Norton.
- Packer, Randall, and Ken Jordan. 2001. *Multimedia*. New York: W. W. Norton.
- Turing, Alan. 1936. On computable numbers, with an application to the Entscheidungsproblem. *Proceedings of the London Mathematical Society* 2, 42:230–265.

Review Questions

1. What is contemporary multimedia?
2. Why are media professionals building their careers with digital technology?
3. What is the essential difference between interactive and noninteractive multimedia? Give an example of each type.
4. Why is hypermedia a more advanced form of interactive multimedia?
5. What are two features of adaptive multimedia?
6. Why is virtual reality called immersive multimedia?
7. Why is multimedia interdisciplinary?
8. Why did Bush propose his Memex I and II?
9. What are the distinctive features of Memex I and II?
10. How is the simple Turing machine different from a universal Turing machine?
11. What did Theodore Nelson hope to achieve with his Xanadu proposal?
12. What did Alan Kay mean by “personal computer”?
13. Why was the Macintosh a turning point in multimedia computing?
14. Why was Tim Berners-Lee’s development of the World Wide Web significant in the evolution of multimedia?
15. Why is “imagineering” significant to multimedia?

Discussion Questions

1. What is a revolution? In what ways has computing generated a multimedia revolution?
2. In what ways is multimedia central to the theoretical design of Vannevar Bush's Memex systems?
3. Discuss the relevance of Turing's universal machine to the future of multimedia technology.
4. Explain the significance of the Turing test.
5. Explain the similarities among Bush, Nelson, and Lee in their approaches to managing information.
6. Identify the pioneers in multimedia computing and list the main contributions of each.
7. Compare and contrast the visions of the multimedia pioneers and the realities of multimedia computing today. Which of their dreams has been realized? Which remain unfulfilled? Which aspects of modern multimedia did they fail to anticipate?
8. Research current developments in virtual reality or video games and report how they are extending the potential of multimedia.

Chapter 2

Digital Data



Topics you will explore include:

- Elements of Digital Media
 - Symbol
 - Data
 - Information
- Digital Codes
 - Bits
 - Bytes
 - Effective and Efficient Codes
- Files
 - Size
 - Format
 - Compatibility and Conversion
 - Maintenance
- Digitization
 - Sampling
 - Quantization
 - Sample Resolution
 - Sample Rate
- File Compression
- Advantages of Digital Information
- Challenges of Digital Information

The language of modern multimedia is digital. Most multimedia products—presentations, websites, tutorials, games, and films—are created and delivered using digital computers. Multimedia developers encounter a varied, and constantly changing, array of digital codes—ASCII, RTF, TIFF, JPEG, PDF, MP3, MOV, and so on. Understanding their nature, purposes, advantages, and limitations is essential for effective work in all areas of digital media.

This chapter presents the elements of digital encoding and explores the basic techniques and issues common to the digital representation of various media. After completing this chapter you should understand:

- Relationships among *symbol*, *data*, and *information*
- Main differences between analog and digital data
- Use of bits to encode digital data and the meaning of effective and efficient codes
- Essentials of files—formats, compression, and conversion
- Digitization—sampling, quantization, sample resolution, and sample rate
- Description-based and command-based media
- Key advantages and challenges of digital information

2.1 Symbols, Data, and Information

Multimedia applications include many different types of information. Information begins with data, and data is encoded using symbols.

Symbols are representations, or “stand-ins,” for something else. Groups of letters often serve as symbols of words, as they do on this page. What letters and other symbols represent is determined by the **convention** that governs their use. The convention of *roman numerals*, for example, uses letters to represent numbers rather than words—IX stands for 9. Agreed upon conventions facilitate communication by defining the meaning and use of symbols.

Symbols organized and understood according to a convention are used to represent data. **Data** are the givens of experience—measurements, observations, facts, beliefs, and the like. A listing of 24 numbers (30.12, 30.05, 29.99, etc.) summarizing hourly barometric pressure readings is data.

This listing of data is not yet information. **Information** is data made useful, data interpreted and applied to produce understanding. The amount of information conveyed through data is dependent on the knowledge of the recipient. The casual observer may see the numbers above and understand that the barometric pressure is dropping. The meteorologist prepares for the approaching storm. Multimedia developers carefully consider the knowledge and skills of their intended audiences. Only in this way can they ensure that the data presented in their applications will become meaningful information.

Data: Digital and Analog

Data is either digital or analog. **Digital data** consists of separate, discrete units. A digital clock presents the time as a sequence of distinct numbers. **Analog data** varies continu-

ously. An analog clock presents time through the continuous movements of its hands (Figure 2.1).

Traditionally, images and sounds were created and delivered in analog form. Paintings and photographs were composed of continuous areas of color, and music was produced through analog motions of strings, reeds, and other devices. But analog media cannot be directly created, edited, or distributed by a digital computer. To take advantage of the power of the computer, multimedia data must be digital.



Figure 2.1 Data—analog and digital.

2.2 Digital Data: Bits, Bytes, and Codes

Digital information starts with digital data, and digital data starts with digits. A *digit* can be any one of the 10 symbols, 0–9. Most people are very familiar with this “base-10” system—it’s the one they use in their everyday lives. Some of the first digital computers also made use of all 10 digital symbols.

Modern computers are electronic and many of their components (such as transistors) are especially well suited to represent one of two different states (high/low voltage, magnetized/nonmagnetized, etc.). As a result, the “language” of these machines uses only 2 of the 10 available digits: 0 and 1. The symbols 0 and 1 are the two elements of a *binary* system (“binary” means having two parts). Each is a *binary digit* or, for short, a **bit**.

Bits are the symbols used to encode modern digital data. **Digital encoding** is the process of assigning bits to a data item. The number of bits a coding system requires depends upon the number of distinct data items to be represented. Each item must be given a unique symbolic representation, that is, a unique arrangement of bits. More bits make it possible to generate a larger number of distinct combinations.

If only two data items need to be encoded, such as a “yes” or “no,” a single bit suffices. The bit can take on one of two values and a convention could be adopted in which a 1 designates “yes” and a 0 designates “no.” One-bit encoding has obvious limitations. For instance, a 1-bit digital code for temperature could only represent two readings of a thermometer. 0 might stand for a temperature of 0 degrees Celsius, and 1 might designate 100 degrees Celsius. This coding scheme could then alert us to the likely freezing or boiling of water, but it could not tell us anything about other temperatures.

Adding another bit to the code produces four distinct combinations: 11, 10, 01, and 00. These combinations still employ just the two symbols, 0 and 1, but now more than one symbol is used to represent the data item. Using a 2-bit code, the four possibilities A, B, C, or D for a multiple-choice question could now be represented. But a 2-bit coding system would still be inadequate for most uses of temperature readings. Just four temperatures, for example 0, 33, 67, and 100 degrees Celsius, could now be represented—still not enough to allow us to choose between a t-shirt and a parka as we leave for work in the morning.

A 3-bit code produces eight distinct 3-bit combinations: 111, 110, 101, 100, 011, 010, 001, and 000. In general, the number of distinct bit combinations that can be produced

Four-bit codes are known as “nibbles.”

is given by the formula, 2^n , where n is the number of bits used in the code. A four-bit code can thus represent 2^4 , or 16, distinct data items. Each additional bit adds a power of two and thus doubles the number of unique encodings.

Eight-bit codes allow for 256 distinct data items (2^8). This is more than adequate to represent the variety of symbols in most uses of the printed English language (the letters of the alphabet, numerals, punctuation marks, mathematical and scientific symbols, etc.). It is also adequate for some uses of sound and graphics (256 different amplitude values for sound samples or 256 colors in pictures). Computers also usually process data either in 8-bit format or in a format that is a multiple of 8 bits, for example 16, 32, or 64 bits. This 8-bit unit is so commonly used in computing that it has a name of its own—a **byte**.

Effective and Efficient Codes

An **effective code** is one that can represent each desired data item with a unique combination of symbols. The days of the week can be effectively encoded using 3 bits; the 12 months of the year would require 4.

In addition to effectively identifying individual data items with unique codes, a coding scheme should also be efficient. An **efficient code** is one that does not waste processing, storage, or transmission resources. Longer encodings use more bits and consume more processing time, storage space, and transmission bandwidth. Efficient codes conserve these resources. For example, if the goal is to represent each degree of temperature between the freezing and the boiling point of water on a Celsius scale (0–100 degrees), 6-bit codes are not enough (64 possibilities) and 8-bit codes are too much (256 possibilities). 7-bit codes (128 possibilities) provide the closest match and the most efficient encoding.

A basic concern in all multimedia development is ensuring that the digital encoding being used can effectively and efficiently represent the required range of media data. As the range or quality of media expands, developers often need to adopt more flexible coding options. For example, the original formulation of the text code known as **ASCII** (American Standard Code for Information Interchange) used just 7 bits. This was adequate for the representation of the letters, numbers, and other symbols used in computer-generated text at the time. Later, the eighth bit was added to double the number of available codes. In this new character set, called **extended ASCII** or **ASCII-8**, more specialized symbols, such as Greek letters and logical operators, could also be represented (Figure 2.2). **Unicode**, a later standard, uses 16-bit codes to effectively designate over 65,000 individual characters. This supports the digital encoding of many more written symbols and a wide range of languages.

Character	ASCII-8
0	0011 0000
1	0011 0001
2	0011 0010
3	0011 0011
4	0011 0100
5	0011 0101
6	0011 0110
7	0011 0111
8	0011 1000
9	0011 1001
A	0100 0001
B	0100 0010
C	0100 0011
D	0100 0100
E	0100 0101
F	0100 0110
G	0100 0111
H	0100 1000
I	0100 1001
J	0100 1010
K	0100 1011
L	0100 1100
M	0100 1101
N	0100 1110
O	0100 1111
P	0101 0000
Q	0101 0001
R	0101 0010
S	0101 0011
T	0101 0100
U	0101 0101
V	0101 0110
W	0101 0111
X	0101 1000
Y	0101 1001
Z	0101 1010
a	0110 0001
b	0110 0010
c	0110 0011
d	0110 0100
e	0110 0101
f	0110 0110
g	0110 0111
h	0110 1000
i	0110 1001
j	0110 1010
k	0110 1011
l	0110 1100
m	0110 1101
n	0110 1110
o	0110 1111
p	0111 0000
q	0111 0001
r	0111 0010
s	0111 0011
t	0111 0100
u	0111 0101
v	0111 0110
w	0111 0111
x	0111 1000
y	0111 1001
z	0111 1010

Figure 2.2 ASCII codes.

2.3 Digital Files

A computer **file** is a container for binary code, which is the universal language of a computer. Everything a computer does, from startup to shutdown, must ultimately be represented as 0s and 1s. This includes the instructions, or programs, a computer follows to carry out its operations as well as the data it processes. A **file format** is the convention that specifies how instructions and data are encoded in a computer file. Without a specific file format, a binary code has no meaning.

File Sizes

The size of a file is usually measured in numbers of bytes. The term *kilo* designates one thousand in the metric system. Because computers use a binary system, storage capacities are given as powers of two. In computer parlance, a kilo represents 2^{10} or 1024—in other words, *approximately* 1000. A **kilobyte** (KB) is thus 1024 bytes. Similarly *mega* designates one million. When applied to computer codes, *mega* stands for 2^{20} or 1,048,576. A **megabyte** (MB) is 1,048,576 bytes or *approximately* a million bytes. Similarly a **gigabyte** (GB) is approximately one billion bytes and a **terabyte** (TB) is approximately one trillion bytes.

File Extensions

A **file extension** is a series of letters that designate a file type. File extensions follow a dot at the end of a file name and are usually limited to two to four letters. For instance, a file with the extension *.ai* is an Adobe Illustrator file, *.exe* is a Windows program file, *.docx* is a Microsoft Word document, and *.html* is a web document. There are hundreds of extensions. Some of the more important ones for multimedia developers are listed in the text box on this page and discussed in later chapters.

Extensions are important for multimedia developers for two main reasons. First, they immediately identify a file type and, often, even the program that created the file. This greatly simplifies the challenge of keeping track of the many media files and programs that make up a multimedia application. Second, file extensions are often used by a computer's operating system to identify and launch an appropriate program to open the file. A developer can simply double-click a file's icon and begin working on it. Removing the extension may require the user to identify a compatible application before the file can be opened. Given these advantages, it is good practice to maintain the extension when naming or renaming files.

File Compatibility

Although nearly all digital computers use binary codes, they do not necessarily use the same codes. Different computer systems, or **platforms**, use different hardware and

Bytes and Bits

KB and Kb are not the same. KB is the abbreviation for kilobytes. Kb stands for kilobits. Similarly, Mb, Gb, and Tb are references to bits, not bytes. These bit measures are often used to describe electronic transfer rates, for example a 56 Kbps (kilobits per second) modem or an 800 Mbps (megabits per second) FireWire interface.

Common Multimedia File Extensions

- .ai – Adobe Illustrator graphic
- .avi – Windows video
- .bmp – BMP graphic
- .docx – Word document
- .gif – GIF graphic
- .htm or .html – Hypertext Markup Language
- .jpg – JPEG graphic
- .mov – QuickTime video
- .pct – PCT graphic
- .pdf – Portable Document Format
- .png – PNG graphic
- .psd – Photoshop image
- .txt – ASCII text
- .wav – Windows audio

software (see Chapters 3 and 4). As a result, a file that can be read and processed on one computer platform, such as a Windows PC, often cannot be used on another, such as a Macintosh. In addition, there are many variations in data file formats both within and between platforms. One of the most important concerns for multimedia developers is **file compatibility**, ensuring that a computer can process the instructions or data that are encoded in a particular file format.

Program files give the computer its instructions. They include operating systems (Windows, OS X), programming languages (Java, C++), and applications (Word, Excel, Photoshop). Programs are developed for specific computer platforms and are generally not compatible with other platforms. Multimedia developers often use more than one computer platform (generally PCs or Macs). The first compatibility issue is whether or not the program they would like to use is compatible with the intended platform. Widely used applications such as Word or Photoshop are usually available for PCs or Macs but the developer will have to own separate copies for each platform.

Multimedia **data files**—text, images, sounds, video, and animations—pose two principal compatibility challenges. The first is whether or not the file format is *cross-platform compatible*. A format that is not cross-platform compatible cannot be used on other platforms. For instance, Microsoft developed the BMP image format and Apple developed PICT. These two formats are not cross-platform compatible and a developer would not use PICT images in an application destined for a Windows PC. Instead, the PICT image would be converted to a Windows format or to a format that can be used by both platforms, such as TIFF.

The second compatibility issue for multimedia data is whether or not different application programs *on a given platform* can process the format. Multimedia developers create or edit the various elements of their applications in *media-specific software*, such as word processors, graphics programs, or video-editing applications. In some cases, developers will work with different programs to create a particular media component. For instance, they may work with an image in a photo-editing application and then add special effects using another program. The various media elements a developer creates or imports are then combined using *authoring software* (see Chapter 10). Throughout the

process it is important to ensure that the files to be used are compatible with the media-specific and authoring applications that will be used. For example, some image formats, such as TIFF, can be used by most image-editing applications and are also widely compatible with authoring software. Newer formats and those intended for specialized purposes may not be widely supported—it took time, for instance, for PNG, a rival to the GIF image format, to be supported by most image-editing programs.

Native file formats are an important example of specialized files. These are coding conventions used by specific computer applications, such as Adobe Photoshop or Corel Painter. Native formats contain information specific to the application that created them. For instance, a file in Photoshop's native format (PSD)

may contain information about filters and other effects applied to the image during editing. In general, native file formats are not compatible with other applications.

File Format Checklist for Multimedia Development

- Is the format compatible with:
 - the operating system of the development platform?
 - the operating system of the delivery platform?
 - the developer's media-specific software?
 - the developer's authoring software?
- Is a file conversion utility available to produce a compatible file?
- Have copies of original files of all media elements been saved?

File Conversion

Problems with file compatibility can often be resolved through **file conversion**, the process of transforming one file type to another.

File conversion can be carried out by specialized applications, such as the Equilibrium DeBabelizer. It is also often possible to perform conversions using the “Save As” function in popular media-specific software. For example, a TIFF image captured by a scanner can be opened in Photoshop and readily saved as a JPEG image for use on the Web.

File Maintenance

The variety of formats that may be required to develop and deliver a multimedia application also makes it important to carefully preserve both original and derivative files. Good file maintenance can save time when applications need to be revised or updated. In addition, information is often lost or modified in file conversion. Preserving the original may be critical if the application needs revision or if high-quality copies are required for future projects.

Effective file maintenance involves three major steps: identification, categorization, and preservation. Files should be clearly *identified* in terms of their specific contents, their general type, and/or their originating program. Contents should be identified by file names that clearly differentiate each item: *LargeLogo*, *OctSalePrices*, *MouseClickSound*. Much uncertainty and frustration in developing and revising applications can be avoided by creating meaningful file names. Standard extensions, as discussed previously, identify file types or originating programs and should always be retained in file names: *LargeLogo.gif*, *OctSalePrices.doc*, *MouseClickSound.aif*.

Categorization is the process of meaningfully grouping related files. Electronic folders serve the same general functions as their paper counterparts. Files are more readily located when grouped as images, text documents, video clips, and so on. More specific categorization is often essential in multimedia development and may have the further benefit of indicating an application’s overall structure: *JuneSalesImages*, *LessonOneAnswers*, *CellDivisionAnimations*. And of course we shouldn’t omit another important category: *PhotoOriginals*, *SoundOriginals*, *SourceVideo*.

Finally, file *preservation* includes the preparation and storage of backup copies as well as their distribution to individuals or departments that may need them for future work. Key considerations include the durability and the accessibility of the storage medium and ensuring that important files have been stored in more than one location.

2.4 Digitization

Multimedia developers work with a wide range of media, each of which is usually best handled in a digital format. Letters and numbers are discrete units. As such, they are readily represented in digital codes: a convention simply identifies particular letters or numbers with particular codes. These codes fully represent the letter or number. For example, the ASCII code 01001110 01001111 represents the letters *N* and *O* with complete accuracy.

Other data—still or moving images, and sounds—are often presented as continuous, or analog, phenomena. To take full advantage of the power of the computer, analog data must be transformed. **Digitization** is the process of converting analog data to a digital format through a process called *sampling*.

Sampling

Sampling is the process of analyzing a small element of an image or sound and representing that element in a digital code. Thousands of individual samples are usually collected. They are then combined to re-create the original analog data in a digital format.




Figure 2.3 Sampling produces a digital version of an analog sound.

To digitize analog sound, thousands of samples of the varying amplitudes of the sound are collected each second. Each sample is assigned a binary code indicating its amplitude at that instant. The computer processes these values to re-create the sound from the individual samples (Figure 2.3). Analog images, such as photographs, are digitized by sampling their color at many different points.

The re-created image is a grid of picture elements, or *pixels*, each having a particular color. If the grid is fine enough, the pixels blend together, producing the appearance of continuous areas of color (Figure 2.4).

Sampling can produce excellent digital reproductions of analog sources but it also often produces very large files. Multimedia developers must constantly balance media



Figure 2.4 Image sampling produces a grid of pixels. This section of the deer’s eye is enlarged 1200%. See Color Plate 1.

quality with the demands of effective and efficient delivery of their products. The two most important factors governing the quality of sampled media are *sample resolution* and *sample rate*. Sample resolution is directly related to another important issue in digital media production, *quantization*.

Sample Resolution and Quantization

Sample resolution is the number of bits used to represent a digital sample. For example, an 8-bit sample resolution assigns 8 bits to each sample, permitting any one of 256 possible colors to be represented. Sample resolution is often described as *bit depth*. **Quantization** is the process of rounding off the value of a sample to the closest available value in the digital code being used.

All sampling involves some degree of quantization. This is because analog phenomena are continuous and sampling always produces a series of discrete values. Because time and space are infinitely divisible, no finite recording of samples can capture all the information in an analog source: all samples are, in effect, “rounded off.” On the other hand, high-quality digital sampling can create virtually indistinguishable digital versions of analog media. Quantization only becomes a problem when sample resolution is too low. For example, photographs often contain thousands of shades of color. As sample resolution is reduced, fewer bits are available for coding and fewer colors can be represented. Some color samples must then be quantized—matched to the closest available substitute. If too few colors are available, much of the original image data may be lost. For example, a light pink and a burgundy might both be represented as the closest available match, a bright red. Figure 2.5 is an extreme example of quantization. Reducing the sample resolution from 24-bits to 2-bits reduces the range of individual colors from



Figure 2.5 Quantization: 24-bit v. 2-bit sample resolution. See Color Plate 2.

millions to just four. Browns and greens must be quantized to gray or black. Gone, too, are the various shades of blue in the sky.

Using codes with more bits—that is, increasing the sample resolution—counters the effects of quantization. The 16.7 million distinct encodings of 24-bit sample resolution make it possible to assign a different code to every shade of color humans can distinguish. This produces images that rival the quality of 35mm analog photos.

Sample Rate

The second major factor determining the quality of digital images and sounds is sample rate. **Sample rate** is the number of samples taken in a given unit of time (sounds) or space (images). In the case of sound, the rate is given in kilohertz, thousands of samples per second. Sample rates for images are defined spatially and are referred to as **spatial resolution**. Spatial resolution typically varies from 72 to several thousand pixels per inch.



Figure 2.6 Spatial resolution: 300 ppi (left) v. 50 ppi (right). See Color Plate 3.

Low sample rates reduce the quality of digital images and sounds because they omit original analog information. For example, the frequency of a sound is determined by the rate at which its waveform repeats its highest and lowest amplitudes. If too few amplitude samples are taken, high-frequency information will be omitted, producing a “flattened,” lower-pitch version of the original. For images, a lower number of samples will miss details such as fine gradations of lines, often producing an incomplete, “fuzzy” reproduction (Figure 2.6).

2.5 Digital Encoding of Media

All digital media, whether converted from analog formats or originally produced in digital form, must be represented in binary code. There are two major approaches to digitally encoding media: **description-based** and **command-based**. In the descriptive approach, a digital media file contains a detailed representation of the many discrete elements that compose the image or sound. An image is described by recording the colors of each of its many individual pixels, thus creating a grid or “map” of their locations. This type of digital encoding is therefore often called a **bitmapped image**. Sound is described through thousands of individual amplitude samples and is known as **sampled sound**.

Descriptive digital encoding takes advantage of the computer’s ability to store and process very large numbers of discrete media elements. Although descriptive encoding usually results in larger file sizes, it is often the preferred method for representing natural scenes and sounds. It also supports very detailed editing. Bitmapped images and sampled sound are the most common examples of descriptive encoding.

The second approach to encoding digital media takes advantage of another property of computers—their ability to execute commands. Rather than storing a detailed listing of constituent elements, the command approach stores a set of instructions that the

computer then follows to produce digital images and sounds. These instructions, like all aspects of digital computing, are encoded as bits and bytes.

Sounds can be encoded as commands by specifying musical actions, such as striking a particular organ key with a certain force and duration. This is the approach used in the popular MIDI format (Musical Instrument Digital Interface; see Chapter 7). A MIDI file stores the commands used to produce sounds, rather than the sounds themselves. As the computer executes the commands, specialized software and hardware (*sequencers* and *synthesizers*) produce the corresponding sounds. Command-based sound is usually described as *synthesized sound*, sound “put together” by the computer. Similarly, digital images can be encoded as drawing commands. For example, commands might specify that a hexagon be drawn at a particular screen location, using one color for a border and another for its fill (see Chapter 6). *Draw programs*, such as Adobe Illustrator, produce images using the command-based approach.

Command-based media have important advantages over their descriptive counterparts. File sizes are usually much smaller, making them particularly useful in applications with limited bandwidth, as is often the case on the Web. They can also be scaled without introducing distortion, unlike most descriptive media. For instance, the size of an image can be increased without introducing “jaggies,” the “stair-step” effect especially evident on diagonal lines when bitmapped images are enlarged. Similarly, the length of a synthesized sound can be changed without affecting pitch. On the other hand, it is usually more difficult to produce complex, natural media using the command approach. Photographs, or the human voice, for example, are usually more effectively encoded descriptively.

The distinctions between descriptions and commands for encoding digital media will recur throughout our consideration of the various media included in modern multimedia applications.

Macromedia Flash, a popular authoring application for the Web, uses command-based graphics to lower file sizes and speed the delivery of animations.

2.6 File Compression

A digital file can easily become very large. This is particularly true when the file involves description-based graphics, sound, and video. An 800 × 600 computer monitor displays 480,000 picture elements. At photo-quality resolution, each of these is represented with 24 bits. This requires the computer to store, read, and process over eleven million bits, or approximately 1.4 megabytes, of information. A video presents 30 of these images every second and adds sound as well. At well over 30 megabytes per second, this stream of digital data would quickly overwhelm the memory and processing capabilities of most personal computers.

Fortunately, the size of digital files can be significantly reduced by file compression. **Compression** is the process of re-encoding digital data to reduce file size. A specialized program called a **codec** (for COmpressor/DECompressor) changes the original file to the smaller version and then decompresses it to again present the data in a usable form. A basic understanding of compression is particularly important in multimedia development for two reasons. First, compression is one of the major strategies developers use to

StuffIt, WinZip, PKZIP are common compression utilities.

reduce file sizes. Reducing file size leads to more efficient multimedia applications and is often essential for effective delivery on the Web. Second, the choice of a particular form of compression can dramatically affect media quality, and the range of compression choices is large and constantly evolving. Developers need to understand the fundamentals of compression to select the most appropriate option.

There are two major types of compression: *lossy* and *lossless*. In **lossy compression**, the number of bits in the original file is reduced and some data is lost. Lossy compression is not an option for files consisting of text and numbers, so-called *alphanumeric* information. Losing a single letter or number could easily alter the meaning of the data. However, it is often possible to maintain high-quality images or sounds with less data than was originally present. **Lossless compression** substitutes a more efficient encoding to reduce the file size while preserving all of the original data. When the file is decompressed it will be identical to the original. Two examples can help to clarify the nature of compression generally and, especially, the differences between lossy and lossless techniques.

Lossy Compression—MP3

MP3 and Portable Music

MP3 also helped revolutionize portable music players. One megabyte can hold approximately one minute of MP3 sound. This allows iPods and other MP3 players to store hundreds of songs.

MP3 is a sound file format that incorporates lossy compression. It is part of a much broader set of compression standards established by the Motion Picture Experts Group (MPEG). MP3 (for MPEG1, audio level 3) achieved its initial popularity because it made it possible to transmit near CD-quality sound files over the Web. Without compression, the transmission of an original CD file is not practical for most web users. The CD-Audio standard uses

16-bit samples of the original music taken 44,100 times per second for each of two stereo channels. This results in files that contain 1,411,200 bits of information for each second of sound (44,100 samples \times 16 bits per sample \times 2 channels). A 56 Kb modem would take approximately 25 seconds to receive this single second of sound (1,411,200 bits / 56,000 bits/second). At this data-transfer rate, a 3-minute song takes more than an hour to download. MP3 files compress this information, producing a file that is approximately 12 times smaller than the original. A modem could then download the compressed file in a few minutes. While today's broadband connections have dramatically increased download speeds for most users, MP3 remains an important, widely used format.

MP3 analyzes the sound file and discards data that is not critical for high-quality playback. For example, it removes frequencies above the range of human hearing. It may also evaluate two sounds playing at the same time and eliminate the softer sound. These types of data can be eliminated without significant impact on quality. The result is a lossy compression, because some information is discarded, but one that maintains near CD-quality performance.

Lossless Compression—Run Length Encoding

One of the simpler strategies to achieve lossless compression is run length encoding (**RLE**). Run length encoding is sometimes used to compress bitmapped image files, such as the Windows PCX format. As noted previously, bitmapped images can easily become

very large because each pixel is represented with a series of bits that provide information about its color. Run length encoding generates a code to “flag” the beginning of a line of pixels of the same color. That color information is then recorded just once for each pixel. In effect, RLE tells the computer to repeat a color for a given number of adjacent pixels rather than repeating the same information for each pixel over and over. The RLE compressed file will be smaller, but it will retain all the original image data—it is “lossless.”

2.7 Error Detection and Correction

Digital data consists of long strings of 0s and 1s. Changing or eliminating even a few of these bits can produce serious distortions. There are a number of ways in which these distortions can occur. For example, the pits and lands of a CD can be altered by a scratch or dust, or the magnetized surface of a zip disk can be affected by stray magnetism or by heat. Data may also be lost or altered in electronic transmission. For digital data to be reliable, some means of detecting and correcting errors must be found.

There are many strategies for error detection and correction and, like compression, the multimedia developer seldom has occasion to enter very deeply into this specialized area. On the other hand, the storage requirements for data in various formats (such as CD and DVD) are significantly affected by the need to add code for detecting and correcting errors, and it is useful to understand the basics of its operation.

The first challenge in ensuring reliable digital information is to find a means of detecting an error. A simple strategy for doing this is the *parity bit*. A **parity bit** is an extra bit added to a data code to maintain either an even or an odd number of 1s in the code. In this approach, the number of 1 bits in each block of data is counted. An extra bit is then added to make the total number of 1 bits either odd or even. The added bit is called a parity bit. If the number of 1 bits is intended to be odd, the coding scheme is called *odd parity*; even numbers of 1s are *even parity*. For example, the ASCII code for the letter A is 01000001. This code has an even number of 1 bits (two). In an even parity system, the parity bit added would be a 0 and the code for the letter would become 01000001**0**. A letter such as C, with an ASCII code of 01000011, has an odd number of 1 bits (three). In even parity, a 1 would be added, producing a parity bit encoding of 01000011**1**.

On receipt of the data block, the bits are again counted. If the number of bits is not the expected odd or even value (depending on the parity being used), an error must have occurred. This simple system can detect many errors, but it does have serious limitations. More advanced approaches are often used to detect errors. Once the error is detected, the second challenge is to correct it with accurate data bits.

For some applications, such as data transmission, knowing an error occurred may be enough. The data error will generate a request from the receiver to retransmit the flawed data item. The process continues until an error-free message is received. This strategy will not work for all types of digital media, however. For example, accurate playback of audio CDs requires *immediate* detection and correction of data errors. To accomplish this, error correction code is added to reconstruct the original bit sequence. This requires

B	E
0	0
1	1
0	0
0	0
0	0
0	1
1	0
0	1

0 1 ◀ Parity Bits

Even parity means that the number of 1 bits must be an even number. If it is, a 0 is added. If it isn't, a 1 bit is supplementary.

redundant data in the bit stream, which increases data storage requirements. It also dramatically improves reliability. CD-Audio discs devote approximately one-third of their storage to error detection and correction.

2.8 Advantages of Digital Data

A computer is a revolutionary form of machine because in principle it is universal—it can become virtually any kind of information-processing device. By changing the computer's instructions, or program, we can instantly change it from a word processor to a photo editor, to a graphing calculator, to a game station, and so on, indefinitely.

Computers can also control the delivery of analog information. For instance, computers have been used to control tape decks or laserdisc players displaying analog images. But the computer cannot edit those images while in their analog form. The chief advantage of digital information is that it can be directly manipulated and transformed by a computer. This has produced significant improvements in the reproduction, editing, integration, and distribution of a wide range of media.

Reproduction

Digital information can be repeatedly copied with no loss of quality. All of the information in the original file can be preserved in the copy, as well as in copies of the copy, and so on. This is not true for analog formats such as videotapes. A video copy does not preserve all the information of the master, and copies of copies soon produce significant distortions, a process known as **generation decay**. Digital information supports full-fidelity copies with no generation decay.

Editing

One of the earliest examples of the editing advantages of digital information was *word processing*. Once words are represented in a digital code, a computer program such as Word can readily apply changes of font and formatting as well as operations such as searching, replacing, and spell-checking. These advantages soon drove typewriters from the forefront of text preparation.

Similar advantages apply to other media. Analog editing of photos tends to be slow and expensive, requiring specialized equipment and techniques. Once a photo is in digital form, programs such as Adobe Photoshop or Corel PaintShop Pro can be used to instantly change its size, crop it, change its brightness or contrast, add special effects such as 3-D embossing, and so on. Digital information is readily and inexpensively edited.

Integration

By definition, multimedia is focused on the integration of different media. This may be as simple as tying the sound of a babbling brook to the image of a pristine mountain stream, or as complex as relating a control input to changes in the instruments and cockpit view of a flight simulator. This process is greatly simplified when all media are in a common digital format and can be stored and accessed by a single device, a digital computer. It is sometimes suggested that the computer has transformed multimedia into a sort of "unimedia" with digital code as its common language. A sound in this new scheme is still different from a photo, but common tools and techniques based on

digital manipulations can be applied to both. Cut, copy, and paste, for instance, were once restricted to text. With the development of modern multimedia, these are common operations that are conducted in much the same way for all media, allowing them to be readily combined in a single application.

Distribution

Distribution is one of the principal challenges in the evolution of modern multimedia. In the past, analog media such as radio, TV, and print enjoyed considerable advantages over digital multimedia. Their well-developed infrastructures and large customer bases allowed for rapid and widespread distribution of information. With the development and partial standardization of CD-ROMs, distribution of large multimedia files became more practical. The development of the Internet, particularly the World Wide Web, dramatically improved the distribution of digital information.

By the beginning of the 21st century it was evident that the future of all media was digital, and steps were underway to guide massive analog information systems, such as television, into the digital age. The existence of widely accessible digital networks, reaching into virtually every corner of the globe, has produced an information distribution system of unparalleled reach and scope. Not only can nearly everyone be reached, but nearly everyone can be reached by anyone else. The language of this revolutionary medium is digital.

2.9 Digital Challenges

Given these advantages, digital data will continue to displace analog formats. This process does involve significant challenges, however. Among these are file sizes, processing demands, standardization, bandwidth, and preservation. Each challenge will almost certainly be overcome with the further development of digital technology. But each is also a significant concern for today's multimedia developers.

File Sizes

Digitization often produces very large files. This is particularly true of dynamic media, that is, media that changes over time, such as sound or video. A minute of CD-quality sound produces a file of over 10 MB. A minute of uncompressed full-screen, full-fidelity (24-bit) video takes up approximately 1.7 GB. At these sizes, digitized dynamic media soon tax the limits of available storage and processing in most personal computers.

Solutions to the challenge of large file sizes involve improvements in hardware and software. Many of these focus on compressing the original files. MPEG2, for instance, uses compression software in conjunction with specialized hardware to reduce the size of video files. It compresses video at about a 150:1 ratio and still retains excellent quality. Other solutions include hard drives with storage capacities in the hundreds of gigabytes and optical technologies such as DVD. DVD (digital versatile disc) uses an optical disc the same size as a CD-ROM but increases the storage capacity from the CD's 650 MB to a potential 17 GB. An extension of the DVD standard, blu-ray, increased storage to 50 GB per disc based on four layers (see Chapter 3).

Processor Demand

Large digital files also burden a computer's processor (see Chapter 3). Some forms of digitization are particularly processing-intensive. In the final stages of producing a 3-D animation, computers must make many calculations. This process, called *rendering*, may take many hours, or in the case of lengthy and complex presentations, days and weeks, to complete (see Chapter 9). In the case of the 3-D animated film *Avatar*, some individual frames would have required 100 hours of processing time from a single computer. At 24 frames per second, each second of the sequence would require 100 days to render. The producers met the rendering challenge with a "render farm" that combined 40,000 processors in a 10,000-square-foot, water-cooled data center. In the final stages of rendering the processors ran 24 hours a day for over a month.

Standardization

The development of multimedia technology is a competitive process in which different organizations pursue a variety of strategies to develop new software and hardware. As a result, a number of different conventions for encoding and manipulating digital data are created. These are often **incompatible**: data formats that work with one type of hardware or software do not work with others.

The absence of a common standard fragments the multimedia market and discourages the development of new applications. Over time, a combination of market forces and the work of standards committees generally produce a dominant standard. This, in turn, spurs the development of multimedia products and services. In the early stages of CD technology, different computer manufacturers used different standards for encoding data. The development of a common standard (ISO 9660) made it possible for most computers to access the information on any CD, thus encouraging the development of many more multimedia applications.

Bandwidth

Communications networks, especially the World Wide Web and cellular data services, greatly facilitate the distribution of digital multimedia. A basic challenge for network users is bandwidth. **Bandwidth** is the rate at which digital data can be transmitted over a communication medium, or band. For instance, in a basic 56 Kb modem connection, the medium is the twisted-pair copper wire of a telephone line and the data rate is 56 kilobits per second (56 Kbps, note lowercase *b*). Fifty-six kilobits is just 7 bytes, a very slow data rate for large multimedia applications. Improvements that have helped to meet the bandwidth challenge include dedicated digital lines such as T1 (1.54 Mbps), DSL (digital subscriber line, up to 8 Mbps), cable modems (up to 52 Mbps), fiber optics (100 Mbps or more), and wireless networks such as Bluetooth (2 Mbps), Wi-Fi (up to 54 Mbps) and 4G cellular (100 Mbps).

Preservation

As digital media continue to displace their analog counterparts, there is growing concern about the longevity and future accessibility of digital data in all its many forms. Although digital encoding supports much more economical and accessible modes of archiving, serious challenges remain in two key areas: (1) the durability and reliability of long-term

storage media such as digital tape, CDs, and DVDs, and (2) the availability of the hardware and software required to read the archived files. These are serious concerns for individuals and organizations alike. Individual family members may have much less access to the digital photos of earlier generations than their ancestors had to the analog prints preserved in albums in drawers, closets, and attics. Governments, courts, hospitals, law firms, and businesses of all kinds also clearly have a substantial stake in the preservation of digital data.

The challenges of preserving this data are already clear. Digital tapes must be periodically refreshed and the long-term durability of optical formats, especially the recordable and rewritable variants, is not completely known. Other widely used technologies, such as flash drives, are even more susceptible to degradation with repeated use. This is a widely recognized problem and a subject of active research that is likely to produce a better understanding of the prospects for media longevity. On the other hand, each new technology will continue to raise these questions, and concerns about media preservation are likely to continue.

The second major challenge is to also preserve access to, and operability on, archived digital data. For this, appropriate hardware and software are essential. The rapid obsolescence of storage devices, processors, and software, including both applications and operating systems, means that perfectly well-preserved files may no longer be readable. While it may sometimes be possible to preserve older software and hardware in operating condition, far more promising solutions are *migration* and *emulation*. Migration is the process of updating digital data to a form that can be read and manipulated by current hardware and software. In the context of preservation, emulation is the use of a new technology to reproduce the operability of an older one. In effect, new hardware and software mimic the capabilities of their predecessors. Both migration and emulation pose demanding challenges with respect to issues such as file compatibility and maintaining full interoperability, including the original functionality of advanced products such as interactive multimedia applications.

2.10 Summary

Data, or the observations, facts, and beliefs of experience, take two principal forms— analog and digital. Analog data is continuous and, in principle, infinitely divisible. Digital data is discrete—it is made up of indivisible units. Both analog and digital data are composed of symbols, representations whose meanings are determined by conventions.

The symbols used in modern digital data are the binary digits (or bits), *0* and *1*. Eight-bit encodings called bytes are fundamental to computing. The meanings of the strings of bits, or codes, used by computers are determined by conventions such as file formats. Codes are designed to be both effective and efficient. Effective codes successfully represent the desired range of data, while efficient codes conserve valuable computing resources. Effectiveness and efficiency are closely tied to sample resolution, the number of bits used to represent a data item. Every additional bit doubles the number of distinct data items that can be encoded, but it also increases demands on computer processing, storage, and transmission.

Good file maintenance is important in multimedia development. This involves identification, categorization, and preservation. Preserving original files from the specialized applications used to produce them is especially important for future revisions and/or the creation of new products.

A computer can process only digital data. Analog data must be converted to a digital format before computers can make use of it. Many of the most important concepts in multimedia development are concerned with this conversion process, called digitization. Digitization is based on sampling, a process in which many separate measurements are made of the continuously varying properties of analog media. Quantization, the rounding of the value of a sample to the closest available value of the digital code, may produce distortions in digital versions of analog phenomena. Ensuring that the samples are represented with adequate bit depth (also known as sample resolution) can lessen these effects. Sample rate, or the frequency with which samples are taken, also affects the quality of digitized media.

Media can also be directly created by the computer and digitally encoded. There are two major types of original digital media—description-based and command-based. Description-based media are encodings of large numbers of media elements—pixels for images and amplitude samples for sound. Description-based media are especially appropriate for the accurate representation of natural images and sounds such as photographs and human speech. Command-based media are encoded as commands that the computer follows to generate the image or sound. Files for command-based media are much smaller, offering significant advantages for delivery over the Web. They also have other advantages, including distortion-free scalability.

High-quality digital media, especially dynamic media such as sound and video, can produce very large files. These often require compression before they can be practically incorporated in multimedia applications. Codecs compress digital data files to reduce their size and then decompress them for display or playback. Some codecs are lossless—they encode data more efficiently while preserving all of the original content. Others sacrifice data judged not to be essential and are described as lossy.

Because the meaning of digital data can be dramatically changed with the loss of just a few bits, error detection and correction routines often play an important role in the transmission and playback of digital data. *EDC/ECC* (error detection code/error correction code) can greatly improve the reliability of digital data.

Digital data has significant advantages related to reproduction, editing, integration, and distribution. It also poses challenges such as file size, processor demand, standardization, bandwidth, and preservation.

Key Terms

Analog data	Convention
ASCII	Data
ASCII-8	Data files
Bandwidth	Description-based digital encoding
Bit	Digital data
Bitmapped image	Digital encoding
Byte	Digitization
Codec	Effective code
Command-based digital encoding	Efficient code
Compression	Extended ASCII

File	Native file format
File compatibility	Parity bit
File conversion	Platform
File extension	Program file
File format	Quantization
Generation decay	RLE
Gigabyte	Sample rate
Incompatible	Sample resolution
Information	Sampled sound
Kilobyte	Sampling
Lossless compression	Spatial resolution
Lossy compression	Symbol
Megabyte	Terabyte
MP3	Unicode

Review Questions

1. What is a symbol? Why is a bit considered a symbol?
2. What is the difference between data and information?
3. Why is an 8-bit code to designate the characters in the English language effective? Is it efficient?
4. Why is file compatibility important for multimedia development?
5. What is a native file format? Give an example of such a format.
6. Why shouldn't you change a file named *zipIt.exe* to *zipIt.jpg*?
7. What are the three main considerations for file maintenance?
8. What is sampling?
9. What is sample resolution?
10. What is quantization?
11. What is sample rate?
12. Why is sample rate often referred to as spatial resolution?
13. Why is RLE compression lossless?
14. Why do CD-Audio discs contain redundant data on the disc?
15. What is a codec?


Discussion Questions

1. What is an efficient code? Why would a multimedia developer be concerned about using efficient codes?
2. Why are multimedia developers concerned about sample resolution and quantization when they scan a full-color photograph?
3. Explain the distinction between description-based and command-based forms of encoding digital media. Give an advantage and disadvantage of each form of encoding.

4. What are the two major types of compression? Identify and explain which type is best for compressing an encyclopedia. Identify and explain which type is best for compressing a digital photo of the ocean.
5. How does MP3 maintain audio quality while also significantly reducing file sizes? Explain two specific strategies.
6. Identify and briefly describe two advantages and two challenges in the use of digital information.

Chapter 3

Computer Hardware



Topics you will explore include:

- Computer Systems
 - Supercomputer
 - Mainframe
 - Personal
- Computer Platforms
- Hardware Components
 - System Unit
 - CPU
 - Primary Memory
 - Expansion Ports
 - Peripheral Devices
 - Secondary Storage Options
 - Magnetic
 - Solid State
 - Optical
 - Input Devices
 - Output Devices
- Networks
 - LAN
 - WAN
 - Internet

Computer technology has transformed our lives for over 50 years. First introduced to alleviate the tedious work of calculating long data tables for the military, we now find computers recording and processing every aspect of our daily activity. The modern computer is no longer just a numeric calculator; it is a multimedia device that displays images, sound, and video through operating systems and applications that give the user unprecedented control over information. Visionaries such as Alan Turing and Vannevar Bush articulated the direction for such computers, but it was the development of micro-electronics that brought multimedia to our desktops. Powerful computing devices make multimedia applications possible. They capture and convert input from various analog sources, process and store the digital data, and output in ways that empower users to create, distribute, search, and share information as never before. Hardware powers the development and delivery of multimedia.

In this chapter you will explore the basic components of a computer system including the peripheral devices used for developing multimedia applications. Developers are concerned about the performance features of not only the processor, but also all input, storage, and output devices. After completing this chapter you should understand:

- Components of a computer system
- Types of computer systems
- Functions and components of the central processing unit (CPU)
- Functions of the system board and hardware interface
- Peripheral devices and performance criteria for:
 - Secondary storage
 - Input
 - Output
- Network fundamentals

3.1 Computer Systems

A **computer system** is an integrated set of hardware and software designed to process data and produce a meaningful result. Every computer performs the basic functions of *input, processing, storage, output, and transmission of data*. Instructions and data are entered, processed into results that are stored for later use, and output in a useful format. Computers are connected to a larger network system for transmission of data and information.

Computer hardware is organized according to these basic functions. The *system unit* focuses on processing, whereas a variety of *peripheral devices* facilitate input, output, storage, and communication.

Types of Computer Systems

Computers are often identified by their size and power. Common categories of computer systems include *supercomputers, mainframes, and microcomputers*. Size traditionally refers to the computer's physical mass, whereas power refers to the computer's speed and the complexity of calculations it can carry out. Originally, mainframe computers

were physically much larger than desktop microcomputers. Size is now less significant, because microelectronics can package very powerful systems in very small spaces.

Supercomputers are the most advanced, powerful, and expensive computers of the day. They are characterized as having the fastest processing speeds and performing the most complex calculations. Today those speeds can reach quadrillions of calculations per second; tomorrow they will be even faster. Supercomputers are unlocking many mysteries of our universe. They are widely used in scientific research, artificial intelligence, defense systems, and industrial design. More recently, they have been applied to multimedia development. For instance, in the film industry, supercomputers are used to carry out the rendering operations that transform digital animations into magical three-dimensional worlds.

A **mainframe computer** is an advanced multiuser machine typically used to manage the databases, financial transactions, and communications of large organizations such as banks, hospitals, retail stores, insurance companies, and government offices. While these applications don't require the computational complexity of supercomputers, mainframes are still very powerful: they can process billions of instructions per second, support hundreds of users, and store terabytes (trillions of bytes) of data. Supercomputers and mainframes are very expensive and require a support staff to maintain daily operations. These computer systems are vital to the performance of many daily tasks but it was the personal computer that transformed the way most of us think and work.

A **personal computer (PC)** is a system that uses a microprocessor to provide computing to a single user. Personal computers have many different names and configurations including **microcomputer**, laptop, desktop, and tablet (Figure 3.1). The first personal computers were developed in 1975 by computing enthusiasts who wanted their own computer rather than share a large centralized mainframe. Their efforts were energized in 1971 when Intel introduced the microprocessor. A **microprocessor** is a single silicon chip that contains all the elements of a central processing unit (CPU). This miniature CPU was not as powerful as a mainframe, but it was much smaller and cheaper. It was perfect for a single user who wanted computing capability on the desktop.

Altair, the first microcomputer, appeared in 1975 and launched the microcomputer revolution. In 1977, Commodore Pet and Apple II followed. The IBM PC appeared in 1981. IBM used the Intel microprocessor to build office computers for word processing, spreadsheets, and databases. These applications focused on text-based data to improve business productivity.

On January 24, 1984, Apple introduced a different type of microcomputer, which relied on images and sound to interact with the user. Steve Jobs and Stephen Wozniak captured the visions of Bush, Engelbart, and Kay when they delivered the first commercial multimedia computer. The Macintosh used an operating system with a graphical

Supercomputer speed and power can be achieved by uniting individual CPUs through a network of distributed computers. The Berkeley Open Infrastructure for Network Computing (BOINC) sponsors open source software for volunteer computing and grid computing to tackle complex research projects. In 2012, BOINC reported sharing over 400,000 computers that delivered 6.438 PetaFLOPS of computing power. See <http://boinc.berkeley.edu/>.



Figure 3.1 Common microcomputer systems.

interface that resembled a standard desktop complete with folders and a trash can. It relied on a mouse to manipulate data and programs. It included sound capabilities and dramatically introduced itself at the January 1984 debut. From that day on, advances in hardware technology supported the development of multimedia computing. Today's microcomputer is in every way a multimedia machine.

3.2 Computer Platforms

Computers have fundamental differences based on the hardware components, such as processors, and the operating systems that they use. An operating system is the software that manages the computer's resources and executes application programs. The combination of hardware and operating system is often called the **computer platform**.

Microcomputer Platforms

The two most common microcomputer platforms are Macintosh and Windows-based PCs. The Macintosh platform utilizes hardware developed by Apple. Apple defines the hardware specifications and develops the operating system to control the hardware. Apple currently manufactures multimedia computers in several configurations: MacBook (end user laptop), iMac (end user desktop), and Mac Pro (developer system). The most popular personal computer today is a Windows/PC platform. These microcomputers utilize the Windows operating system developed by Microsoft. Many companies, such as Dell, Gateway, HP, and Sony, build Windows/PC computers. You might even build one yourself, as the hardware components are readily available from a variety of manufacturers.

Understanding the distinctions between computer platforms is important for multimedia development. Developers who plan to reach a wide market are concerned about **cross-platform compatibility**, the ability of an application to run on different hardware and operating systems. For example, images that are saved in a color palette and file format optimized for the Windows/PC platform may appear distorted on a Macintosh computer. Font technologies and typeface families also vary between the two platforms. Advances are underway to standardize digital media formats so they can be utilized on both platforms. Adobe Acrobat, now in widespread use, provides one successful cross-platform format for text and images. The World Wide Web is a major catalyst for defining data formats so that they can be viewed on any computer through network connections and a browser.

Mobile Computing Platforms

Mobile computing platforms are the result of the continuing miniaturization of computers and the merger of computing and telephone technologies. Mobile computing devices include lighter personal computers, special purpose e-readers, and tablet computers, as well as smartphones networked through Wi-Fi or 3G/4G technologies. Applications designed for traditional Mac and Windows platforms must now take into consideration mobile devices based around the Google Android OS, Apple iOS, Blackberry OS, and a wide array of proprietary systems, many built around the Linux operating system. The proliferation of mobile computing devices has dramatically increased opportunities for multimedia developers while also posing the challenge of creating applications that meet the requirements of a variety of mobile platforms.




Figure 3.2 System unit.

3.3 Computer Hardware Basics

Computer hardware is divided into two main categories: the system unit and peripherals. The **system unit** contains the electronic components used to process and temporarily store data and instructions (Figure 3.2). These components include the central processing unit, primary memory, and the system board. **Peripheral devices** are hardware used for input, auxiliary storage, display, and communication. These are attached to the system unit through a hardware interface that carries digital data to and from main memory and processors.

System Unit

Central Processing Unit The most important component of any electronic computer is the central processing unit. A **CPU** is a complex integration of millions of transistors that execute program instructions and manipulate data. The Intel 10-Core Xeon houses over 2.6 billion transistors within a tiny 2-inch chip. This ability to store a CPU on a single silicon chip ushered in the age of personal computers.

The CPU has three essential sets of transistors that work together in processing digital data: a control unit, an arithmetic logic unit, and registers. The **control unit** directs the flow of data and instructions within the processor and electronic memory. The **arithmetic logic unit (ALU)** contains programmed transistors

The System Unit and the Box

Many refer to the rectangular box of the computer as the system unit. In fact, that “box” can contain several peripheral devices such as hard drives, optical drives, and even the monitor. As computer sizes shrink, manufacturers combine peripherals with the system unit in a single container.

that perform mathematical and logical calculations on the data. The **registers** are special transistors that store data and instructions as they are being manipulated by the control unit and ALU. New microprocessors also have additional high-speed memory called **cache**, on the chip to store frequently used data and instructions.




Figure 3.3 Sequential processing steps.

Processing data and instructions are managed in a machine cycle. The **machine cycle** includes four steps that a processor carries out for each instruction: fetch, decode, execute, and store (Figure 3.3). The control unit *fetches* data and instructions from a part of the computer's memory called RAM (random access memory). It transports the digital bits through an electronic bus, stores the instruction in registers, and *decodes* the instruction for the arithmetic logic unit. The ALU *executes* the instruction and returns the result to an accumulator register and storage register. When one machine-level instruction is completed, a second one is sent through the cycle. Eventually there is an instruction to *store* the results and the control unit moves data from its temporary storage register to a specific address in RAM. Various performance features of the CPU determine the efficiency of this basic machine cycle. These include clock speed, word size, bus width, and techniques such as pipelining, RISC processing, multiprocessing, and multicore technology.

Clock Speed An internal system clock synchronizes the machine cycle. On each clock tick, the CPU executes another instruction. **Clock speed** is the rate at which the CPU carries out its basic instructions. Computers execute instructions very rapidly, at speeds measured in hertz. One *hertz* is one cycle per second. Microcomputer clock speed is measured in *megahertz* (MHz, millions of cycles/second) or *gigahertz* (GHz, billions of cycles/second). Newer chip set designs combined with faster electronic storage are making it difficult to rate CPU performance solely on clock speed (Table 3.1). Increasing internal clock speed is just one method of improving the performance of a CPU. Other performance features must also be optimized to take full advantage of the processor's power.

Word Size One important factor that contributes to CPU power is the amount of data or instructions that are moved through a processor in one machine cycle. **Word size** refers to the group of bits that a processor can manipulate as a unit in one machine cycle. A 64-bit processor can manipulate 64 bits (or 8 bytes) of data at one time, clearly an advantage over a 32-bit (4 bytes) processor.

Table 3.1 Sample Processor Ratings

Microprocessor	Transistors	Clock Speed	Word Size
Intel Pentium IV	42 million	2.4 GHz	32 bit
AMD Athlon64	105.9 million	2.2 GHz	32 bit
AMD K10	758 million	1.6 GHz	64 bit
Intel i7 Quad	731 million	2.93 GHz	64 bit
Intel Atom Z540	47 million	1.86 GHz	64 bit
Intel i7 Six Core	2.2 billion	3.9 GHz	64 bit

Bus Width Another performance factor is the width of the system bus between the processor and memory. A **bus** is an electronic path for the flow of data. The **system bus** is an electronic pathway between the CPU, memory, and other system components. The processor has two bus connections to memory: the data bus and the address bus. The **data bus** is the set of pathways that carries the actual data between memory and the CPU. A 64-bit data bus can move 8 bytes of data to the processor in the same machine cycle. The data bus width should be matched to the word size of the CPU for optimum performance.

The **address bus** is the electronic pathway that carries information about the memory locations of data. The width of the address bus determines how much potential memory a processor can recognize. Larger address buses mean the processor can address more memory. Processors that use a 64-bit address bus can access a potential of 16 GB of memory (2^{64}). The processor's ability to access a large address space is important for multimedia applications. Digital video, sound, and images produce large data files. Larger address buses support faster multimedia processing by allowing these files to be moved from hard drives, CD-ROMs, DVDs, and other peripheral storage devices to the computer's electronic memory where they can be processed and displayed faster.

Pipelining Microprocessor manufacturers such as Intel, Motorola, and IBM utilize additional techniques to maximize the CPU's speed. **Pipelining** increases CPU efficiency by reading an instruction, starting processing, and reading another instruction before finishing the previous one. Using pipelining, different steps of the machine cycle can be carried out on several instructions simultaneously (Figure 3.4). This reduces CPU idle time and increases the speed at which instructions can be executed.

RISC Processing RISC (reduced instruction set computer) chips also increase overall speed of the CPU. **RISC** chips eliminate complex embedded microcode instructions and




Figure 3.4 Modern processors support pipelining to increase the performance of the processor. In pipelining, instructions are sent to the processor in stages.

replace them with a simpler set of instructions for executing the most common commands used by the processor. These common commands are combined to carry out the less frequent, more complex processing tasks. This results in faster overall processing of routine operations. RISC technology is found in many microprocessors and is rapidly expanding to mobile phone processors.

Multiprocessing Multiprocessing can also improve system performance. **Multi-processing** is a combination of multiple processors on the system board that execute instructions simultaneously. There are several approaches to multiprocessing. Computers

Microcode is a programming technique for implementing the instruction set of a processor. An **instruction set** is the set of instructions that a processor can carry out.

may have a CPU and math coprocessor or graphics coprocessor working together to increase the overall performance of a system. The Apple G5 computer has dual processors that speed CPU operations using 64-bit chips, reaching processing power comparable to a supercomputer. Multimedia development may also employ **parallel processing**, a technique of linking multiple processors to operate at the same time on a single task. Parallel processing is often used to speed the final stage of 3-D animation, known as rendering. DreamWorks employed a “render farm” of over 1000 HP ProLiant DL145 servers to render the daily versions of its animated films *Shrek 2* and *Madagascar*.

Multicore Technology Multicore processors are an increasingly popular approach to multiprocessing in personal computers. A processor core is a CPU’s “computational engine,” that is, those components that directly execute instructions. Older processors were single core. The CPU was built around a single computational engine that fetched and executed each command in the pipeline as fast as it could. To improve processing capacity, engineers increased clock speeds and made other improvements that added transistors to the CPU. However, the extra electronics increased the heat on the chip and did not achieve the performance gains necessary for current computing demands. Manufacturers looked for a different strategy to increase processing speeds while reducing heat and improving energy efficiency. The result was the multicore architecture.

Multicore technology combines two or more processor cores and cache memory on a single integrated circuit. A dual-core processor has two execution cores and two L2 memory caches. These two “cores” work together simultaneously to carry out different tasks. More cores can be added to further improve computer response time for increasingly complex operations. To achieve these computing gains however, the operating system and applications must be adjusted to take advantage of the multiple cores using a technique called multithreading, or passing tasks simultaneously to different cores to execute.

Multicore processors can significantly improve performance in multitasking work environments where one processor core can address one task while a second task is completed by another core. For example, one core might be directed to writing a DVD and a second one to editing images in Photoshop. A multicore processor would execute both tasks faster because each core could address a separate task. This can speed the process of multimedia development. The technology also has benefits for multimedia playback, particularly for graphics-intensive applications. Multicore processors are used

in many video gaming consoles where they speed real-time rendering of complex graphics and player interactions.

The fetch/execute cycle of the CPU is optimized by a variety of techniques to increase speed and deal with more complex data types. By increasing clock speed, word size, and the system bus, the control unit and ALU can process data faster. New developments in pipelining, multiprocessing, and multicore chips are producing faster processors that can handle increasingly complex commands for manipulating multimedia data.

Research continues to improve the speed and performance of the CPU. Moore's Law suggests that manufacturers can double the speed of a processor every 18 months. Future computers may use nanotechnology to achieve smaller and faster processors. Reliance on electronics may be replaced with optical circuitry to increase the speed of processing to "light speed." Whatever the technique, we can expect new computer processors to continue to show improvements in performance.

Nanotechnology: Manufactured objects are designed and built by the specification and placement of individual atoms or molecules.

Primary Memory Modern computers operate with electricity. The CPU processes electrically and uses basic instructions wired in the ALU's electronics. Therefore, data and instructions directly manipulated by the CPU must also be stored electronically. **Primary memory** is electronic storage that is directly addressed by the CPU.

There are several forms of primary memory on a computer system. **Random access memory (RAM)** consists of addressable storage areas for data and instructions in electronic format. This storage is volatile. Once electricity is powered off, the contents are lost. While not suitable for long-term storage, RAM provides the fast, electronic access to data and instructions required for processing by the CPU.

The amount of RAM storage is an important performance feature of computer systems. RAM is measured in units of megabytes (MB) or gigabytes (GB). Personal computers used to develop and play complex multimedia should have as much installed RAM as possible. Large RAM capacities are necessary to store the operating system, application software, and data for multimedia processing. Modern multimedia operating systems use large amounts of electronic storage. Current operating systems from Apple and Microsoft recommend 2 GB of RAM. The application software to develop media also has large memory requirements. Developers like to keep more than one program open in memory. This practice of **multitasking** (running more than one program simultaneously) consumes large amounts of RAM. In addition, multimedia data files are often very large. Sound and video files, for example, can easily require 500 MB or more of electronic storage. Larger capacities of RAM storage mean more data and applications can be open and readily accessed by the CPU. This translates to greater efficiency in the development and delivery of multimedia applications.

A second form of primary memory is **read-only memory (ROM)**. ROM is a special form of nonvolatile electronic storage that contains frequently used instructions for the CPU. These commands are hardwired or embedded in the chip by the manufacturer; they can be read, but not changed. The instructions perform essential system checks and load the operating system from disk storage into RAM. ROM is activated when the power is on. The embedded instructions do not disappear when the power is off, unlike RAM storage.

A third form of electronic memory is called cache storage. This high-speed electronic storage optimizes microprocessor speed by storing frequently used data and instructions close to the processor. This reduces the time it takes to locate and transport data from RAM. Primary cache (Level 1) is on the actual CPU chip. Level 2 cache is positioned between the CPU and RAM. It has higher capacity than primary cache on the CPU, but less capacity than RAM. Neither Level 1 nor Level 2 cache storage adds to the overall total of available RAM. However, cache is an important feature that improves processor performance.

System Board The **system board** (also called the *motherboard*) is the main circuit board, or the electrical foundation of the computer. In addition to CPU, RAM, and ROM chips, the system board contains the following:

- Expansion slots to add memory and hardware devices
- Special purpose chips that convert analog signals to digital format
- Video card to control the display monitor
- Power supply
- I/O interface ports to capture and send data to peripheral devices

Multimedia computers are equipped with many built-in devices, but often a developer may want additional hard drives, a DVD burner, or a second video board, for example. Many computers have expansion slots to add these hardware components; others have limited or no expansion capability at all. An alternative to adding devices directly on the system board is to plug external devices into an interface port.

Hardware Interface A **hardware interface** is a point of union between the system unit and a peripheral device. Data flows through the interface between the system board and peripheral devices in a serial or parallel path. **Serial data transmission** is a single stream of bits. One wire sends the bits and another wire returns the bits. This method is generally used for devices that don't transfer large volumes of data, such as a keyboard, mouse, or modem. **Parallel data transmission** is a series of bits transferred simultaneously. Each bit has its own wire in a parallel path. Parallel connections may move 8 or more bits of data at once, thus increasing the amount of data transferred in a given amount of time. **Interface ports** are connections to add peripheral devices to the system board (Figure 3.5). They are generally located behind the system unit cabinet or on the sides of portable computers. Current microcomputers are equipped with USB (Universal Serial Bus), FireWire (IEEE 1394), audio, video, and Ethernet ports.




Figure 3.5 Interface ports for MacBook Pro.

Universal Serial Bus (USB) is an input/output bus to transfer data at higher speeds than older serial and parallel interfaces. USB has several advantages over previous bus systems. First, it is a widely supported standard. This simplifies purchasing external devices. A USB device can plug into any USB port, whether on an Apple or PC. Second, a USB cabling system creates its own independent bus where up to 127 devices can be daisy-chained together and share a single port on the microcomputer. Third, USB devices are “hot swappable.” A USB device can be disconnected and another device swapped (plugged) into the system without restarting the computer. Fourth, USB devices can be powered through the interface port rather than a separate power supply. This greatly reduces the number of power adapters (or “wall-warts” as they’ve been called) that clog up power strips. Finally, USB has faster data transfer. USB transmits data at speeds of 12 Mbps (megabits per second) compared to the RS-232C speeds of 115.2 Kbps (kilobits per second). USB devices such as printers, scanners, zip drives, and keyboards benefit from faster transmission rates. The USB 2.0 standard introduced even faster transmission rates (480 Mbps) for devices that require higher rates of transmission such as MP3 players, removable hard drives, and DVDs.

IEEE 1394 (named **FireWire** by Apple) is a high-speed serial interface standard with data-transfer rates of 400 Mbps over cables up to 4.5 meters in length. It has its own bus system that can daisy chain up to 63 devices. Like USB, FireWire devices are hot swappable and power for these devices is drawn from the FireWire port. These ports are most often found on digital video cameras or large capacity external hard drives. A further development of the standard, FireWire 800, has twice the transfer speed and can maintain it across 100-meter cables. This opens efficient cabling possibilities to capture digital video and/or audio from cameras placed significant distances from the computer (Figure 3.6).

As the processing speed of CPUs increases, computer manufacturers continue to seek ways to increase the interface speeds between the user and the system board. **USB 3.0** and **Thunderbolt** are the newest interfaces for connecting peripheral devices to the system board.

Code named *SuperSpeed* USB, the USB 3.0 standard offers faster transfer speeds than its predecessors. USB 3.0 can deliver up to 4.8 Gbps and remain backward compatible to the USB 2.0 standard. High-bandwidth devices such as camcorders, webcams, and Blu-ray burners, for example, will experience better performance using the USB 3.0 interface.

Thunderbolt was developed by Intel and introduced to the market by Apple. It offers three main advantages over other interfaces. First, Thunderbolt combines the transfer of both computer data, from devices such as hard drives, and display data for additional monitors or projectors. This simplifies the interface by eliminating the need for a separate video port. Second, Thunderbolt improves transfer speeds. It delivers simultaneous data and display transfer on a single bidirectional cable at speeds of 10 Gbps, making it the fastest entry into computer interface design. Finally, Thunderbolt increases the



Figure 3.6 USB, FireWire, and Thunderbolt cables.

Table 3.2 Transmission Rates for Common Interface Standards

Serial Port	115 Kbps
Standard Parallel Port	115 Kbps
USB	12 Mbps
USB 2.0	480 Mbps
USB 3.0	5 Gbps
IEEE 1394 or FireWire	100–400 Mbps
FireWire 800	800 Mbps
Thunderbolt	10 Gbps

power available to peripheral devices to 10 watts compared to USB 3.0's 4.5 watts. Table 3.2 summarizes transmission rates for the various standards.

Peripheral Devices

Peripheral devices are the hardware components that input, output, and permanently store data and applications for computer processing. Although often located close to the system unit, they are outside the main processing circuitry and thus are considered peripheral (Figure 3.7). The functions and performance characteristics of peripherals are important considerations both for multimedia users, who may want the best display device for a video game, and for developers, who seek high-performance data capture and access.

Secondary Storage Devices Computer systems are not complete without a means of storing data and instructions for future use. Random access memory is essential for the CPU to process data and instructions electronically, but RAM is volatile. Once the power is off, memory is cleared and data is lost. **Secondary storage** is the media that holds data and instructions outside the system unit for long periods of time. It is also called *external storage* or *auxiliary storage* to distinguish it from primary electronic storage inside the



Figure 3.7 With the miniaturization of today's mobile computing devices, the peripherals may not seem so distant. Smartphones and tablet computers embed display and input into the single-system device.

system unit. Early forms of secondary storage were paper tape, punched cards, and magnetic tape. Secondary storage now includes hard disks with gigabyte capacities, optical discs that deliver high-fidelity multimedia, and a wide array of portable storage ranging from zip disks to flash drives, as well as portable music players and smartphones (Figure 3.8).

Secondary storage has several advantages over primary electronic storage. In addition to being nonvolatile, secondary storage is easily expandable and portable. If one disk fills with data, another disk is readily available. Data and applications are easily distributed and shared through secondary storage media such as CDs, DVDs, flash drives, or zip disks. Each of these addresses one or more of the five main uses of secondary storage: *saving, backup, distribution, transport, and archiving.*

The most obvious use of secondary storage is to *save* the data that is in electronic memory for further processing. Multimedia developers frequently save data files to hard drives or other devices as they work. They know that RAM is volatile and that hours of effort can be lost in an instant with a system crash or power failure. Important performance criteria for saving include capacity, access time, and transfer rate. **Storage capacity** is the amount of digital data, measured in bytes, that a device can record. Multimedia developers require high storage capacities for large media files such as digital video. **Access time** is the time needed to locate data on the storage device. **Transfer rate** measures the speed at which data moves between secondary storage and RAM. Faster access times and transfer rates mean less time waiting for data and applications to load into RAM. This speed is especially important if developers are working with large sound or video files where fast access to data editing and playback is essential.

Another use of secondary storage is to *back up* entire hard drives or important volumes on the hard drive. Data is a major asset for most organizations. It must be preserved in the event of damaged drives, theft, system crashes, viruses, or natural disasters. Backup systems should have large storage capacities and be able to transfer data quickly. Frequently, a hard drive is backed up to another hard drive because both have large capacities and fast transfer rates. Users should also consider backing up important data files to other devices, such as a zip disk, flash drive, or DVD, on a routine schedule. To further protect the data, the backup should be stored in another location, preferably off-site.

A third use of secondary storage is *distribution* of data and applications. Networks improve data sharing over communication lines, but data portability cannot be restricted to network connections. Data and applications can also be distributed by “snail mail” or as retail products such as “shrink-wrap” software. CDs, for example, are cheap to produce, have long storage life, and are lightweight. Most computers can read the disc, which makes them a good choice to distribute applications and data. Performance features to consider in distributing secondary media include cost, weight, data integrity, and adherence to standards for playback.

In addition to distributing data and applications, secondary storage media *transport* digital content. Commonly called “sneaker-net,” users can carry their digital files on por-



Figure 3.8 The iPod is also a popular storage device. In addition to holding hours of music and video, the iPod can plug into a USB port to record data for transport.

table media such as flash drives. Adequate capacity and the ability to withstand temperature extremes, magnetic fields, and the wear and tear of a duffel bag are important criteria for digital data on the move.

Finally, a fifth use of secondary storage is to *archive* digital information for long-term preservation. Digital files abound in all the transactions of daily life, and schools, hospitals, governments, businesses, and other organizations must preserve them for legal and historical purposes. In the past, this meant large vaults of file folders. Later, these files were transferred to tape and stored in special tape libraries. Archived data requires storage media with massive and expandable capacity, media longevity, and security. These include RAID (redundant array of independent disks) drives, WORM (write once, read many) optical disk library systems, and digital tape.

The secondary storage devices fall into three broad categories based on the underlying technology used to represent digital data: magnetic, optical, or solid state.



Figure 3.9 Zip cartridges.

Magnetic Storage **Magnetic storage** devices record and/or read digital content in magnetic form. Early microcomputers used floppy disks for magnetic storage. These were thin plastic disks with a coating of iron oxide that could be inserted in a floppy drive mechanism. They were light and easily transportable but very limited in storage capacity (1.4 MB per disk). Later, cartridge drives such as the zip drive provided removable media with larger capacities (100 MB, 250 MB, and 750 MB) (Figure 3.9). Although zip cartridges and similar media are still in use, they have largely been replaced with solid-state devices such as USB flash sticks. Magnetic storage is now found principally in internal and portable hard drives.

Hard drives are composed of rigid platters mounted on a spindle in an enclosed drive container. The container regulates air pressure and filters the air that enters the drive to protect it from dust and other contaminants. A drive motor rotates disks at speeds of 7200 revolutions per minute (rpm) or more.




Figure 3.10 Disk platters are rotated on a spindle. The access arms move to a track location and the read/write head transfers data to and from RAM.

The drives record bits on a disk platter as positive or negative magnetic fields. Access arms with read/write heads move between platters to read tracks on both top and bottom surfaces (Figure 3.10). Data is stored on these platters in addressable tracks and sectors defined by the operating system. A **track** is a circular path along which data is stored. **Sectors** are pie-shaped logical divisions of a track (Figure 3.11). Each sector holds a designated amount of data (traditionally 512 bytes; more recently 4096 bytes). The number of tracks and sectors determine the drive's storage potential. Hard-disk units built inside the computer system have capacities ranging from gigabytes to terabytes, but even these disks quickly fill with large multimedia data files, applications, and modern graphics-based operating systems.




Figure 3.11 Track/sector addressing scheme for magnetic storage.



Figure 3.12 External hard drives.

External hard drives supplement the fixed hard drive capacity while providing data portability and security. These drives often use FireWire or Thunderbolt for high-speed data transfer to the system unit. They are commonly used to back up and secure data, or store and edit large projects such as digital video (Figure 3.12).

Magnetic media can provide large-capacity storage and rapid data access and transfer. Magnetic storage is also economical. Prices are currently under 10 cents per gigabyte and they continue to drop. But magnetic storage also has several disadvantages, not the least of which is its limited durability. Magnetism is easily destroyed or weakened over time, resulting in damaged or lost data unless backups are done frequently. See Table 3.3 for sample performance measures of magnetic storage.

Optical Storage **Optical storage** uses laser technology to read and write data on specially coated reflective discs. The origins of optical storage can be traced to the early 1980s.

In 1982, the CD (compact disc) revolutionized the music industry and spurred the development of multimedia applications. Philips and Sony first developed CDs to replace vinyl records with a medium that could deliver high-quality sound on a small, lightweight platter. LP (long-playing) records were limited to 45 minutes of analog music. Sound quality was governed by the condition of the record and the needle, and records themselves were bulky and difficult

Disc and Disk

Disc refers to optical storage media as opposed to *disk*, which is used for magnetic media.

Table 3.3 Magnetic Storage Performance Measures

Device	Access Time	Transfer Rate	Capacity
Zip drive	29 ms	1.2 MB/s (USB 250)	100, 250, 750 MB
Hard drive	< 9 ms	15 MB/s–160 MB/s	Variations of GB/s & TB/s
External hard drive	> 13 ms	20 MB/s–100 MB/s	Variations of GB/s & TB/s

to manage. Portable music was restricted to tapes, also easily susceptible to damage. Compact disc storage and digital music provided a medium for permanent, high-fidelity recordings. CDs were designed to hold a full 74 minutes of digital audio recording, significantly increasing music storage over the long-playing vinyl record.

The advent of optical storage also offered new potential for multimedia. A new CD standard, called CD-ROM, was developed especially for computer data. Now applications that required large storage could easily be distributed on a small 4.72-inch disc. The first general interest CD-ROM was *Grolier's Electronic Encyclopedia*. Released in 1985, its 9 million words only used 12% of the CD-ROM's capacity. Optical storage technology developed rapidly. From music CDs of the 1980s, technology expanded to DVD-Videos in the 1990s.

- **Compact Disc Technology:** CD storage uses a laser beam to read and write data to a disc.

Lasers are amplified light energy focused into a very precise beam. The basic process is simple: focus a laser beam on a reflective surface and measure the amount of light reflected back on a photo detector. By altering surface texture, light will either be reflected or deflected. The disc acts as a reflective mirror with pits and lands that encode digital content. **Pits** are indentations on the surface and **lands** are the flat area. Pits scatter light and lands reflect light (Figure 3.13). Binary data once encoded as positive/negative magnetism is now read as variations in light reflection.

CD-Audio and CD-ROM discs are manufactured by pressing pits into a plastic base. This process is called *stamping*. A reflective layer of aluminum is then added and finally a lacquer coating is applied to protect the surface. The laser beam scans the bottom of the disc surface where pits appear as bumps to scatter light. Lands reflect the full intensity of the light beam. Once the CD is stamped, data is permanent.

Optical storage has several advantages. The first is high-capacity storage. Laser beams are extremely precise and pits and lands are extremely small, so data is densely recorded on a disc. Pits are approximately 0.83 microns long by 0.5 microns wide (about 30 times narrower than a human hair). Data is recorded in one continuous spiral from the center to the outside edge of the disc. There are about 20,000 windings of this single

spiral on a CD, resulting in a total track length of 5000 meters, or about 3 miles. This produces a storage capacity of 680 MB.

Another benefit of optical storage is stability. CD data is more durable than data stored magnetically. Pits are pressed into the disc. This process makes it unlikely that normal handling and exposure to the environment will destroy the data. CD data is also encoded with special error detection and correction code (EDC/ECC) to further ensure data integrity if the disc is damaged. Magnetic disks do not incorporate error detection and correction, with the result that damaged data is often lost

Pits, Lands, and EFM

Pits and lands do not translate directly to bits. Instead, optical discs use an encoding system called *eight-to-fourteen modulation* (EFM). Fourteen bits are used to encode the 8 bits of a data byte. The extra information is used to ensure the accuracy of the optical reading of each byte.




Figure 3.13 Pits scatter light and lands reflect light.

data. By contrast, the data on a scratched CD-Audio disc can usually be repaired as it plays. CD technology is synonymous with high-capacity, high-quality, and durable storage.

- **Optical Data Encoding:** Optical data is organized in *tracks*, *frames*, and *sessions* on the disc. A track is the basic addressing scheme on a CD. A CD has a physical, continuous spiral from the center to the outside edge, but it is further divided into logical units called tracks. A compact disc addresses 1 of up to 99 sequentially numbered tracks. Each track can handle only one data type, so a CD with music and text would require at least 2 separate tracks (Figure 3.14).

The basic unit of information stored on a CD is a **frame**. Frames define the physical format of data. Frames contain data code, error detection and correction code, synchronization code, and information about the track. Fifty-eight frames are grouped together to form the smallest addressable data unit, called either *blocks* (CD-Audio) or *sectors* (CD-ROM). Each CD-Audio block has 2352 bytes of user data, while CD-ROM sectors contain 2048 bytes of data code. There are fewer bytes of data code on the CD-ROM because these sectors contain more error detection and correction code that helps ensure the integrity of error-sensitive media such as text and numbers.

A **session** is a single recorded segment on the CD. Sessions may cover several tracks depending on the content of the application. For each session, a track table of contents is added to the disc. A *track table of contents* (TTOC) is an index of track contents. Early CDs supported only one session and one TTOC per disc. This is called a single-session CD. Newer CD formats support *multisessions*. Kodak used the first multisession CD for their PhotoCD by recording one set of photos on a CD, then adding another set




Figure 3.14 CDs store data in a continuous spiral from the center to the outside of the disc. The single spiral is further divided into logical units called tracks. The smallest addressable data unit is called a block or sector.

of images with a separate track table of contents to the same CD at a later time. Today, multisession storage is common on CD-R (CD-Recordable) discs.

- **Compact Disc Formats:** One of the more important decisions made by optical disc manufacturers was to standardize the size of the disc. Disc size is fixed at 120 mm, with a 15-mm center hole and 1.2-mm thickness. As a result, all CDs will fit into any drive, making it possible to design newer drives with backward compatibility. *Backward compatibility* is the ability of more recent hardware or software to use data from an earlier product. The most important CD formats are CD-DA, CD-ROM, CD-R, and CD-RW.

CD-ROM sectors have less data capacity than CD-Audio blocks because they contain more error detection and correction code. This helps ensure the integrity of error-sensitive media such as text and numbers.

Backward compatibility is the ability of more recent hardware or software to use data from an earlier product. The most important CD formats are CD-DA, CD-ROM, CD-R, and CD-RW.

The **CD-DA** (CD-Digital Audio) format was the first digital optical disc standard and it is still used in the production of music CDs. While these discs can typically be played on a computer CD drive,

CD-DA cannot be used to record computer data. CD-DA specifies a high-quality audio file format that records 16-bit samples at a rate of 44.1 KHz.

CD-ROM was developed to take advantage of CD technology for the storage of computer programs and data. CD-ROM discs are read-only memory. They can be used to distribute prerecorded data to various computers, but computers can only read them, they cannot change content by writing to the disc.

CD-R (CD-Recordable) discs use a different method of recording “pits” to allow computers to write, as well as to read, a disc. Discs are coated with a photosensitive dye. This dye is translucent when the disc is blank. Light shines through and reflects off the metal surface. When data is applied, a laser beam heats the dye and alters its molecular structure to create opaque “pits” that will not reflect light.

Several dye materials are used to create these discs, each with a different color. CD-R discs are manufactured with predefined spiral tracks and sector formatting, which determines disc capacity. CD-R discs have different recording capacities measured in minutes of music and MB of data. One common capacity is 700 MB and 80 minutes. CD-ROM and CD-R discs are similar in that once the data is written, it cannot be altered or removed.

CD-RW (CD-Rewritable) discs use a different material so the laser beam can read, erase, and write data. Discs have a special layer of phase-change chemical compound. A laser beam heats the compound and changes it either to a liquid or crystalline structure. This compound in its liquid state becomes amorphous and absorbs light. The crystalline state allows light through to reflect off the aluminum surface. These crystalline and amorphous properties remain on the disc when it cools down. These discs require a special drive with a laser that alters the heat intensity as it adjusts to read, write, and erase operations. Most computers today are equipped with a rewritable optical drive. (See Appendix A for further detail on development of standards and formats for CD storage.)

- **Optical Drives:** Optical drives are complex mechanical devices that move a laser light along a track on the disc. The laser reflects light back to a system of mirrors that direct reflections to a photo detector. A tracking mechanism controls the location of the laser beam on the disc (Figure 3.15). Early optical drive motors varied rotational speed from 500 rpm when the light was at the center of the disc, to 200 rpm when the light was at the outer edges. This allowed the drive to maintain a constant data-transfer rate.




Figure 3.15 A beam of light produced by a laser is directed through a series of lenses until it is focused on the surface of the spinning disc. A drive motor moves the laser head along the rails to reposition the laser lens.

Transfer rate measures the speed at which data is moved to the computer or other device for playback. The CD-DA standard established a transfer rate of 0.15 MB/s or 1X. This ensured accurate playback of digital music. Altering this speed would distort the sound by speeding it up or slowing it down.

When CD technology was adapted for computers, higher transfer rates were needed to quickly move data from disc to RAM. One technique to produce higher transfer rates is increasing rotational speed. Current computer CD drives have transfer rates of 48X to 64X. If the drive is rated at 48X, the transfer rate is 48×0.15 MB, or 7.2 MB/s. Transfer rates are affected not only by rotational speeds, but also by the method used to store and access data on disc. There are two methods to locate and transfer data: CLV and CAV.

CD-Audio drives read data from discs at a **constant linear velocity (CLV)**. A CLV disc stores pits and lands as closely together as possible in a uniform, continuous spiral from the center to the outside edge. This produces the highest possible storage capacity, but it also creates a problem. Because disc diameter is larger at the outside, a constant rate of spin will result in more data being read per second at the outer edge than at the inner edge. To keep the transfer rate constant, CLV drives spin the disc faster when data is being read toward the center of the disc and slower as reading takes place toward the outside. This results in the same length of the data spiral being read each second, regardless of its location on the disc (hence, constant *linear* velocity). For audio data, varying disc spin rate is a reasonable mechanical adjustment because the rate of music playback is continuous and predictable from one song to the next.

Using CLV for computer data, however, poses a problem. An important performance feature of computers is random access. **Random access** is the ability to quickly read data from any location on the storage device. Random access is difficult to achieve with CLV because drives must constantly adjust spin rates depending on data location,

speeding up if the data is located close to the center and slowing down if it is closer to the outside of the disc. When CD drives were first adapted for computer data, they maintained the CLV standard but increased the motor spin rates to improve transfer rates from 1X to 12X. However, it became apparent that CD drives needed to dramatically increase rotational speeds to keep up with faster processor demands. It was reasonable to alter spin rates from 200 rpm to 500 rpm, but much harder to go from 5000 rpm to 12,000 rpm. A second method of storing and accessing data was needed.

Computer optical drives adopted the same technique used in hard drives, **constant angular velocity (CAV)**. These drives spin the disc at a constant high speed regardless of the location of the laser. Transfer rates vary from the inside to the outside track. While this would destroy playback of a symphony orchestra on a CD player, computers can compensate for the data flow variations by buffering data and storing it in RAM for later processing. Today, most CD drives that exceed 12X transfer rates are using CAV to control disc spin rate. Computer optical drives may also combine CLV and CAV techniques. CLV mode is used to write CD-Rs and CD-RWs, while CAV mode is used to read discs.

The transfer rates of current optical drives are still slower than a hard drive, but they are much faster than the original CD-Audio drives. CD-R and CD-RW drives have a range of transfer rates. CD-R has a write transfer rate and reading transfer rate. CD-RW drives have different rates for writing, erasing, and reading. A 52X–24X–52X drive will write and read at a 7.8 MB/s transfer rate, but erase at a slower 24X, or 3.6 MB/s (Table 3.4).

- *DVD: Movies and More on Disc:* The music industry sought ways to improve on vinyl records with the first CD. In similar fashion, the movie industry pushed development of DVDs to record full-length films on a higher-quality medium than film or tape. CDs held promise for video, but their storage capacity was too low for a 133-minute movie, even with high levels of data compression.

DVD, or digital versatile disc, first appeared in 1997. Originally, it was targeted as a storage format for movies and called the digital *video* disc, but developers soon recognized its potential to store all forms of digital data and changed the name to “versatile.” The versatility of DVD is reflected in its various designations: *DVD-Video* for motion pictures, *DVD-Audio* for high-quality music, *DVD-ROM* for distribution of computer software. Competing standards and other uses of the technology have led to a proliferation of DVD specifications. See Table 3.5 for a listing of the most significant of these formats.

The main advantage of DVDs over CDs is storage capacity. The capacity of a CD is approximately 650 MB. A DVD can hold up to 17 GB. The higher capacity of DVDs is

Table 3.4 CD Drive Rotational Speeds and Transfer Rates

Drive Rating	Access Method	Avg. Transfer Rate (MB/s)	RPM
1X	CLV	0.15	200–500
8X	CLV	1.2	1600–4000
12X	CLV	1.8	2400–6000
20X	CAV	3.08	4000
40X	CAV	6.15	8000
56X	CAV	8.6	11,200

based on four major developments: a more precise laser light, multilayer storage, new video compression algorithms, and improved error detection and correction code.

DVDs and CDs are the same physical size and share the same basic optical storage technology. But new lasers with a wavelength of 635 to 650 nanometers and powerful laser lens systems can focus on smaller pits to significantly increase storage capacity. DVD pits have a minimum length of 0.40 microns, compared to the CD's 0.83 microns (Figure 3.16). Data is recorded on a spiral

4.7 GB of DVD storage can hold:

- More than 400,000 text documents, the equivalent of eight 4-drawer filing cabinets stuffed with paper information
- 4700 full-color digital photos @ 640 × 480 resolution
- 210 minutes, a full 3.5 hours of compressed MPEG2 satellite-quality video
- 120 minutes of compressed MPEG2 theater-quality video
- 14+ hours of MP3 compressed audio

Verbatim Corp.

Table 3.5 DVD Formats

Format	Features	Players
DVD-ROM	Read-only format Video or game content burned into the DVD First standard	Runs on any DVD-ROM equipped device
DVD-Audio	Higher-quality sound than CD 192 kHz/24-bit 74 min high-quality sound 7 hrs CD-quality sound	Requires special player to read the higher-quality sound files
DVD-RAM Supported by Panasonic, Toshiba, Apple, Hitachi, NEC, Pioneer, Samsung, and Sharp	Writable DVD formats for use in computers Rewrite more than 100,000 times Life expectancy about 30 yrs	Removable storage for computers Not compatible with most players
DVD-R Supported by Panasonic, Toshiba, Apple, Hitachi, NEC, Pioneer, Samsung, and Sharp	Writable DVD discs using organic dye technology 4.7 GB	Compatible with most DVD drives and players
DVD-RW Supported by Panasonic, Toshiba, Apple, Hitachi, NEC, Pioneer, Samsung, and Sharp	Phase-change erasable format 4.7 GB Rewrite about 1000 times Drives write DVD-R, DVD-RW, CD-R, CD-RW discs	Playable in many DVD drives and players
DVD+RW Supported by Philips, Sony, HP, Dell, Ricoh, and Yamaha	Erasable format Holds 4.7 GB/side Writes in a way compatible with many existing DVD readers Rewritten about 1000 times	Readable in many DVD-Video players and DVD-ROM drives
DVD+R Supported by Philips, Sony, HP, Dell, Ricoh, and Yamaha	Record only in CLV mode A write-once variation of DVD+RW.	Readable in many DVD-Video players and DVD-ROM drives
Blu-ray Developed by Sony, Samsung, Sharp, Matsushita, Pioneer, Mitsubishi, and LG Electronics	Rewritable disc Transfer rates of 36 Mbps Up to 25 GB on single layer, 50 MB on dual-layer disc 9 hrs of HD video or 23 hrs of standard video	Plays in game consoles and home theaters and can support all the disc-based media

Adapted from www.dvddemystified.com/dvdfaq.html#4.2




Figure 3.16 Pits are closer together on a DVD disc.

track that measures 7.5 miles, as compared with the CD's 3 miles. Each layer stores 4.7 GB of data, two layers on the same side offers 8.5 GB of storage. When all four layers are used, a total of 17 GB is available, enough storage for 8 hours of movies.

The second factor contributing to increased capacity is multilayer storage. Each side of a DVD can be divided into two layers. A DVD disc is a lacquer-coated sandwich of polycarbonate plastic, aluminum, and semireflective gold. The plastic is impressed with pits arranged in a continuous spiral of data. A coating of aluminum is added to the inner layer and a layer of semireflective gold is used for the outer layers. This provides two reflective surfaces. The laser first focuses on the outer layer of semireflective gold, then the lens mechanism focuses through the semireflective layer to the second layer of aluminum.

DVD players first appeared for commercial use as stand-alone systems to play DVD-Videos. Each disc could hold 133 minutes of video and an assortment of video add-ons such as trailers and outtakes. DVD drives with the capability of also handling CD and CD-RW formats were soon developed for use in com-

puters. The drive is similar to a CLV CD. The motor rotates the disc from 200 rpm to 500 rpm to maintain a constant data-transfer rate. A tracking mechanism moves the laser along a spiral track. It starts at the center and moves to the outside edge of the outer layer, then works from the outside back to the center on the inner layer to optimize the drive action.

DVD drives are rated according to rotational speeds (4X, 12X, etc.) just like CD drives, but the actual transfer rates are much higher for DVD drives. For example, a 1X DVD-ROM drive transfers 1.321 MB/s (as opposed to the 0.15 MB/s of CDs). A 6X DVD drive transfers approximately 7.93 MB/s, equivalent to a 54X CD drive. There is no advantage to a 6X DVD player for playing movies. Speeds above 1X do not improve video quality, but they will impact the speed for reading computer data and playing games.

Despite a DVD's impressive 17-GB capacity, a single disc still cannot accommodate the 110 GB required for an uncompressed full-length movie. The third improvement, video compression, delivered movies on a DVD. Video compression reduces file size without compromising the quality of video content. The Motion Picture Experts Group (MPEG) developed a 40:1 compression ratio for MPEG2. This compression format, combined with the storage capacity of the DVD, now makes it possible to have movies and much more on a single disc.

Finally, DVDs also benefited from improved error detection and correction code. On a CD, EDC/ECC may take up as much as one-third of the available storage space. DVDs reduce this to approximately 13%, making more disc space available for data.

DVDs have such extensive storage that manufacturers often package additional content with their films. Dolby Digital surround sound, sound tracks presented in up to 8 languages, subtitles in up to 32 languages, as well as related content such as actor profiles and alternative endings can be easily accommodated by DVD storage. Some production companies even plant “Easter eggs.” These are hidden movie clips that are not on the index. You can explore the world of DVD Easter eggs at <http://www.dvdeastereggs.com>.

The DVD gained acceptance as a medium to distribute movies, but a wide array of applications soon followed for this high-capacity disc. Basic DVD formats were applied to the music industry (DVD-Audio) and read/write computer drives. DVD formats include DVD+RW, DVD+RAM, DVD-R, and DVD-RW, but not all of these formats are compatible. Successful playback of a DVD recording will depend on the type of disc, recording drive, and the playback device.

The DVD standard introduced massive storage capability using a laser beam that was more precise than that used to create CDs. Full-featured digital video was now possible on these discs but manufacturers were not satisfied with a mere 17 GB of storage. HDTV programming and video games could benefit from even higher capacities and a new form of laser made that possible. **Blu-ray** disc (BD), developed at Sony, holds 25 GB on a single side. These storage densities are possible because a blue-violet laser has a shorter wavelength than the red laser used to record DVD discs. The result: as much as 50 GB on dual-layer discs or about 9 hours of high-definition video and 23 hours of standard definition video on Blu-ray discs.

Solid-State Storage A **solid-state storage** device is a form of computer memory that contains no moving parts. Solid-state secondary storage is nonvolatile memory that can be both read and written to. The use of solid-state devices for secondary storage has grown dramatically as their capacity has increased and their cost has fallen. Common examples include USB **flash drives**, **memory cards**, and the built-in memory used in MP3 players, digital cameras, and mobile phones. The technology used in all these devices is called **flash memory** (Figure 3.17).

Flash memory is made up of a grid of cells, each of which contains two transistors. A very thin layer of insulating oxide separates the transistors. One serves as a *control gate*. The other is a *floating gate*. The insulating oxide layer traps any electrons present on the floating gate, preserving the electronic information with no need for external power. The charge of the floating gate, in turn, modifies the electric field of the control gate. The voltage of this field is then read to determine the bit value (0 or 1) of the cell.

Solid-state memory has a number of advantages. The absence of delicate mechanical parts makes solid-state storage more durable. They are smaller and weigh much less than their mechanical counterparts. Finally, solid-state devices use less power.



Figure 3.17 Solid-state storage devices have a variety of names. Memory stick, thumb drive, and travel disk are commonly used. The standard name is USB flash drive or “UFD.”

These benefits will lead to increasing use of flash technology for secondary storage. Mechanical storage is not likely to be completely replaced, however. Flash storage is more expensive than magnetic and optical storage, and the capacities of most flash devices are significantly smaller. But perhaps the biggest concern is that flash memory has a limited life expectancy. In general, the average flash drive lasts between 10,000 and 100,000 write/erase operations. Environmental damage, manufacturer defects, and human error also reduce the flash drive's life span. As a result, magnetic, and especially optical, devices are currently the preferred media for long-term storage.

Storage in the Cloud A popular alternative to secondary storage devices is to store and manage data on a remote server. Storage in the cloud has gained popularity with the increase in Internet access, mobile computing devices, and high bandwidth connectivity. **Cloud storage** is a service provided through a network (usually the Internet), either free or fee based, to back up, maintain, and manage data remotely. It offers convenient access to data from any place on any networked device. This portability and ubiquitous access has made such platforms as Google Docs, Apple iCloud, and Microsoft SkyDrive popular alternatives to secondary devices where data remains locally controlled and managed. Many providers of cloud services offer unlimited storage capacity and the ability to share data with other users. However, this storage service does raise security and reliability concerns. Without a consistent Internet connection, a user will not have ready access to the data. Protection of the data is subject to the practices of the provider. Should the cloud service go out of business, data recovery may be difficult. Despite the convenience of storing data on a remote server, multimedia developers should thoroughly research the reliability of the service provider before entrusting data to the cloud.

Input Devices for Multimedia Computers

Multimedia requires a variety of input devices to transmit data and instructions to a system unit for processing and storage. Keyboards and pointing devices, such as trackballs, touch pads, and touch screens, are central to interacting with graphical user interface (GUI) applications and operating system software. Other devices are necessary to input sound, video, and a wide array of images for multimedia applications. Some of these, such as microphones, are built into the system. Others, such as scanners, cameras, sound recorders, and graphics tablets, are plugged into USB or FireWire interface ports.

Scanners capture text or images using a light-sensing device. Popular types of scanners include flatbed, sheet fed, and handheld, all of which operate in a similar fashion: a light passes over the text or image, and the light reflects back to a **CCD** (charge-coupled device). A CCD is an electronic device that captures images as a set of analog voltages. The analog readings are then converted to a digital code by another device called an **ADC** (analog-to-digital converter) and transferred through the interface connection (usually USB) to RAM.

The quality of a scan depends on two main performance factors. The first is **spatial resolution**. This measures the number of dots per inch (dpi) captured by the CCD.

Consumer scanners have spatial resolutions ranging from 1200 dpi to 4800 dpi. High-end production scanners can capture as much as 12,500 dpi. Once the dots of the original image have been converted and saved to digital form, they are known as pixels. A **pixel** is a digital picture element.

The second performance factor is **color resolution**, or the amount of color information about each captured pixel. Color resolution is determined by **bit depth**, the number of bits used to record the color of a pixel. A 1-bit scanner only records values of 0 or 1 for each “dot” captured. This limits scans to just two colors, usually black and white. Today’s scanners capture 30 to 48 bits for each pixel. This delivers a wide range of color possibilities for each pixel, making it possible to produce high-quality digital versions of photographs, paintings, and other color images.

Scanners work with specific software and drivers that manage scanner settings. Spatial resolutions and bit depth can be altered for each scan. These settings should reflect the purpose of an image. For example, if an image is a black and white photo for a website, the scanning software can be adjusted to capture grayscale color depth (8 bit) at 72 dpi. This produces an image suitable for most computer monitors that display either 72 or 96 pixels per inch. Scanner software also has settings to scale an image and perform basic adjustments for tonal quality (amount of brightness and contrast).

Optical character recognition (OCR) is the process of converting printed text to a digital file that can be edited in a word processor. The same scanners that capture images are used to perform OCR. However, a special software application is necessary to convert a picture of the character into an ASCII-based letter. This OCR software recognizes the picture of the letter C, for example, and stores it on the computer using its ASCII code (01000011). These characters are then edited and reformatted in a word processing application. Many image scanners today are shipped with OCR software that can recognize basic text formations. Specialized applications, such as OmniPage or Readiris Pro, are optimized to deliver high-speed, accurate OCR results. The final success of any OCR conversion depends on the quality of the source material and the particular fonts used on the page. Small print on wrinkled, thin paper will not deliver good OCR results.

OCR scanning is one method of capturing text documents. Scanners are also used to create a PDF (Portable Document Format) file. The scanner captures a specialized image of the page and saves it as a .pdf file. Adobe Acrobat Reader is necessary to view the contents of a .pdf file. This file format is cross-platform compatible, so it is particularly suitable for distributing highly formatted documents over a network. OCR scanning creates a file that can be edited in any word processing application. PDF scanning, on the other hand, creates a specialized file format that can only be managed by Adobe Acrobat software.

Flatbed scanners are configured to meet a variety of uses. The scanner bed varies to handle standard letter- to legal-size image sources. Multifformat holders are available for 35mm filmstrips and slides (Figure 3.18). Some scanners have an optional sheet-feed

Need a larger image? Scale when you scan. Scaling during scanning captures more information from the original image. Scaling later, using an image-editing program, forces the computer to interpolate image information, producing a lower-quality enlargement.

ASCII is American Standard Code for Information Interchange, the basic digital code for alphanumeric symbols.



Figure 3.18 Slide and flatbed scanners.

device. For small production, these adapters to a flatbed scanner may suffice. For larger projects, more specialized scanners should be considered. Slide and film scanners are specifically calibrated to capture high spatial resolution, some at 4000 dpi. Sheet-fed scanners are built to automatically capture large print jobs and process 15 or more pages per minute. In selecting a scanner for multimedia development there are many considerations. Image or text source, quality of scan capture, ease of use, and cost all factor into choosing the right scanner.

Digital cameras are a popular input source for multimedia developers (Figure 3.19). These cameras eliminate the need to develop or scan a photo or slide. Camera images are immediately available to review and reshoot if necessary, and the quality of the digital image is as good as a scanned image. Digital capture is similar to the scanning process. When the camera shutter is opened to capture an image, light passes through the camera lens. The image is focused onto a CCD, which generates an analog signal. This analog signal is converted to digital form by an ADC

and then sent to a digital signal processor (DSP) chip that adjusts the quality of the image and stores it in the camera's built-in memory or on a memory card (Figure 3.20). The memory card or stick has limited storage capacity. Images can be previewed on the card, and if not suitable, deleted to make space for additional images.



Figure 3.19 Digital cameras have a variety of features including size, storage capacity, megapixel, and optical zoom ratings.

Digital camera image quality, like scanning, is based on spatial resolution and color resolution. Most consumer-grade digital cameras use 24-bit color resolution. This is quite adequate for most multimedia development. Professional digital cameras often use 42- or 48-bit color resolution, allowing them to capture a wider range of data for manipulation by image-editing programs.

A digital camera's spatial resolution is measured in the number of pixels captured by the CCD. Early digital cameras were 1 megapixel. This means the maximum image resolution is 1200 horizontal by 800 vertical ppi ($1200 \times 800 = 960,000$, or close to 1 million pixels). The physical size of the image depends on where it is viewed. If this image is viewed on a monitor at 72 ppi, the image will appear quite large: 16 by 11 inches. If printed at 300 dpi, the image will be 4 inches wide by 2.6 inches high (Table 3.6). These camera images are fine for web pages or sending email attachments, but they do not capture sufficient data to produce high-quality, photolike printouts.

Newer digital cameras capture resolutions of 10 to 15 megapixels. Higher pixel ratings mean more realistic printed photographs. They also mean larger file sizes. If the camera is set to capture the highest-quality image, the total number of stored images is reduced. Most cameras have adjustments to lower the resolution and capture more images on the memory card or stick.

Images are transferred to a computer from the memory card through a USB adapter, a memory card reader, or wirelessly through Bluetooth or Wi-Fi. Image catalog programs such as iPhoto help to manage digital images on secondary storage. These files can then be edited using programs such as Photoshop or PaintShop Pro to enhance quality, adjust size, or add special effects. The digital camera has brought great efficiency to multimedia development. The costs of film, development, and time are reduced by digital source capture. It has also introduced a new level of creativity to the photo-editing process as developers take advantage of editing software to enhance and combine the digital photos.

Digital video (DV) cameras are another important input device for developers (Figure 3.21). Before DV cameras became effective and affordable, developers captured video in




Figure 3.20 Memory cards for digital cameras.

Dots vs. Pixels

Spatial resolutions are measured in *dpi* for print material and *ppi* for electronic display.

Table 3.6 Comparison of Selected Megapixel Ratings and Image Sizes

4 Megapixel	6 Megapixel	8 Megapixel	12 Megapixel
2700 h \times 1704 w = 4,600,800 total pixels	3008 h \times 2000 w = 6,016,000 total pixels	3266 h \times 2450 w = 8,001,700 total pixels	4290 h \times 2800 w = 12,012,000 total pixels
Viewed @ 72 ppi = 37.5" \times 23.6" image size	Viewed @ 72 ppi = 41.7" \times 27.7" image size	Viewed @ 72 ppi = 45.3" \times 34.0" image size	Viewed @ 72 ppi = 59.5" \times 38.8" image size
Printed @ 300 ppi = 9" \times 5.6" image size	Printed @ 300 ppi = 10.02" \times 6.67" image size	Printed @ 300 ppi = 10.88" \times 8.16" image size	Printed @ 300 ppi = 14.30" \times 9.34" image size



Figure 3.21 Digital video camera.

analog format. Analog video was played through a VCR to a video-capture board where the analog signal would be converted to digital format and stored on the hard drive. DV cameras eliminate that conversion process. Full motion capture is stored on a built-in hard drive, a tape, DVD, or memory card. DV cameras often have a FireWire interface to transfer a digital movie to other devices. Using applications such as Apple Final Cut Pro or Adobe Premiere, developers can edit and enhance the video in a wide variety of ways.

The performance of a DV camera is determined by several factors. The first is the method used to capture video data. Professional-quality video requires a 3-chip camera. These cameras have a separate CCD for each channel of red-green-blue (RGB) color. One chip captures the full

range of reds, another greens, and the third blues. These three separate channels yield high-quality color. Less expensive consumer DV cameras use a single CCD and rely on sharpening algorithms to reproduce three channels of color. This tends to oversharpen the image and add artifacts to the moving images. While consumer DV cameras are an affordable means of capturing video footage and may suffice for some multimedia applications, a professional project will require the more expensive 3-chip cameras.

Lens and zoom quality are also important for high-quality capture. An inferior lens affects the camera's ability to reproduce color and capture sharp images. DV and still-image cameras feature **digital zoom**. This simulates the effect of a stronger telephoto lens by digitally enlarging and cropping an image. Digital zoom inserts additional pixels based on an analysis of the original image, in effect creating a "best guess" enlargement. Digital zoom is not a good substitute for high-quality optical zoom lenses that faithfully capture the details of the original image.

Most standard consumer DV cameras also have built-in automatic-exposure features, image stabilization (to compensate for the shaky hand), and preprogrammed modes that adjust video for backlit scenes, sports photography, snow, or spotlight scenes. A retractable liquid crystal display (LCD) screen displays the video and can be an alternative to using the eyepiece to frame a shot. Many consumer DV cameras also have a still-capture media card and can be used to take photographs, though usually at lower resolutions than a digital still camera.

Sound capture devices transform analog waveforms into digital files. Microphones are built into many computers and are useful for capturing voice commands and recording directly into applications such as PowerPoint. Built-in microphones, however, can introduce interference and are not suitable for high-quality capture. Developers often connect high-quality microphones directly to the computer's audio-capture port for better results. CD and tape players can also be plugged into a sound-capture board through the audio port. An ADC translates the analog sound wave into a digital file. Sound-editing software, such as Sound Forge or Audacity, can then be used to remove unnecessary segments, enhance sound quality, or add special effects.

Graphics tablets have a flat drawing surface for freehand image creation (Figure 3.22). The artist uses a stylus to draw on a pressure-sensitive surface. Software interprets the

stroke pressure to control density and color, reproducing the artist's drawing as a digital image. Tablets are also useful for tracing existing art. Many developers work with graphics tablets because of the intuitive drawing control they provide. The digital artwork they produce can then be directly manipulated with popular image-editing programs such as Photoshop or Corel Draw.

Multimedia Output Devices

Computer output devices present processed data in a useful form. Output devices include screen displays, audio speakers or headsets, and hard copy. The quality of output for display, sound, and print is dependent on the performance features of these devices.

Display Devices *Display devices* share their heritage with either cathode ray tube (CRT) technology used in analog televisions or liquid crystal displays (LCD) first used in calculators and watches. Both CRT and LCD technologies produce an image on a screen through a series of individual picture elements (pixels). As in scanners and digital cameras, the quality of a display image is largely determined by spatial resolution (the number of pixels) and color resolution (the bit depth of each pixel).

CRT monitors use raster scanning to generate a display. In this process an electronic signal from the video card controls an electron gun that scans the back of a screen with an electronic beam. The monitor's back surface is coated with a phosphor material that illuminates as electronic beams make contact. The electronic signal scans horizontal rows from the top to the bottom of the screen. The number of available pixels that can be illuminated determines the spatial resolution of the monitor. For example, a CRT with 1024×768 spatial resolution can display well over 700,000 pixels (Figure 3.23).




Figure 3.23 Raster scan CRT creates images through electron beams that illuminate a phosphor coating on the back of the monitor screen. RGB color monitors have three beams to illuminate red, green, and blue phosphors. See Color Plate 4.



Figure 3.22 Artists and designers use graphics tablets and a stylus pen to input drawings for further editing.

24- and 32-bit Color

24-bit color assigns 8 bits to each of three color channels—red, green, and blue. This produces 256 variations for each channel and 16.7 million colors for their combination ($256 \times 256 \times 256$). The extra 8 bits in 32-bit color does not produce more color options. Instead, this is an “alpha channel,” used to specify the transparency of each pixel.

Color resolution, or bit depth, is the second factor to influence display device performance. The number of bits per pixel determines the range of possible colors that are displayed. The video card controls bit depth. Video cards convert computer data to an electronic signal that illuminates the pixels. An 8-bit color monitor has a range of 256 color possibilities (2^8). This is sufficient for text and simple graphics, but a wider range of colors is needed for more sophisticated graphics and video. Current video cards generate 24- to 32-bit color, supporting 16.7 million colors.

CRT technology is now replaced with smaller, lighter-weight, fully digital displays that use a different technique to create pixels. An **LCD** screen is a sandwich of two plastic sheets with a liquid crystal material in the middle. Tiny transistors control rod-shaped molecules of liquid crystal. When voltage is applied to the transistor, the molecule is repositioned to let light shine through. Pixels display light as long as the voltage is applied. Laptops borrowed this technology and improved its resolution, color capability, and brightness to make LCDs suitable for computer display.

Laptop computers employ an **active matrix** screen that uses **thin film transistor (TFT)** technology. TFT displays assign a single transistor to each liquid crystal cell to control the color and light that compose a pixel. Each pixel on the LCD is a bundle of subpixels (red, green, and blue) that are combined to generate the array of colors.

Resolution and brightness impact the quality of LCD output. LCD screens have specific resolutions controlled by the size of the screen and the manufacturer. This fixed-pixel format is referred to as the *native resolution* of the LCD screen. A 15-inch LCD screen has a native resolution of 1024×768 pixels: there are exactly 1024 pixels in each horizontal line and 768 pixels in each vertical line for a total of 786,432 pixels. Altering the resolution to lower settings, 800×600 for example, reduces the output quality. Most LCDs use an expansion technique to fill the screen with the image at a lower resolution. Pixels are either doubled, producing a chunky effect, or added using interpolated colors, resulting in a blurred effect. Either way, the quality of the image is compromised. LCD screens should remain in their native resolution for best results. The brightness of light that shines through the screen is also significant in overall output quality. Brighter screens display richer graphics.

LED (light-emitting diode) displays have moved from large TV screens to mobile phones, tablets, laptops, and desktop screens. These displays use the same TFT display technology as the LCDs. A major distinction is in the manner of providing the light source to illuminate the pixels on the screen. LCD displays use a fluorescent lamp as the light source to project the colors through polarized liquid crystals. A single fluorescent tube, smaller than a pencil, provides a bright white light that is diffused across the back of the display without increasing the temperature of the panel. LED screens use a single row of light-emitting diodes to make a brighter backlight that significantly improves the quality of the monitor display. There are several advantages that come from altering the method of backlighting the liquid crystals. LED monitors offer more intense lighting and finer color resolution to deliver a more natural color experience. They use on average 40% less power than the LCD display, preserving battery life for mobile devices. Finally, the LED

display has a sharper image from any angle, unlike the LCD display that is best viewed directly in front of the monitor (Figure 3.24).

Sound Devices *Speaker systems* are essential components of modern computers. Most early microcomputers restricted sound output to warning sounds such as a loud beep when there was an error message. Macintosh computers raised the bar on sound output when the first Mac introduced itself to the world in 1984. A computer that could speak changed the prevailing belief that all computer information needed to be in visual form. Sound capability soon became a requirement for a multimedia computer.

Sound output devices are speakers or headsets. They are plugged into the soundboard where digital data is converted to analog sound waves. Soundboards can be a part of the system board or added to a computer's expansion slots. Soundboard circuitry performs four basic processes: it *converts* digital sound data into analog form using a digital-to-analog converter, or **DAC**; *records* sound in digital form using an ADC; *amplifies* the signal for delivery through speakers; and *creates* digital sounds using a synthesizer. A

synthesizer is an output device that creates sounds electronically. Synthesizers may be built into the computer's soundboard or added later, usually as a card mounted in one of the system's expansion slots. The most common standard for creating digital music using a synthesizer is MIDI (Musical Instrument Digital Interface). MIDI specifies the format for musical commands, such as striking a piano key. The computer sends these commands to the synthesizer, which then creates the appropriate sound.

Sound quality depends on the range of digital signals the soundboard can process. These signals are measured as sample size and rate. *Sample size* is the resolution of the sound measured in bits per sample. Most soundboards support 16-bit sound, the current CD-quality resolution. *Sample rate* measures the frequency at which bits are recorded in digitizing a sound. Modern boards accommodate the 48 KHz sample rate found in professional audio and DVD systems. Soundboards control both sound input and output functions. Input functions are especially important for developers because they need to capture and create high-quality sounds. End users are concerned with output; they want high-quality sound for games, movies, and digital music.

Print Devices *Printers* remain an important multimedia peripheral device, despite the fact that multimedia applications are primarily designed for display. Storyboards, system plans, schematics, budgets, contracts, and proposals are just a few common documents that are frequently printed during multimedia production. End users print images and web pages, as well as the standard text documents associated with most computer applications.

There are two basic printing technologies: impact and nonimpact. *Impact printers* form images and text by striking paper. **Dot-matrix** printers use a series of pins that strike the paper through an inked ribbon. These printers are used for applications that



Figure 3.24 LED screens use a row of light-emitting diodes to backlight the display, resulting in better clarity, resolution, and color.

require multiform output or high-speed printing. They are easy to maintain and relatively inexpensive to operate. However, limited color and graphics capability, combined with high noise levels, make impact printers undesirable for most printing needs.

Nonimpact printers form printed output without physically contacting the page. These devices include inkjet, photo, and laser printers. **Inkjet printers** are used in many homes and businesses. They are affordable, quiet, and versatile: inkjets can print everything from labels and envelopes to photo-quality color images. An inkjet printer is a line printer. The print head moves across the page, one line at a time, spraying drops of ink. Different techniques are used to produce the ink spray, but the most common is the “bubble” jet method first implemented in 1977 by Cannon and later adopted by Hewlett-Packard (HP). As the ink cartridge moves across the paper, heat is applied to tiny resistors on the metal face of the print head. The surface of the ink boils, producing a vapor bubble. This bubble forces ink through a nozzle and onto the paper (Figure 3.25).

Inkjet output quality is determined by printer resolution and type of paper. Printer resolution is measured in dpi. The drop of ink is a dot. An image printed at 200 dots per inch will have more ink applied than one printed at 100 dots per inch. Inkjet printers can support optimized resolutions of 4800 dpi. Because the inks tend to blend together on the paper before they dry, inkjet printers can achieve higher-quality output with fewer dpi. Setting the print resolution to 200 dpi will deliver a reasonably good photograph and also reduce ink consumption.

Inkjet papers vary in surface texture. Glossy photo paper is used to transform digital images into printed photos, while matte finish paper can produce colorful reports.




Figure 3.25 Inkjet printers spray dots of colored ink to form an image. See Color Plate 5.

Papers with linen or cotton fibers and textured papers will bleed where ink is applied. For best results, use paper specifically designed for inkjet printers.

Printer speed is measured in pages per minute (ppm). Inkjet printers average 20 ppm. Color printing is much slower than black and white output. A typical black-and-white speed is 18 ppm, whereas color output slows to 12 ppm.

Although most inkjet printers are very affordable, the cost of consumables can be high. Print cartridges are expensive to replace (Figure 3.26). Expect to replace color cartridges frequently if the output is full-size color photos. Specialty papers for high-gloss photos are also expensive. Paper and ink costs should be factored into the decision to use inkjet printing for multimedia production.

A **photo printer** is a color printer specifically designed to produce photos (Figure 3.27). The best photo printers can deliver photo lab-quality output. Many consumer photo printers are based on inkjet technology. These printers use a media card from a digital camera and have a push-button panel to set the size, quality, and number of copies. Images do not have to be transferred to a computer before they are printed. This increases the ease and speed of sharing digital pictures. Some inkjet printers are configured as both a standard and photo printer by adding a media card slot and panel controls to manage the photo printing. More expensive photo printers use dye sublimation technology for output. **Dye sublimation** uses heat to transfer colored dye to specially coated papers. These printers are found in professional settings such as photography studios and digital imaging labs.

Laser printers use a copier-like technology to fuse text and image to the paper. They are called *page printers* because the entire page is transferred to the printer's electronic storage before it is formed on paper.

Laser printing begins with document transfer to the printer's electronic storage. A laser beam then scans an **optical photo-conductor (OPC)** drum, placing a negative electrical charge where text and images should appear. Toner, a form of powdered ink, is attracted to these charged areas. When paper moves through the printer, it passes under the OPC drum, which deposits the toner. Other rollers add heat and pressure to fuse print material on the page. Because lasers print an entire page at once, they are faster than inkjet printers.

Laser printers have resolutions of 600 to 2400 dpi. Common print speeds range from 20 to 45 ppm. Laser printers are very popular in offices with large black and white print jobs where quality and speed are imperative. For years, inkjet printers held the advantage of color over a standard laser printer. Color laser technology is now delivering high-quality color output at reasonable costs.



Figure 3.26 Inkjet cartridges.



Figure 3.27 Photo printers can crop, enlarge, and enhance the image before printing on special photo paper.

Color laser printers add cyan, magenta, and yellow toners to traditional black. Applying additional toners slows printing speeds. The laser scans each color separately to the OPC drum, making a separate pass of the drum to collect each color for the entire page. Early printers moved the paper past the drum each time to collect a particular color, but the constant movement of paper back and forth through the printer rollers often misaligned the color output. Now one-pass color lasers simply move the drum four times around to collect toner for each color and then pass the paper once to transfer the final colored image. Color laser printers are significantly slower than standard black and white lasers because there is extra processing for each color.

Color laser printers require large electronic storage capacity. A full-page, 600-dpi color image may require over 16 MB of printer storage. If the printer cannot form the entire page in memory, it will only print the portion it can store. In some cases, insufficient memory produces an error message and the page is not printed at all. Color laser printers should have from 128 MB to 512 MB of primary storage.

Considerations for Selecting a Printer

- Resolution (measured in dpi)
- Speeds (measured in ppm)
- Cost of the printer
- Cost of consumables (paper, inks, toner)
- Paper-handling features (duplexers, envelopes, labels, legal, continuous paper forms)
- Built-in memory capacity (more is always better)
- Computer and network interface (USB, parallel, Ethernet capable)
- Maintenance requirements (service contracts, cleaning requirements, operating environment)

Laser printers are desirable output devices because they have high-quality and high-speed output. However, these printers are expensive to operate. Operational expenses include toner cartridges, service contracts, and paper. Laser printers also require special environmental conditions. Excessively dry or damp atmospheres will affect printer operation. Many multimedia development offices share laser printers through network connections, reducing the cost to individual users. Most laser printers have built-in network cards for Ethernet LANs (local area networks).

In addition to standard printers, there are other print devices for specialized applications. Plotters, portable printers, and label printers are just a few. A hybrid device that combines printer, scanning, fax, and copier technology in one unit is called a

multifunction printer. This single unit saves desk space and eliminates the need for purchasing separate output devices. All printing devices utilize either the basic impact or nonimpact methods. When selecting printers for multimedia development, consider the purpose of the output and the media to print. If documents are text-based reports for staff members, high-quality, expensive printers may not be necessary. If the media is detailed images for production design, then a printer with high color resolution is important.

3.4 Networks

Multimedia projects may require input from many individuals working independently on their personal computers. The integration of this work requires a network of computers. A **network** is a collection of computers connected through a communication link to share hardware, data, and applications. Networks also allow individual processors in each computer to work simultaneously on a single task. Complex rendering projects for animation sequences are frequently done with an array of networked computer proces-

sors called a “render farm.” Networks are the backbone that ties together the work of individual developers and the resources of their personal computers.

Computer networks are categorized as *WAN* (wide area network) or *LAN* (local area network). The **WAN** connects computers over a wide geographic region using the communication lines of an outside service provider such as a telephone or cable company. A developer can transfer digital files via email attachments or use *file transfer protocols* (FTP) to add digital files to a remote network server. In both cases, the computer connects to other systems through external communication links.

The **Internet** is a special form of WAN. It is a network of networks that uses Transmission Control Protocol and Internet Protocol (**TCP/IP**) to send data from one computing device to another. **Protocols**, or rules for transmitting data, control the transfer and addressing of data between each host computer. The Internet started in 1969 as a government research project with four computer systems interconnected to share system resources. Twenty years later, the Internet exploded with possibilities when Tim Berners-Lee developed the HTTP (hypertext transfer protocol) protocols for the **World Wide Web (WWW)**.

The Web introduced interactive multimedia to the Internet. Web pages, written in *HTML* (Hypertext Markup Language), display multimedia through a browser such as Internet Explorer or Safari. **Hyperlinks** connect resources from one web page to another location. Hyperlinks are defined with a **uniform resource locator (URL)** that identifies the path to an Internet resource such as an image, web page, or video file.

The efficiencies of the Web are in its *client/server* model for distributing data. **Server** computers store and send data to a client computer. **Client** computers have software to open and process data files. Once data is downloaded from the server, applications on the client computer, such as browsers and plug-ins, display or play data content. Client computers process data locally, which is more efficient than processing it on a server computer shared by thousands of users.

Special data file formats are necessary to ensure data is compatible on any client system. For example, image files include .jpg, .gif, or .png format and text files use .html or .pdf format. Incompatibilities between computer platforms and data file formats are slowly disappearing through the network connections and protocols of the World Wide Web.

<http://www.jblearning.com/about/overview/>
This URL identifies the http protocol, the host computer (jblearning), the domain (.com), and the path to a specific document resource on that host (/about/overview/).

A **LAN** is a series of computers connected within an organization. Many homes now have a LAN to share printers and access to the Internet. Multimedia developers connect computers to distribute files, access applications from a local server, or share hardware devices. Computers on a LAN can be connected using twisted pair cable that resembles a phone line, although wireless connectivity is increasingly common.

Ethernet is a common set of protocols to control the flow of data on a LAN. Ethernet defines how files are transferred, the speed of transfer, and the cables used to connect the computers. Many LANs are using wireless connections as computers become more mobile and users desire flexible network access. A wireless network requires an **access point** (AP) that broadcasts a radio signal within a cell area. The AP often contains a firewall to prevent unauthorized wireless network access. The AP is connected to a larger network system through a cable modem or **router** (a switch to control data flow on a

network). Computers need a wireless card or built-in wireless capability to send and receive data via radio waves.

Wi-Fi and Bluetooth are two popular wireless LAN standards. The **Wi-Fi (wireless fidelity)**, or 802.11b standard, transmits on 2.4 GHz radio frequencies. Transmission rate is 11 Mbps up to 300 feet away from the AP. Distance, interference, and number of users can adversely affect the transmission rate. Frequent upgrades to this standard introduce higher bandwidth and increased reliability of data transfer within the 2.4 GHz frequency range. The 802.11g provides bandwidth up to 54 Mbps and 802.11n introduces newer transmission techniques to achieve up to 100 Mbps. The **Bluetooth** protocol was developed in 1994 to communicate between devices within 30 feet at 1-Mbps speeds. Bluetooth is designed to transfer data between nearby computers and PDAs, or to communicate with a nearby printer or other peripheral device.

Networks have increased the power of individual computers and expanded the efficiency of computer users. Networks are also instrumental in fulfilling the visions of Bush and Nelson to build "trails" from one data point to another.

3.5 Summary

Computers are manufactured in many sizes and platforms. Mainframe and supercomputers are used in organizations with high volumes of data and complex processing requirements. Personal computers use microprocessors to bring computing power to the desktop of both multimedia developers and end users. Personal computers are defined by their platform, the combination of hardware and operating system they use. Multimedia developers must consider the development platform that meets their project requirements, as well as the delivery platform, the computer system available to potential users.

All computer hardware systems share the basic functions of input, processing, storage, output, and transmission of data. The system unit, consisting of the CPU, primary memory, expansion ports, and the circuitry that connects them, provides the foundation for processing digital instructions and data. Peripheral devices support processing through input and output interfaces on the system board. Hard drives, CD and DVD drives, and solid-state media are common peripheral devices that support the main processing activity by storing software and data for later processing. Large capacities of permanent, portable storage are necessary to deliver the applications expected of today's multimedia computers. Networks unite computer hardware making it possible to share and distribute media within local organizations or over wide geographic areas.

The evolution of multimedia hardware is far from complete. New devices appear daily. The marvel of the digital computer is its scalability and adaptability. Computer microelectronics move ever-larger volumes of data at ever-increasing speeds. Processors transform those bits into wondrous images and sounds. But even the most advanced hardware is simply a collection of components awaiting instructions and data from a user. Software, the subject of the next chapter, transforms electronic computers into useful tools to create and manage an increasingly interconnected world of digital multimedia.

Key Terms

Access point
Access time
Active matrix
ADC
Address bus
Arithmetic logic unit (ALU)
ASCII
Bit depth
Blu-ray
Bluetooth
Bus
Cache
Constant angular velocity (CAV)
CCD
CD-DA
CD-R
CD-ROM
CD-RW
Client
Clock speed
Cloud storage
Color resolution
Computer platform
Computer system
Constant linear velocity (CLV)
Control unit
CPU
Cross-platform compatibility
CRT
DAC
Data bus
Digital zoom
Dot-matrix printer
DVD
Dye sublimation
Ethernet
FireWire
Flash drive
Flash memory
Frame
Hard drive
Hardware interface
Hyperlinks
Inkjet printer
Instruction set
Interface ports
Internet
LAN
Land
Laser
Laser printer
LCD
LED
Machine cycle
Magnetic storage
Mainframe computer
Memory card
Microcode
Microcomputer
Microprocessor
Mobile computing platform
Multicore
Multifunction printer
Multiprocessing
Multitasking
Nanotechnology
Network
Optical character recognition (OCR)
Optical photoconductor (OPC)
Optical storage
Parallel data transmission
Parallel processing
Peripheral devices
Personal computer (PC)
Photo printer
Pipelining
Pit
Pixel
Primary memory
Protocols
Random access
Random access memory (RAM)
Raster scan
Read-only memory (ROM)
Registers
RISC
Router
Scanner

Secondary storage	TCP/IP
Sector	Thin film transistor (TFT)
Serial data transmission	Thunderbolt
Server	Track
Session	Transfer rate
Solid-state storage	Uniform resource locator (URL)
Spatial resolution	Universal Serial Bus (USB)
Storage capacity	USB 3.0
Supercomputer	WAN
Synthesizer	Wi-Fi
System board	Word size
System bus	World Wide Web (WWW)
System unit	

Resource

Taylor, Jim. 2005. DVD Frequently Asked Questions (and Answers). *DVD Demystified*. <http://www.dvddemystified.com/>

Review Questions

1. What are the differences between a supercomputer, mainframe, and microcomputer?
2. What are the two main components of a computer system?
3. Why should a multimedia developer be concerned about cross-platform compatibility?
4. What are the two main categories of computer hardware? Explain the function of each.
5. Why is the system board an essential component of the system unit?
6. What are the three main sets of transistors on a microprocessor chip? Identify the main purpose of each set.
7. How do clock speed and word size determine the performance of a CPU?
8. What is the advantage of a 64-bit address bus over a 32-bit bus?
9. What are the differences between and uses of RAM and ROM?
10. How does cache memory improve the overall performance of a processor?
11. What are the similarities and differences between USB and IEEE 1394 interfaces?
12. Why is the transfer speed of the hardware interface important to a multimedia user and developer?
13. What are the magnetic storage options for portable media?
14. How do pits and lands on an optical disc store digital data?
15. What is one advantage and one disadvantage of the CLV method of data storage?
16. Why does the V in DVD currently stand for *versatile*?
17. Why can DVDs store more data than CDs?
18. What are three input devices that would be useful for a graphics artist?


19. What are the three computer display technologies? Identify a major distinction of each.
20. What is an advantage and disadvantage of each of the following printer categories: inkjet printer, laser printer, photo printer, and color laser printer?
21. What is the distinction between a WAN and a LAN?
22. What features did the WWW introduce to the Internet?
23. What are the essential similarities and differences between Wi-Fi and Bluetooth?
24. Why is the Internet a special form of WAN?
25. Why is the client/server arrangement an efficient use of the server's processor and the network's bandwidth capacity?

Discussion Questions

1. Recommend four essential system unit performance features a video developer should consider when purchasing a computer to import, edit, and store digital video.
2. Identify the five main uses of secondary storage and recommend a storage medium for each one to manage 900 MB of digital sound.
3. What are the three major categories of secondary storage devices? List the main advantages and disadvantages of each.
4. Do you think CD-RW/DVD drives will soon replace magnetic external storage devices? Explain your position.
5. As a video editor on a multimedia production team, what type of secondary storage would you use for composing and editing the digital video? Explain your choice.
6. Many organizations are storing all their vital data on cloud storage services. Do you think this is a good idea? What are the most important issues to consider? Support your answer with web research on these issues.
7. Locate a recent ad for a flatbed scanner and describe the performance features of that scanner.
8. Locate a recent ad for a digital camera and describe the performance features of that camera.
9. Will solid-state storage soon replace magnetic storage? Explain your position.
10. Research how render farms are used to develop digital animation sequences and report your findings.
11. Research two cloud storage providers and compare the features of each. Identify specific provisions each makes for the security and privacy of your data.
12. Review the vision of Vannevar Bush and Ted Nelson and determine if today's networks and search engines are fulfilling their vision. Explain why they are or are not.

Chapter 4

Computer Software



Topics you will explore include:

- Main Categories of Software
 - Operating Systems
 - Programming Languages
 - Applications
- Functions of the Operating System
 - User Interface
 - Hardware Management
 - Program Execution
 - File Management
- Types of Programming Languages
 - Low-Level Languages
 - High-Level Languages
 - Object-Oriented Languages
 - Visual Programming Languages
- Software for Multimedia Development
 - Media-Specific Applications
 - Authoring Applications
 - Media Utilities

A computer is a blend of physical components, or *hardware*, and sets of instructions, or *software*. This chapter presents the essentials of the different types of software that make multimedia development and delivery possible. After completing this chapter you should understand:

- The three main categories of software
- The functions of operating systems
- The main types and uses of programming languages
- The different types of software used to develop multimedia products

4.1 Categories of Software

Software is the collection of computer programs that govern the operation of a computer system. A **program** is a list of instructions that can be carried out by a computer. Without software, a computer can do nothing. With the appropriate software, computers can perform virtually any information-processing task. There are three main categories of software. *Operating systems* are software that control hardware devices and basic system operations. Programs that perform specific tasks are *applications*. *Programming language* software is used to create other software programs. Each of these three types of software has important uses in multimedia computing.

4.2 Operating Systems

Operating systems are taken for granted by most users. We power on the computer and quickly launch into a favorite application. Yet without the operating system there would be no access to hardware, applications, or data. The **operating system** is a collection of programs that provide a user interface, manage the computer's resources, and execute application programs. The user interface facilitates interaction with the computer system. Computer resources such as memory, central processing unit (CPU), printers, and disk drives are hardware components managed by the operating system. The operating system also manages and executes application software such as Photoshop or Excel. Operating systems are vital to making the computer a useful tool.

Operating systems vary from one computer platform to another because different platforms use different hardware. Versions of Windows manage hardware specific to the PC. OS X is an operating system designed for the hardware used in the Macintosh computer platform. Other operating systems such as Unix and Linux are multiplatform systems because they are easily adapted to control hardware from different manufacturers. While there are many operating systems on the market, all perform the same basic functions. Multimedia developers rely on the operating system to provide an intuitive, easily navigated user interface; to manage a wide range of hardware devices; and to control the operation of many different application programs.

User Interface

The **user interface** provides a means to communicate with the programs and hardware of a computer system. The user interface may consist of commands typed into the

operating system directly, or it may be a series of icons and menu bars. Early computers used commands to manage computer operations. This *command-line interface* required knowledge of a specific command language and precise attention to syntax: misplace a comma or make a spelling error and the command would not execute. The command language interface discouraged widespread use of computers because it was neither intuitive nor forgiving.

Visionaries such as Douglas Engelbart and Alan Kay recognized the limitations of this interface. Their ideas helped to shape the first graphically controlled computer, the Alto, developed in 1973. Alto presented computer functions in windows where an operator could manipulate a mouse to visually control objects like papers on a desk. This early research into graphical computing paved the way for Steve Jobs to develop the first GUI (graphical user interface) for the Lisa computer. This operating system was revised in 1984 for the Macintosh, which used a desktop metaphor complete with folders, clipboard, and trash can to control complex hardware functions. The operating system was slowly adapting to the way people work and freeing the user from learning arcane computer commands.

The graphical user interface is standard in operating systems today. A **GUI** (or “gooey”) presents the functions of the operating system as a series of icons, pull-down menus, and dialogue boxes. “Point and Click” and “Drag and Drop” now provide users with easily learned, intuitive procedures to control complex computer systems. This interface is now extended to more than mouse pointers and clicking, as the mouse is being replaced with one or more fingers. Often referred to as multitouch, this form of **NUI** (natural user interface) offers more intuitive control of the operating system. **Multitouch** is a method of input that allows one finger or multiple fingers to manipulate the computer interface. It is one expression of a wider form of natural user interface that allows direct input to the operating system without an intervening tool such as a mouse or stylus pen.

Touchscreen technology to control electronic devices was first introduced in the late 1960s by IBM. Both hardware and operating systems have advanced dramatically since then to include single-touch action and multifinger manipulation of screen images. A 1991 publication by Pierre Wellner that described a “Digital Desk” first formalized multitouch and pinching motions to control the screen display. Apple acquired the technology in 2005 for use with the iPhone. It became immediately popular in the mobile device market. The tabletop touch interface used by Microsoft is another expression of NUI. Introduced in 2001, this interface not only recognizes touching by multiple fingers, but also recognizes certain devices, such as a digital camera or a cell phone, placed on the surface. As tablet computers and e-readers proliferate, users will increasingly rely on a user interface that doesn’t require an external input device. Multimedia developers can now unleash a new wave of creative products that take advantage of natural user interfaces.

Managing Computer Resources

Operating systems control a variety of computer resources including processors, memory, peripheral devices, and networks. In many cases, the operating system (OS) performs its tasks behind the scenes with little or no user interaction. In other cases, the operating



Figure 4.1 The Macintosh option to select monitor properties built into the operating system.

system may provide special programs, called *utilities*, to assist users in more directly controlling operating system functions (Figure 4.1).

The OS and the Processor

Operating systems control how programs are executed in the processor. Some processors are so powerful they can support many users simultaneously. Multiuser operating systems control the amount of processor time each user's program will have. This process is also called **timesharing** because the operating system allocates "slices" of processor time to multiple simultaneous users. First one user, then another, will be given a few microseconds of the processor's time. Multiuser systems are also multitasking. **Multitasking** is the ability of the operating system to manage more than one application concurrently.

Each user can be executing different programs to complete different tasks and all will appear to be running at the same time.

A *microsecond* is one-millionth of a second.

Multiuser systems are found on midrange, mainframe, and supercomputers. These systems can support hundreds or thousands of users at one time. However, if a sudden increase in users occurs, everyone will notice a slowdown in computer performance because each user is competing for a "slice" of the processor's activity. Unix and Linux are common multiuser operating systems.

Operating systems for microcomputers such as the Macintosh and the PC are designed to support a single user. Microcomputer operating systems also support multitasking. Multitasking is particularly important for multimedia developers because they often work with several programs at once. Earlier microcomputers frequently crashed because the operating system lacked control over application execution. Multitasking often caused systems to "freeze" because one application monopolized computer resources and failed to release control to other applications. *Preemptive multitasking* gives the operating system additional control over system resources. The operating system can interrupt an application process and pass control to another program. The operating system can also regain control if one of the running applications suddenly stops. This results in more stable performance when multiple applications are open.

The OS and Memory Management

Memory management is another important function of every operating system. The operating system controls how much memory is accessed and used by application programs (Figure 4.2). Operating systems monitor use of memory and release memory when the processor no longer needs it. With today's multitasking environments, it is important to have the operating system allocate memory effectively among multiple programs. There is a finite amount of installed RAM and it is easy to fill it up with several open applications and large data files.

Virtual memory is a method to expand the amount of memory available for processing tasks. The operating system identifies a portion of the hard disk to simulate RAM. The operating system then swaps program segments between RAM and the hard drive through a process called *paging*. While this swapping process may slow down processing time, it does make it possible to run large applications on a limited amount of RAM storage.

Virtual memory is sometimes helpful in multimedia development because it may make it possible to run several programs concurrently on a computer with insufficient RAM. However, virtual memory complicates and slows processing and is no substitute for RAM. The preferred solution to main memory shortages is always more installed RAM.

The OS and Peripheral Devices

Operating systems also include a number of programs to control peripheral devices such as monitors, printers, keyboards, mice, and storage devices. These programs are shipped with the computer system or later added as device drivers. **Device drivers** are programs that tell the operating system how to communicate with a peripheral device. When a new device such as a scanner is added, the operating system must be able to recognize and manage that device. Many of these peripheral devices are easily installed with advances in “Plug and Play.” The operating system senses that a new device is plugged into an interface and automatically configures the system to support it.

In cases where the operating system does not automatically recognize the device, it may be necessary to install a device driver. For example, some operating systems do not recognize certain printers as “Plug and Play” until the correct driver is added to the operating system.

Managing Network Resources

The widespread use of microcomputers on networks requires operating systems to manage the access and security of networked computers. The operating system provides options to share files with other users on the network as well as connect to network servers and printers. Operating systems include commands to connect to wide area networks (WANs) as well as local area networks (LANs) (Figure 4.3). They also manage access to wireless



Figure 4.2 Activity Monitor in OS X displays CPU and memory usage.



Figure 4.3 Network configuration for TCP/IP connection.

networking. Current microcomputers and mobile devices have operating systems that can be configured to detect and connect to Wi-Fi (or AirPort) and Bluetooth networks.

Networks are particularly important for advanced multimedia development in which teams of specialists need rapid access to planning documents and media files prepared by their colleagues.

OS Utility Programs

In addition to managing hardware devices to carry out basic system operations, operating systems also include various utility programs (Figure 4.4). **OS utility programs** provide tools to optimize operating system functions. Disk management tools are a common utility set. These programs include disk repair, disk defragmentation, disk partitioning, and backup routines. Other common utilities are programs to write CDs and DVDs, view graphics files, uninstall programs, and set up screensavers. The file manager is also an important utility that provides a graphic interface to managing data on secondary storage.

Most current operating systems bundle multimedia utilities such as basic image editing, photo management tools, speech recognition, and sound controls. The Mac OS is thoroughly integrating multimedia data in its operating system with a series of utilities that includes iTunes, iMovie, and iPhoto, as well as the popular QuickTime program. Windows operating systems include Media Player for Internet radio and MP3 files, Movie Maker, and built-in drivers to transfer images directly from a digital camera or scanner.

Name	Size	Kind
Activity Monitor.app	10.3 MB	Application
Adobe AIR Application Installer.app	840 KB	Application
Adobe AIR Uninstaller.app	157.1 MB	Application
Adobe Installers	--	Folder
Adobe Utilities	--	Folder
AirPort Utility.app	34.6 MB	Application
AppleScript Editor.app	17.7 MB	Application
Audio MIDI Setup.app	11.8 MB	Application
Bluetooth File Exchange.app	1.8 MB	Application
Boot Camp Assistant.app	9.5 MB	Application
ColorSync Utility.app	12.1 MB	Application
Console.app	7 MB	Application
DigitalColor Meter.app	1.4 MB	Application
Disk Utility.app	31.3 MB	Application
Exposé.app	479 KB	Application
Grab.app	1.7 MB	Application
Grapher.app	29.8 MB	Application
Java Preferences.app	1 MB	Application
Keychain Access.app	9.5 MB	Application
Migration Assistant.app	3.8 MB	Application
Network Utility.app	2.4 MB	Application
Podcast Capture.app	10.1 MB	Application
RAID Utility.app	6 MB	Application
Remote Install Mac OS X.app	2.1 MB	Application
Spaces.app	426 KB	Application
System Profiler.app	5.5 MB	Application
Terminal.app	18.9 MB	Application
VoiceOver Utility.app	9.7 MB	Application
X11.app	5.2 MB	Application

Figure 4.4 Utility programs provide tools to optimize the functions of the operating system.

Operating systems continue to expand their multimedia functionality as new computer technology emerges.

Disk Management

Managing disk storage and access to data files is another important feature of operating systems. Operating systems prepare a disk for storage by **formatting** the storage medium. Formatting prepares a disk in three essential ways. First, it defines track and sector addressing on the disk platter. These physical addresses are used by the operating system to locate and retrieve data from a disk. Second, formatting defines a logical storage unit called a *cluster*. A **cluster** is the smallest unit of disk space that contains data. A single cluster can hold data from only one file. Depending on the operating system, the cluster may span one or several sectors on a single track of the disk platter. Finally, formatting defines the **file system** for the disk. This is a type of index to each file name and cluster location on the disk. When a file is retrieved, the operating system locates the cluster address based on the file system. When a file is saved, the operating system records cluster addressing with the filename properties. Different operating systems use different file systems. A common file system for the Windows OS is NTFS (New Technology File System) whereas Apple OS X uses HFS Plus (Hierarchical File System Plus).

Disk management also involves deleting files and reuse of disk space. When the user deletes a file, it is marked for removal in the file system. Windows and Mac operating systems have a "Restore" command that will undelete files. This restores the address to the file. But once the user empties the "recycle bin" or "trash can," it is more difficult to recover the deleted files because the file system frees up cluster addresses for other data or program files. Only special utility programs can recover the lost data.

File Management

Files are containers for data and programs. They have unique names and properties that are recognized by the operating system. Understanding how to manage files is also important for the user. If a file is not carefully named and saved in an appropriate folder, it can easily be lost in the myriad of files stored on the disk.

Many file names have two components separated by a dot: a prefix name and the **file extension** (see Chapter 2). The user defines a data file prefix. The prefix name should clearly indicate the contents of the file, for instance *RedRose*. The file extension can define two properties of a file: its source application or a file data type. *RedRose.psd* indicates that the file is a Photoshop document; *RedRose.gif* identifies the file type (graphic image format).

Files are initially named when they are saved from RAM to secondary storage. The user must be aware of the filename conventions of the operating system. For instance, Unix file names are case sensitive, whereas Windows and Mac OS file names are not. The allowable length and the characters that can be included are also important

Disk Fragmentation

Disk fragmentation results when segments of a file (called *data blocks*) are scattered to noncontiguous locations on the disk. This slows access to the file and can decrease system performance. Defragmentation reorganizes file contents and saves them in contiguous locations. Some operating systems, including OS X, automatically defragment disks.

considerations for file names. For years, DOS users struggled with very restrictive file-name conventions. File names could only be 8 characters with no spaces or special symbols. Mac users could use 32 characters to define a file name that included spaces and no extension. Both Windows and Mac operating systems now allow more than 250 characters for prefix names, enough to meaningfully name just about any file.

In addition to filename rules, the user must be aware of the importance of the extension.

Opening Files with Missing Extensions

In cases where an extension is missing, a data file can be opened within the application. Launch the application first, then use the File/Open command to locate the file in the directory of file names.

Some extensions are unique to programs and must not be changed. For example, *Photoshop.exe* designates a Windows application file. If the extension is deleted or changed, the Windows operating system will not recognize the program. Application prefix names should not be changed either, because there are many supporting programs that locate the application based on its name.

Other extensions identify the program that created the data file. A Word file has a *.docx* extension, Photoshop uses *.psd*, and Adobe Acrobat has the extension *.pdf*. These extensions associate the data with the application. Macintosh operating systems use either an extension with the file prefix or an icon to associate the data file with the application.

File extensions are also useful for end users. If the extension is correct, the user can “double click” on a data file name and launch the application to view data immediately. However, if the extension is deleted or changed, the operating system may not associate a source application with the data. In both Windows and OS X, a dialogue box often appears to select an application from a long list of installed programs that could have created the data.

Extensions can also define a specific data format. These data files are not associated with any particular application; instead, they indicate the type of data stored in a file. For example, *book.txt* is an ASCII text file that can be opened with any text editor or word processing application. Extensions such as *.jpg*, *.gif*, and *.bmp* are graphics images that are opened in a variety of image-editing applications. Like other extensions, those that designate data formats should not be changed. An *.aiff* extension indicates a sound file. If the extension is changed to *.txt*, this will not only confuse a user trying to locate a sound file, but also the operating system as it tries to relate it to an application.

Directories

In addition to observing file naming conventions, effective file management also requires an understanding of directories. A **directory** provides a common storage label for collections of data files and program files. Directories are similar to folders in a file cabinet. Windows and Macintosh operating systems display filename information in directory windows (Figure 4.5 and Figure 4.6).

Directories are usually organized in a hierarchical pattern in which folders are placed within folders to create related subdirectories. The logical structure of directories and subdirectories can be defined either through *pathnames* or graphically through folders that can be opened to reveal other folders. Pathnames identify the main directory first

Name	Kind	Size	Date Modified
Course Files	Folder	--	Mar 20, 200
Fra Lippo Lippi 06	Folder	--	Sep 16, 200
CommentaryByPage	Folder	--	Sep 16, 200
CommentaryPg1.mp3	MP3 audio	950 KB	----
CommentaryPg2.mp3	MP3 audio	295 KB	----
CommentaryPg3.mp3	MP3 audio	426 KB	----
CommentaryPg4.mp3	MP3 audio	524 KB	----
CommentaryPg5.mp3	MP3 audio	229 KB	----
CommentaryPg6.mp3	MP3 audio	360 KB	----
CommentaryPg9.mp3	MP3 audio	295 KB	----
CommentaryPg11.mp3	MP3 audio	721 KB	----
CommentaryPg19.mp3	MP3 audio	360 KB	----
FlashLippiPoemImages	Folder	--	Sep 16, 200
FLL fla	Adobe FL...Document	37.3 MB	Oct 26, 200
LippoLippi Project	Folder	--	Sep 16, 200
Fra Lippo Lippi	Application	22.2 MB	Oct 26, 200
Giotto.txt	Plain Text	66 KB	Oct 11, 200
glossary.txt	Plain Text	66 KB	Sep 27, 200
LippoLippi.txt	Plain Text	66 KB	Oct 11, 200
Masaccio.txt	Plain Text	66 KB	Oct 25, 200
Medici.txt	Plain Text	66 KB	Oct 11, 200
Paged Poem Readings	Folder	--	Sep 16, 200
HUMA READER	Folder	--	Sep 16, 200
7thseal.addendum	Unix Executable File	33 KB	Jun 22, 199
Gothic Cathedrals	Unix Executable File	66 KB	Jul 12, 199
Gothic Cathedrals.txt	Plain Text	66 KB	Jul 12, 199
Reader	Unix Executable File	1.2 MB	May 18, 19
reader98	Unix Executable File	1.4 MB	Oct 6, 2000

Figure 4.5 Macintosh OS Finder: Files and folders.




Figure 4.6 Windows Explorer: Files and folders.

and then indicate subdirectories: "C:\Projects\AjaxCo\Website\Bid.doc" provides the path to a Word document, *Bid*, stored on the computer's hard drive (C).

Like file prefix names, directory names should also clearly identify file contents. For instance, a popular directory in the Windows operating system is "My Documents." This name clearly identifies the files as those created by the user.

Directories are also an important means of grouping related files for ease of access. For example, directories labeled "JonesProject" or "SmithProject" might store all the files associated with a specific multimedia project. These could be added as subdirectories within "My Documents." Such hierarchies of directories provide an efficient index to locate specific files.

Another important function of operating systems is to provide tools to create and manage directories. Windows has a file management utility named Windows Explorer that displays the contents of a disk directory. Users can move, copy, rename, and delete files as well as set up directories within the GUI window area. Windows Explorer is an important utility to control the contents of a disk. The Mac OS also provides a window to the contents of a storage device. Within each window of a directory the user can move, copy, rename, and delete files. New folders are easily created in each window to further organize files on the disk. Using meaningful file names and appropriate directories makes it much easier to locate specific files among the hundreds that are often created in the course of a multimedia project.

4.3 Programming Languages

The second major category of software is programming languages. A **programming language** is a defined system of syntax (or "grammar") and semantics (or "vocabulary") to write computer programs. All operating systems and software applications are written in a programming language. There are many different programming languages. Some languages, like *BASIC*, provide the fundamentals of programming and are simple to learn; others, like *C*, are difficult to master but very powerful. Some languages are better suited for scientific programs, others for business applications, and still others for multimedia programs.

Programming languages are divided between *low-level* and *high-level* languages. Low-level languages relate directly to specific processors, requiring programmers to understand technical details of the computer's hardware. High-level languages are not tied to specific hardware. They are more flexible and easier for programmers to understand.

Low-Level Languages

Machine Code

```
0011110 0101101
1001100 0111001
0100110 0111001
```

In the early 1950s, when computer hardware systems were limited, programs were developed for each specific computer using a set of commands that were recognized directly by the computer's processor. These machine-dependent languages are known as **low-level languages**.

The most basic low-level programming language is **machine code**, in which program commands are directly coded in binary digits to control specific computer systems. These commands are immediately recognized and executed by the processor. In fact,

machine code is the only language the computer can directly execute. Ultimately every other language must be translated into machine code before it can be processed. But machine-code programming is very tedious. Programmers quickly tired of writing commands in strings of binary digits and turned to a series of abbreviations that were less error prone and easier to use. This form of low-level programming is known as *assembly language*.

Assembly language uses easily remembered combinations of letters as abbreviations for the 0s and 1s of machine-coded programs. This greatly improves the efficiency of programming, but the assembly language abbreviations still have to be translated into machine code before the computer processor can execute the program. A translator program called an **assembler** converts abbreviated code into a binary program. Assembly code is also machine dependent, so a program written for a specific computer model could not run on a different computer system. Programmers still use assembly language to create fast and efficient programs because the commands are designed to correspond directly to machine-code instructions in a particular computer's CPU.

Assembly Code*

A = add
C = compare
MP = multiply
STP = store

*Assembly languages have different sets of abbreviated codes.

High-Level Languages

Computers and software proliferated in the 1960s. High-level languages emerged that were more English-like, less error prone, and not dependent on specific computer systems. **High-level languages** are those that abstract from specific hardware components, allowing programmers to concentrate on the program itself rather than the way it is implemented in the computer. Using high-level programming languages, programmers could ignore the operation of specific computers and write programs that could be run on a wide range of computer systems. Useful applications soon multiplied. Languages such as BASIC, COBOL, Pascal, and FORTRAN were widely used to develop software applications. Although these languages are easier for programmers to use, they too must be converted to machine language before they can be executed. This process of converting "source code" written by the programmer to machine code for a specific computer system requires either an interpreter or a compiler.

Interpreters and compilers are programs written to read source commands and translate them to a string of 0s and 1s that the specific computer can process. **Interpreters** translate one line of the program into machine code, execute that line of code, and proceed to the next line in the program. Every time the program is executed it must be interpreted to binary code, one line at a time. This is a time-consuming process, especially for software applications with millions of lines of code. The main advantage of interpreters is that programmers can more easily correct errors in a program that is translated line by line.

A **compiler** converts the entire source code program into machine code. This produces an executable file that runs on a specific computer. The compiled file is much faster to execute because the entire program is saved in its machine-code format. Software applications such as Corel Draw or PaintShop Pro are compiled programs that run on a specific computer platform. The compiler for Windows-based computers is very different from the compiler for Macintosh systems because the two platforms use

different hardware. This is why software purchased for Windows cannot be run on the Mac OS.

Approaches to Programming

There are two main approaches to programming: procedural and nonprocedural. **Procedural programming** follows a series of computational steps that focus on a specific result. This method of development divides complex tasks into routines, subroutines, and functions, all contained in a single program environment where each step is linked to the previous step. These subprograms can be reused in multiple locations of a larger program to reduce the need for redundant code, but it is difficult to migrate such routines to other applications because the various components are interdependent. Languages such as FORTRAN, C, Pascal, and BASIC, among hundreds of others, facilitate this procedural approach to application development. They are effective for many programming tasks but do not allow programmers to reuse the code modules in other applications without significant code modification. This results in decreased efficiency and adds increased maintenance costs to application development.

Nonprocedural programming languages maximize programmer productivity by recycling modules from one application to another, thus making application development more responsive to the task with less emphasis on how to achieve it. Two categories of this approach, object-oriented languages and visual programming, are making programming easier and faster.




Figure 4.7 An object to manage a “circle” has three methods defined to shape, show, and erase a circle. The instructions to make the shape, as well as the data for the location and size of the circle, are contained in the object.

Object-oriented programming languages use self-contained programmed objects that are repeatedly referenced in an application. These objects hold all the data and instructions for a particular task (Figure 4.7). Independent objects with their own characteristics interact with each other based on a series of messages from other objects. The programmer structures the exchange of messages between objects to build up complex operations. Object-oriented programming allows developers to quickly test routines and easily incorporate routines from other projects. C++, Java, PHP, and Perl utilize this object approach to application development.

Visual programming uses a graphical interface to expedite writing source code. Command segments are created using “Drag and Drop” procedures. Once a segment is developed it is compiled to machine language and can be used without having the entire application completed. Visual programming is often used for rapid application development (RAD) because it offers an effective means of generating an application with various stages of testing and usability. Visual Basic .NET is an example of an object-oriented language that includes visual programming (Figure 4.8).

Programmers often use object-oriented languages and visual programming to create customized routines for multimedia applications. Special features such as database interactions or user control of players, vehicles, and other objects in video games may be created using a language like Java or C++. These programs can then be compiled for use in the application.




Figure 4.8 Visual Basic is a visual programming environment that allows programmers to build object-based programs. The programmer uses buttons and text boxes to assign properties and write code for each object. The segments can be individually tested as each set of properties and code is developed.

Programming languages are essential for all software development. Every application and operating system is generated from these languages. While machine code remains the *lingua franca* of computer hardware, modern languages are making it easier to craft applications that address a wide range of computing needs. The computer is a word processor, 3-D game, or window to the Internet using the applications that are developed with programming languages.

4.4 Application Software

An **application** is software that performs a specific task. These programs combine with the operating system to make computers productive tools. Early software for microcomputers included word processing and spreadsheet applications. Today's business productivity tools also include database, presentation, project management, desktop publishing, and time management applications. These programs are often bundled together with a common interface and integrated set of commands. iWork, Microsoft Office Suite, and OpenOffice.org are examples of these program suites.

There are two major types of software for multimedia development. **Media-specific applications** are used to create and edit the individual media elements (text, graphics, sound, video, animation) that make up a multimedia product. **Authoring applications** contain software tools to integrate media components and provide a user interface. This

Scripting is a simplified form of programming provided within an application in order to extend its functionality or automate routine tasks. Scripts are used in productivity applications to automate a series of tasks such as a spreadsheet **macro** to sort, print, and save a data set. Several multimedia development applications also offer an embedded scripting feature. Adobe Flash (ActionScript), Adobe Director (Lingo), and Autodesk Maya 3-D animation software (MEL) offer scripting capability. This allows developers who may not have formal programming skills to improve the functionality of their multimedia applications.

chapter provides a brief overview of media-specific and authoring applications. More details about each of these topics will be found in Chapters 5 through 10.

Text

Multimedia developers use several types of application software to create and edit text. The most common are *word processors* such as Corel WordPerfect or Microsoft Word. These programs make it possible to readily create text in different fonts and styles, check spelling, search and replace words and phrases, and import and export text in a variety of file formats. These functions are just as important in multimedia development as they are in other forms of communication.

Text editor software, such as Notepad, generates ASCII text files. Unlike a word processor file, an ASCII file is compatible with any platform or application. The disadvantage of an ASCII file is that it does not include the advanced formatting and style options available in word processors. Text editors are very useful, however, for tasks that require only simple formatting, such as writing source code for computer programs. Notepad, for example, is commonly used to write XHTML code for web pages.

The development of the World Wide Web also introduced specialized programs designed to preserve the formatting of text documents and to support a variety of interactive features such as hyperlinking, text searching, and speech synthesis. Multimedia developers use Adobe Acrobat to produce PDF files that incorporate these features. Acrobat text files are cross-platform compatible, making them ideal to distribute highly formatted text over the Internet. PDFs are readily viewed using a free Acrobat Reader.

Multimedia text is further explored in Chapter 5.

Graphics

Graphics applications generate 2-D or 3-D paint and draw images. Developers may use several graphics applications, each specialized for the type of image they seek to create. **Paint programs** contain tool sets to create graphics objects as well as editing tools for digital photos or scanned images (Figure 4.9A). They offer a wide array of features such as filters (blur, emboss, pixelate), image adjustment settings (scale, brightness, rotate), and special effects (drop shadow, gradient overlay). Special control over individual image elements is possible using layers and mask options. Text tools are used to generate graphics text with distinctive patterns, shapes, and 3-D effects.

Draw programs contain a distinctive set of tools for creating basic shapes such as ovals, rectangles, Bezier curves, and polygons generated from mathematical formulas (Figure 4.9B). These shapes are grouped, filled, and scaled to produce complex drawn images. These programs create unique logos, designs, and graphics objects that can easily be resized for specific multimedia projects.

Many projects, especially animation sequences and gaming applications, require 3-D images. **3-D imaging programs** are used to model 3-D objects, define surfaces, compose scenes, and render a completed image (Figure 4.10). In *modeling*, the graphic artist creates the shape of an object; in *surface definition*, color and texture are applied; in *scene composition*, objects are arranged, lighting is specified, and backgrounds and special effects are added. Because the creation of the objects and scenes of 3-D graphics can be very time consuming, many 3-D applications provide libraries of clip objects that can be adjusted for individual projects. The final stage of 3-D graphics is rendering. *Rendering*




Figure 4.9 (A) Photoshop paint tools palette. (B) Corel Draw tool palette.




Figure 4.10 3-D graphics application (Carrara) to model, define surface, compose scene, and render objects.

Table 4.1 Sample Graphics Applications

Paint	Draw	3-D Graphics
Photoshop (Adobe)	Illustrator (Adobe)	Carrara (Eovia)
PaintShop Pro (JASC)	Draw (Corel)	Bryce 3-D (Corel)
Painter (Corel)	FreeHand (Macromedia)	Infini-D (MetaCreation)
Gimp (open source)	Inkscape (open source)	Blender (open source)

creates a 3-D image from the specified scene. Rendering is both processor intensive and time consuming because the software must calculate how the image should appear based on the object's position, surface materials, lighting, and specific render options.

Image editing and creation is an important part of multimedia development. Graphic artists select the application they will use—paint, draw, or 3-D graphics program—based on the specific needs of the project (Table 4.1). *Graphics suites* bundle several applications that share a common command set and interface. Adobe and Corel each offer a graphics suite with paint and draw applications.

The different types and uses of graphics are further discussed in Chapter 6.

Table 4.2 Sound Applications

Sampled Sound	Synthesized Sound
Sound Forge (Sonic Foundry)	Cubase 6 (Steinberg)
Soundbooth (Adobe)	SONAR (Cakewalk)
Sound Studio 4 (Felt Tip)	GarageBand (Apple)

Sound

There are two major types of sound applications for multimedia development: *sampled* and *synthesized* (Table 4.2). **Sampled sounds** are digital representations of analog sound sources captured from microphones or other devices. Software settings control the sound format of the sound recording. Sampled sounds can be edited in a wide variety of ways such as trimming to delete dead space, splicing to combine sound segments, setting fade-in and

fade-out (enveloping), adjusting volume, and adding special effects such as echoes or sound reversals (Figure 4.11).




Figure 4.11 Audacity edit window where analog sound is recorded to a digital file and edited. Special effects can be applied and additional tracks can be added and mixed to create a sound file for a multimedia project.

Synthesized sound applications use digital commands to generate sounds. These commands can be captured from a MIDI instrument such as an electronic keyboard or created with a sequencer program. Using sequencer programs such as Cakewalk or GarageBand, developers can enter music notations, determine instruments to play, layer instrument tracks to achieve a full-orchestra effect, and synchronize sound tracks to play a rich musical score. The musical file is then saved and played back on a computer's *synthesizer*, an electronic device to generate sound. MIDI applications are a good source of original music for multimedia applications. However, the developer does need to know music notation and have musical talent to generate high-quality sound files. Digital sound is further explored in Chapter 7.

Video

Video applications provide an environment to combine source material called *clips*, synchronize clips to a sound track, add special effects, and save the work as a digital video. High-quality digital video production once required specialized, expensive hardware and software only available to large multimedia development firms. The widespread use of digital video cameras, the development of more powerful microcomputers, and improvements to the Web made digital video production practical for most developers.

A video project starts by assembling film clips in a project window (Figure 4.12). The clips can be still images, animations, sounds, or digital video files. Video applications provide tools to move and insert clips on a timeline, set *In points* and *Out points*, trim the clip, and define transitions between tracks. Sound tracks, title fields, and special effects such as superimposing, transparency, and lens flare add to the video composition. Video editing applications also define playback size and frame rate. When the video project




Figure 4.12 Video-editing process with Final Cut. Clips are imported into the project window, arranged on a timeline, and previewed. Special effects and transitions are added before exporting the final video project.

object, object shape, and color changes over the frame sequence. Objects are placed on a timeline where effects can be applied to fade in, morph, rotate, spin, flip, or change pace. Multiple objects can be layered to interact with each other to create more complex animations.

Multimedia projects include a wide variety of animations ranging from simple animated logos to full-length feature films such as *Toy Story* or *Madagascar*. Additional details on animation are presented in Chapter 9.

Media Utilities

Developers use a wide array of media utilities in addition to media-specific applications (Table 4.5). **Media utility** programs add functionality to media-specific applications. Some utilities provide productivity features such as image or font cataloging; others perform specific tasks such as color matching or compression. These “enhancement” programs include the following:

- Clip libraries of images, sounds, and animations
- Color utilities to match Pantone color ink formulas for printers
- Image cataloging programs to manage image files
- Font utilities to manage, create, and convert type formats
- Video production utilities to encode and publish streaming video and audio to an array of streaming formats and codecs
- Compression applications to reduce file sizes of specific media and application projects

Table 4.5 Sample Utility Programs for Multimedia Development

Eye Candy (special effects)	MonacoEZColor (color management)	FontReserve (font utility)
PhotoObjects (royalty-free clip images)	Cleaner 6 (publish/compress video and audio)	Sonicfire Pro (manage sound tracks for video projects)
Sorenson Squeeze (compression suite)	Extensis Portfolio (image cataloging)	StuffIt (compress files)

Authoring Software

Authoring applications are programs specifically designed to facilitate the creation of multimedia products. They are used to assemble media elements, synchronize content, design the user interface, and provide user interactivity (Figure 4.14). Authoring programs fall into one of three main categories based on the metaphor they use to organize media elements. Programs such as ToolBook, PowerPoint, and SuperCard use a *card-based metaphor* in which elements are arranged much as they might be on index cards or the pages of a book. These applications are easy to use and are ideal for products such as information kiosks, lectures, and tutorials that do not require precise synchronization of individual media elements. Others, such as Director or Flash, use a *timeline* of separate




Figure 4.14 Two common authoring applications are Keynote (A) and Flash (B).

frames much like a motion picture film. These applications provide the precise control needed for advanced animations. Other authoring programs, such as Authorware, use *icons* arranged on flow lines to quickly develop a wide range of multimedia products including advanced tutorials, product demonstrations, and simulations. Icons can represent both content (images, text, animations, video) and a wide range of interactions (play, stop, go to, calculate, etc.).

Authoring software and the authoring process are discussed further in Chapter 10.

4.5 Summary

Software is the collection of programs that make a computer a useful tool. Operating systems provide the “hidden programs” to control hardware devices, application execution, and access to data. Programming software provides the language to create operating systems and computer applications. Application software makes it possible for users to carry out an ever-expanding array of tasks with their computers.

Multimedia development requires a wide selection of applications to capture and prepare various media components. Media specialists such as graphic artists, sound specialists, and video editors use increasingly powerful media-specific application programs to prepare digital content for multimedia projects. Once the media components are completed, they are assembled using an authoring application. Authoring software integrates the media, provides interactivity, and produces the final multimedia project.

Key Terms

3-D imaging program	Media utilities
Animation	Media-specific application
Application	Multitasking
Assembler	Multitouch
Assembly language	Nonprocedural programming
Authoring application	NUI
Cluster	Object-oriented programming language
Compiler	Operating system
Device drivers	OS utility program
Directory	Paint program
Draw program	Procedural programming
File	Program
File extension	Programming language
File system	Sampled sound
Formatting	Scripting
GUI	Software
High-level language	Synthesized sound
Interpreter	Timesharing
Low-level language	User interface
Machine code	Virtual memory
Macro	Visual programming

Review Questions


1. What are the three main categories of software?
2. What is the main function of each category of software?
3. Why is the operating system critical to a computer system?
4. What are the three types of user interface presented by an operating system?
5. How does the operating system control access to the processor by multiple users?

6. Why is multitasking important for multimedia developers?
7. What is virtual memory and when is it helpful to a developer?
8. What are the three ways formatting prepares a storage disk for data?
9. What are two important considerations when naming a data file?
10. What are directories and how can they be used to manage media files effectively?
11. Why are programming languages an important type of software?
12. What is the essential distinction between low-level and high-level programs?
13. Why must all programs be translated to machine code?
14. What is the difference between an interpreter and compiler?
15. What is the distinction between procedural and nonprocedural approaches to programming?
16. What is the difference between a text editor and a word processing application?
17. What is the difference between a paint and draw application?
18. What is the difference between sampled and synthesized sound applications?
19. Why might a developer rely on media utility applications?
20. What is the purpose of authoring software?

Discussion Questions

1. Open the system preferences on a Mac or Windows operating system. Explain how you can control five different hardware devices through the operating system.
2. Locate the operating system utility programs in Mac OS or Windows and list three OS utility programs.
3. Research and report on developments in natural user interface control of digital devices.
4. Locate the yahoo.com directory of programming languages (Directory > Computers and Internet > Programming and Development > Languages). How many languages are listed there? Why do you think there are so many programming languages? Choose one language and report how it is used.
5. Point your browser to <http://www.tucows.com>. Search for popular media utilities for editing images or sound. Select one image-editing and one sound-editing utility and describe the main features of each.
6. Research the media you can add to a Word document. Do you think Word is an authoring application? Why or why not?

Text



Topics you will explore include:

- Text Tradition
 - Typeface
 - Font
 - Text Characteristics
- Computer Text
 - Codes for Computer Text
 - ASCII
 - RTF
 - Unicode
 - Font Technologies
 - Bitmapped
 - Outlined
 - Multimedia Text
 - Graphics Text
 - Text and Sound
 - Text and Interactivity
- Adding Text to Multimedia Applications
 - Methods
 - Guidelines for Use of Text

In 1518, Michelangelo sketched a series of simple images on the back of an envelope. This scrap of paper, today preserved at the Casa Buonarroti in Florence, is perhaps the most valuable shopping list of all time. Known simply as *Three Lists of Food*, the sketch includes the artist's menu for a meal for two, including six rolls, two soups, and a fish. Apparently the person who was to fetch the ingredients was illiterate and so had to be told what to get in pictures. Michelangelo knew how to draw; but how much easier it would have been, even for him, if his assistants knew how to read. And if he had wanted a *thousand* fish, that one word would have been worth a thousand pictures. Writing, now as then, is sometimes the most efficient mode of communication.

The power and usefulness of text derives in part from its universality. Literacy is a requirement of modern social life. In much of the world it is a formal condition for citizenship. A few people can paint; nearly all can read and write. Multimedia developers often take advantage of the universality of reading. It is common to label new icons to make their meaning clear. When the new icon is widely recognized and has itself become a symbol, the label is often dropped. Developers also list contents, write out instructions for Help screens, and add their names to credits (as well as invoices). Text speaks to nearly everyone.

Text also has unique powers of expression. $E=mc^2$. Five symbols capture a set of concepts—energy, equivalence, mass, the speed of light, squaring—that are invisible to the senses but made evident to the mind in text. No picture can replace this simple formula, though one might help to explain it. Multimedia developers, like other writers, continue to use text to express abstract concepts.

Text can also be powerfully suggestive, engaging a reader's imagination, creating its own images, or prompting a string of unexpected reflections. Byron writes of a looming battle and our minds fill in the images:

*The Assyrian came down like the wolf on the fold,
And his cohorts were gleaming in purple and gold;
And the sheen of their spears was like stars on the sea,
When the blue wave rolls nightly on Deep Galilee.*
(Hebrew Melodies, "The Destruction of Sennacherib")

He speaks of his life and we reflect on our own, and on life itself:

*My days are in the yellow leaf;
The flowers and fruits of love are gone;
The worm, the canker, and the grief
Are mine alone!*
(“On This Day I Complete My Thirty-Sixth Year”)

Byron, as the poem's title suggests, was 36, and this was the last year of his life.

The suggestive, engaging power of text does not belong to poets alone. Politicians use it: “Ask not what your country can do for you; ask what you can do for your country” (John F. Kennedy). And so do advertisers: “99 and $\frac{4}{100}$ % pure” (Ivory soap); and song

writers: “I tried to forget you but you tied bells to your name. They jingled every time I thought of you, without shame” (Jewel). Multimedia developers also craft their words to capture the attention and to engage the imaginations of their readers.

Like all writers, multimedia developers value text for its universality, its clarity and efficiency, and its powers of abstraction, engagement, and suggestion. But unlike traditional writers, the multimedia developer has a wide choice of media, and this adds another step to the “writing” process. Developers must decide where and how to use text most efficiently and effectively. They generally avoid lengthy text presentations because reading is more difficult on-screen. They often provide instructions in text rather than sound because listening is more tiring than reading. Multimedia developers also make use of new tools for creating engagement with text. Words can be animated to attract attention. They can be linked to other words, sounds, or images to entertain or to inform.

Much of the creative challenge of multimedia development lies in effectively exploiting the potential of a new technology, of finding new uses for text and other media. Text also has a long history and a set of traditional conventions that remain important for multimedia development. These are the foundation on which developers build new forms of multimedia writing.

After completing this chapter you should understand:

- Key elements of traditional text, including typeface, font, style, case, weight, kerning, tracking, leading, and justification
- Fundamentals of computer text including codes, font technologies, anti-aliasing, and the problem of installed fonts
- Defining features and uses of multimedia text: editable vs. graphics text, text and sound (speech recognition and speech synthesis), hypertext and hypermedia, and multimedia text formats
- Major options for adding text to a multimedia application
- Basic guidelines for the use of text

5.1 The Text Tradition

Text was dramatically transformed by the invention of the printing press in the 15th century. In addition to greatly increasing the volume of written communication, the printing press also standardized many elements of text presentation. A number of the print-based text properties remain important to multimedia developers today.

Typeface

Characters are grouped into families that share a common design. These designs are traditionally called **typefaces**. Examples of typefaces include New York, Times, Helvetica, and Courier. Typefaces are carefully designed for specific purposes, and thousands have been created. Bell Centennial was created for telephone books and Spartan Classified was specially designed to improve the legibility of small classified ads in newspapers.



Figure 5.1 Serif text.

Times: A serif typeface

Arial: A sans serif typeface

Edwardian: A script typeface

Symbols: ∞ | ℞ ♣ ♦ ⊗ ⊙ ⊕ ⊗ ≡ δ

Figure 5.2 Categories of typefaces.

Typefaces are commonly divided into two major categories: *serif* and *sans serif*. A **serif** is a fine line added to finish a letter stroke (Figure 5.1). Serifs tend to make letters flow into one another. This makes it easier for the eye to move from one word to the next in long segments of text. As a result, serif text is often used for the longer selections of text known as *body text*. **Sans serif** text is text without a serif (*sans* is *without* in French). This text typically has a clean, bold look. Sans serif text is traditionally used for headings. Other categories of typefaces include *script*, type that is designed to look like handwriting, and *symbols* (Figure 5.2).

Style

Typefaces generally contain several *styles* of letters. **Styles** are readily recognized variations in the appearance of characters that allow writers to adapt the typeface to specific purposes. Roman or plain text is usually used for body text while **bold**, *italic*, and underlined styles are often used for titles or for emphasis.

Point

A **point** is a measure of the size of type. The individual letters, numbers, and other characters that were mounted in printing presses were measured in points. A point is approximately 1/72 of an inch. Another traditional measure based on the point is the *pica*. A pica is 12 points; 6 picas is approximately 1 inch.

A typeface may be printed in many different sizes. The point size of a typeface measures the space within which each of its characters is designed. This is approximately the distance from the bottom of the *descender*, the portion of the letter normally written below a line (as in the dropped vertical line of a “p”) to the top of an *ascender* (as in the rising vertical line of a “d”).

The print industry also works with a variety of other measurements, including the height of capital letters (*cap height*) and the height of the small letter “x” (*x-height*) (Figure 5.3).



Figure 5.3 Point size, cap height, and x-height.

Font

A complete set of characters of a particular typeface, style, and size is traditionally known as a **font**. *New York, italic, 12 point* is an example of a font. A typeface has many different fonts.

Some fonts are monospaced while others are proportional. **Monospaced fonts** assign the same width to each character, regardless of its shape. In monospaced fonts, narrower letters such as an “i” occupy the same space as wider letters such as an “m.” Monospaced fonts have the somewhat choppy appearance of typewriter text. **Proportional fonts** adjust the width of a letter or other character based on its shape. Narrow letters are assigned less space than wider letters. Proportional fonts are usually easier to read and more elegant because they distribute characters more evenly (Figure 5.4).

Courier is a monospaced font.
Palatino is a proportional font.

Figure 5.4 Monospaced and proportional fonts.

Case

Small letters are traditionally labeled *lowercase*. Capitals are called *uppercase*. These designations refer to the containers, or **cases**, used to store the two different types of metal castings for use in printing presses. Capitals were stored in cases placed above the cases holding small letters.

Weight

Some typefaces are designed in multiple versions with lines of different thicknesses. **Weight** is the line thickness of a typeface. Thin lines are designated as *lighter* weight with thicker variations being *heavier* weights. A version of a typeface with particularly heavy weight is sometimes designated as “black.” Arial, for instance, is light and **Arial Black** is heavy.

Kerning

The different shapes of letters sometimes result in distracting variations in letter spacing. At standard spacing, uppercase “A” and “W” appear to be further apart than uppercase “H” and “N” (compare AW & HN). This effect can be corrected by moving the pairs of letters either closer together or further apart. This process of adjusting the spacing between pairs of letters is **kerning** (Figure 5.5).

Before kerning: AW
After kerning: AW

Figure 5.5 Kerning.

Tracking

It is also often desirable to change the spacing of all characters, or **tracking**. More space between letters results in a looser track, less space produces a tighter track. A tighter track can usually be used on shorter lines of text; longer text lines typically require a looser track. Tracking adjustments are also often used to adjust the length of individual lines to avoid hyphenation (Figure 5.6).

This is a tighter track.
This is a looser track.

Figure 5.6 Tracking.

Condensed/Extended Text

Changing the proportions of the characters themselves can also alter the length of a text line. Instead of inserting more space between characters, as in tracking, the width of a character can be narrowed or widened. Narrowing the width of characters results in **condensed text**, widening results in **extended text** (Figure 5.7).

Condensed and extended text are usually used for space adjustments to an individual line of text or for artistic effect. Because fonts are carefully designed for specific purposes, condensing or extending the font in large blocks of text should usually be avoided.

This is Futura.
This is Futura Condensed.
This is Futura Extended.

Figure 5.7 Condensed and extended text.

Leading

The spacing between lines of text can also be adjusted. This is referred to as **leading** (pronounced “ledding”). The term is derived from the use of thin strips of lead to separate lines of text in printing presses. In general, as the number of words in a line of text increases, leading also needs to increase. Leading and tracking are also interrelated: a looser track typically requires greater leading and a tighter track less leading. This is because the distance between lines of text needs to be greater than the distance between words. If lines are spaced more closely than words the eye will tend to jump to the next line rather than moving to the next word on the same line (Figure 5.8).

A Looser Track with More Leading

Modern scholars have interpreted the various symbols in Lippi’s works differently, and perhaps Lippi’s contemporaries did as well. We simply do not know exactly what the 15th-century viewer would have seen in Lippi’s art, but we do know that they would have approached his paintings with symbolic references in mind.

A Tighter Track with Less Leading

Modern scholars have interpreted the various symbols in Lippi’s works differently, and perhaps Lippi’s contemporaries did as well. We simply do not know exactly what the 15th-century viewer would have seen in Lippi’s art, but we do know that they would have approached his paintings with symbolic references in mind.

Figure 5.8 Track and leading.

Alignment and Justification

Alignment and justification are also characteristics of print-based text that continue to be relevant in multimedia development. **Alignment** is the position of text relative to a document’s margins. Text *aligned to the left* margin has a ragged (uneven) edge to the right. *Centered* text has ragged edges on both sides. Text *aligned to the right* margin has a ragged edge to the left. **Justification** is the process of adjusting line lengths to produce straight edges on both the left and right margins. This requires adjustments in the spacing of characters to make each line of text the same length. Traditionally, justified text has been used for more formal presentations and for the columns of text in magazines and newspapers. Left-alignment produces a more casual feel. Centered text and right-alignment are usually used for aesthetic effect (Figure 5.9).




Figure 5.9 Alignment and justification.

5.2 Computer Text

Text as it is treated by the computer shares many features with traditional text. Word processing programs allow their users to easily change the appearance of text and its size by changing typeface, style, and points, for example. In almost all programs, however, typefaces are listed, somewhat inaccurately, as “fonts” (Figure 5.10). Strictly speaking, a font is not the whole collection of characters with a single design—this is a *typeface*. Instead, a font is a set of characters within the typeface of a particular size and style. Palatino, bold, 18 point is a *font*; Palatino is a *typeface*. The substitution of “font” for “typeface” is now well established in the computer industry, however, with nearly all references to computer font actually referring to typeface. In the sections below, the current convention of using “font” for what traditionally would be called a “typeface” will be followed.




Figure 5.10 Word processors use “font” for “typeface.”

Word processing programs also allow users to manipulate many other elements of traditional printing operations. Users can generally adjust kerning (the spacing between pairs of letters) as well as tracking (the spacing between all letters) and leading (the spacing between lines). Condensed (narrowed) and extended (widened) fonts are also often available.

Codes for Computer Text

All the data in a computer must be represented by a binary code, a combination of 1s and 0s. Developing such a code for text is relatively simple: each character (letter, number, symbol, punctuation mark, etc.) is assigned a unique combination of bits. Several different coding schemes have been developed for computer text. Two of the most important are ASCII and Unicode.

ASCII **ASCII** stands for *American Standard Code for Information Interchange*. Virtually all computers can readily process ASCII files. The original version of ASCII was a 7-bit code.

Designing a Text Code

Binary codes are carefully chosen to facilitate specific tasks. For instance, the ASCII code was designed so that lowercase and uppercase versions of the same letter differ only by the value of one bit. Changing that single bit changes lowercase letters to uppercase and vice versa.

An expanded version of the code, known as “extended ASCII,” uses an 8-bit code, thus doubling the number of characters that can be represented.

ASCII coding produces a very basic text file in which only letters, numbers, common symbols (for example, “+” or “©”), punctuation marks, and a limited set of control functions (for example, delete or carriage return) are represented. Notepad on the PC is an example of a basic ASCII text program.

More advanced word processing programs, such as Microsoft Word, use proprietary coding schemes that support many more characteristics of text, such as styles (*underline*, *italic*), tabs, and so on. Computers that do not have these word processors or compatible programs installed will not be able to read these more elaborate codes.

Most word processing programs can also produce ASCII versions of files. Users simply save the file as ASCII or “text only,” under the *Save As* or *Export* options. ASCII files can be read on nearly every computer, but the conversion process will strip away much of the formatting information (for example, tabs, text alignment, and text styles) in the original word processor file, leaving behind only those elements supported by ASCII code. The text itself will be preserved, however. If the objective is simply to create basic messages, an ASCII text editor is very effective and efficient.

RTF A variation of ASCII that is also available in many word processors is RTF. **RTF**, or Rich Text Format, was developed by Microsoft to facilitate cross-application and cross-

platform use of text files produced by different word processors. RTF is based on the ASCII code but it also includes special commands to reproduce the formatting of the original file. In this way, text files created using one word processor and operating system can be opened and edited using another word processor or operating system without loss of the original formatting. Like plain ASCII, RTF is often available as a file option under *Save As* (Figure 5.11).




Figure 5.11 The RTF option in Word.

Unicode Extended ASCII added, among other characters, a selection of Greek letters to the Latin letters and Arabic numerals available in original ASCII. However, many languages, such as Japanese and Chinese, do not use either Latin or Greek script. In an effort to more effectively present these languages, a new coding scheme was devised in 1988. Known as **Unicode**, the new standard is based on a 16-bit code that permits approximately 65,000 characters to be represented. The Unicode standard also specifies code subsets (called “surrogates” in the Unicode standard)

that permit a total of as many as one million additional characters. Unicode is continually evolving. Unicode 3.0 included 49,194 characters, covering virtually all languages in modern use and many historical languages as well. Unicode 5.0 specified over 100,000 characters. Unicode fully incorporates ASCII encoding as well as several other national and international standards.

The goal of the Unicode project is to define “a consistent way of encoding multilingual text that enables the exchange of text data internationally and creates the foundation for global software” (Unicode 2001). Unicode has been widely adopted for text representation. It is included in all modern computer operating systems and in HTML, XML, and Java.

For current developments in the Unicode project, see <http://www.unicode.org>

5.3 Font Technologies

Standards such as ASCII, RTF, and Unicode specify the codes to be assigned to particular text characters. The codes 01010100 01100101 01111000 01110100 specify the word *Text* in ASCII-8, for instance.

Assigning a code is only the first step in the process of generating computer text. Text also must be displayed through monitors or printers. The techniques for displaying text are referred to as **font technologies**. There are two basic approaches to generating text display. The first makes use of *bitmapped fonts*, the second is based on *outline fonts*.

Bitmapped Fonts

A computer monitor displays a grid of pixels, or “picture elements.” A monitor set to a resolution of 800 × 600 displays 800 vertical lines and 600 horizontal lines for a total of 480,000 individual pixels. Each of these pixels can be described with one or more bits. If a single bit is used, two color values, usually black or white, can be assigned to each pixel. Two bits can designate any one of four colors; three will allow eight colors and so on. The number of possible colors doubles with each additional bit used.

In a **bitmapped font**, each pixel of the letter to be displayed is described by a binary code. The listing of these codes constitutes a “mapping” of the text character as it will be displayed, hence a “bitmap.” Because information must be saved about each pixel, bitmapped fonts require relatively large amounts of memory. This is particularly true if a wide range of colors must be available, because this requires more bits to be used for each pixel. A range of 256 colors, for instance, would require 8 bits to represent each pixel of the text character.

Bitmapped fonts have the advantage of giving font designers precise control over the appearance of text characters. Fonts can be edited down to the level of the individual pixel, ensuring that characters will appear exactly as intended. This degree of control can be particularly important in the use of smaller fonts because characters often become less precise and less readable as font size is reduced.

In general, different bitmaps must be designed for each size of text to be used. Bitmapped fonts do not scale well. Attempting to enlarge a 12-point bitmap to 28 points, for example, generally produces distortions in the text characters. This is because the

computer must interpolate the additional pixels in the new, larger character rather than having the font designer directly select them. Effective use of bitmapped fonts requires separate bitmaps for each typeface, style, and point size to be used. This significantly increases memory requirements. It also limits flexibility in the use of computer text because the required font may not be available when needed.

Outline Fonts

Outline fonts represent a solution to the problems of memory and flexibility associated with bitmapped fonts. The basic strategy in **outline fonts** is to store a set of instructions to draw the character rather than a mapping of each of the character's pixels.

One common outline font technology is Adobe PostScript. *PostScript* specifies a series of commands and parameters to produce text characters. The computer then draws the character to be displayed on-screen or causes a printer to produce the character on paper. To produce a different font size, PostScript simply specifies a different drawing command. Outline fonts therefore scale much more effectively than bitmaps. Moreover, it is not necessary to store detailed descriptions of each character to be used, as is the case with bitmaps. All that needs to be stored are the drawing commands. As a result, files for outline fonts are much smaller than those for bitmapped fonts. PostScript commands can also be used to describe other elements of page layout, including illustrations.

Other outline fonts were developed following the success of PostScript. Apple and Microsoft, for instance, collaborated to produce *TrueType* for use on their computers. This allowed both companies to use an efficient, scalable outline font without paying royalties for the use of PostScript. TrueType is now very common on both Macintosh and Windows platforms. PostScript remains the standard of choice in professional publishing, however. Multimedia projects that include high-quality print materials often require the use of PostScript fonts.

Text Display and Anti-Aliasing

Both bitmapped and outline fonts are displayed on monitors as patterns of pixels. Many printers also use separate dots of color to compose text characters. Pixels are usually displayed as very small squares. Smooth lines can be created with a series of these small squares if the lines are vertical or horizontal. Curves and angled lines, however, will display with a stair-step effect that produces jagged lines (often called **jaggies**).

This deviation from the text character's true form is called an *alias*. **Anti-aliasing** combats this effect by blending the color of the text with the color of the background on which it appears. The pixels adjacent to black text on a white background would be shaded gray; red text on white might use shades of pink. This shading blends the text to the background, minimizing the appearance of jagged outlines (Figure 5.12).

Anti-aliased text is an option in image-editing programs such as Photoshop and is often automatically applied in multimedia presentation programs such as PowerPoint. Producing clean, professional type usually requires the use of anti-aliasing.



Figure 5.12 Anti-aliasing smooths "jaggies."

The Problem of “Installed Fonts”

The coding schemes used for text, such as ASCII or Unicode, are so widely supported that multimedia developers seldom need to be concerned about their availability to users.

This is not true of fonts. Particular fonts (Palatino, Times, Chicago, etc.) must be installed in the user’s operating system for text to be displayed as the developer intended. If the specific font is not available, the computer operating system will generally substitute another. The results may not be pretty. Text alignment may be lost and the psychology of the text display, its mood or feel, may be altered.

Developers employ two basic strategies to deal with the challenge of installed fonts. The first is to use only fonts that are widely available. Arial, Bookman, Courier, Times, and Lucida are available on nearly all Windows computers. Commonly installed fonts for the Mac include Chicago, Courier, Geneva, New York, and Times. Restricting a design to one of these fonts generally ensures that users will view text as the developer planned.

The second strategy is to make the required font available to the user. This is done by including the font, with instructions for installation, among the application files. The user then installs the required font or fonts prior to using the multimedia application. As with all software, the developer must determine the conditions of licensing associated with the font prior to distribution. Some fonts may not be available for distribution at all while others may require payment of fees.

Cross-platform compatibility is another aspect of the problem of installed fonts. Fonts that share the same name may not appear the same on different computer platforms. The Windows Times font, for instance, will not produce the same text display as Times on the Macintosh. Developers who target their applications to both platforms need to test their products on each.

5.4 Multimedia Text

Computer text added powerful new tools to those traditionally available to the printing industry. Typesetting tasks could be carried out much more efficiently using specialized computers. Individuals using personal computers could create their own sophisticated designs and layouts with “desktop publishing” programs such as InDesign or QuarkXPress.

Multimedia further expands the possibilities of text by transforming it from a static to a dynamic medium. Text becomes dynamic as it is linked to other media and takes on new forms of interactivity. Text can change color with user interactions; it can be animated, spinning and rotating its way onto a screen; and it can be linked to charts, tables, photos, sounds, and video.

Text and Picture

The multimedia developer treats text in one of two main forms, either as the editable computer text discussed previously or as graphics text. **Editable text** is the text produced by basic text editors and word processors. Editable text can be easily revised, searched, spell-checked, and reformatted. Multimedia developers take advantage of these capabilities for much of the text content of their applications.

Graphics text, on the other hand, is essentially a picture. Like other pictures, text in the form of a graphic can be manipulated to produce a wide range of artistic effects. Letters can be rotated, reshaped, variously colored, or animated. Such capabilities are often used in the creation of original logos or attention-grabbing headings. The words that make up graphics text are coded only as a pattern of shapes and not as the identifiable letters represented by ASCII or Unicode. In effect, the computer cannot “read” or process these images as words. For this reason, operations such as spell checking or search and replace are not applied to graphics text.

Graphics text allows developers to apply their artistic talents to words. The result is often an original, engaging word-picture. There is also another important use of graphics text. As noted previously, one of the challenges of computer text is ensuring that users have the appropriate fonts installed on their computers. If text is presented as a graphic, this problem disappears. Because graphics text is simply a picture, virtually any computer will be able to display it, and it will appear exactly as the designer intended it. For this reason, developers sometimes convert the editable text in their applications to a graphics text format.

Text and Sound

Just as the flexibility of text has been enhanced by its associations with graphics, so, too, has the use of text benefited by its newly developed connections to sound. The interconnection of text and sound takes two principal forms: speech recognition and speech synthesis.

In **speech recognition**, specialized software analyzes the sound patterns of human speech to identify individual words. These can then be converted into the corresponding text and displayed on-screen as if the user had typed the words. Programs such as Dragon NaturallySpeaking allow users to speak the text they would like to write into a microphone connected to the computer. The success of such programs depends upon techniques developed in another area of computer science, artificial intelligence. Speech recognition continues to improve, but because of the variations between speakers’ voices, speech recognition programs sometimes require adjustments such as carefully separating words with pauses or “training” the system to respond correctly by speaking particular words or phrases to it.

In **speech synthesis**, text is given voice. Specialized software is used to analyze text for the distinctive elements of speech sounds that compose spoken language. Speech synthesis has been extensively developed. Printed texts are “read” to the blind. Directory assistance is automated, as are a wide range of telephone ordering and marketing systems. Text-to-speech (TTS) capabilities provided in OS X and Windows can synthesize speech from any selected text as well as read system alerts. Users can select a variety of voices and speech rates. Both Windows and OS X also support speech recognition. Users can directly control certain computer operations by voice commands such as “Switch to Microsoft Word” or “Get my mail.”

Text and Interactivity: Hypertext and Hypermedia

The terms *hypertext* and *hypermedia* were first proposed by Ted Nelson in 1963 to describe new ways of representing and accessing information. Nelson’s vision was pow-

erfully extended and given practical implementation in the 1980s with Tim Berners-Lee's development of the elements of the World Wide Web.

Hypertext is linked text, text that leads to other text. The linkages may be very simple and direct, as in words linked to definitions—clicking on *mitosis* leads a user to a definition of that term, for example. Linkages may also be more sophisticated and complex. The Help functions in many applications provide hyperlinks based on different criteria such as content lists or an index. Searching for a particular topic may return a list of links ranked according to relevance.

The content items joined through hypertext are referred to as **nodes**. The point of departure in a hypertext link is called a **link anchor**. Clicking on the anchor leads to the related information, or node. **Link markers** indicate links. Underlined blue text is a common link marker on the Web, although linking has become so common that virtually any distinguishing text feature can now be used as a marker.

The development of the multimedia computer transformed hypertext into hypermedia. **Hypermedia** is an information structure in which a variety of media are used as nodes or link markers. Words, for instance, might be linked to illustrative graphics or to a sound file providing a pronunciation. Similarly, a picture might be linked to a text description.

Hypermedia fulfills many of the dreams of Vannevar Bush and other early multimedia theorists. It provides readily accessible, powerful tools for storing, organizing, and accessing information. It dissolves disciplinary boundaries, promotes multisensory understanding, and engages its audience in ways never before possible.

Like any new mode of communication, hypermedia has been applied to the wide range of human needs and interests. Tim Berners-Lee's vision of improving scientific research through a web of readily exchanged multimedia resources is one use. Lecture presentations, tutorials, interactive texts, and simulations are among the educational applications of hypermedia. Advertising, shopping, political campaigning, and the many facets of entertainment (from video games to books, film, radio, and television) have all been affected by hypermedia.

HTML and XHTML

HTML, or Hypertext Markup Language, is a standard for the display of text and other media through browser software. A **browser** (such as Safari, Firefox, or Microsoft Internet Explorer) is a program running on the *client* (user's) computer that displays information received via a network from another computer that acts as a *server*. As its name suggests, HTML also provides for hyperlinking.

HTML encloses the information to be displayed between "tags" that specify the structure of the document and the formatting of text or other media elements. For instance, the following HTML coding causes the browser to display "This Month's Specials" as a large red heading: `<h3> This Month's Specials </h3>`. HTML provides only limited control of the appearance of text. While developers can specify a desired font in HTML, if the font is not available on the client machine, a substitution will be made. In addition, the formatting of text (for instance, line lengths and spacing) is difficult to preserve in HTML. This means that text may not be displayed on a user's machine in exactly the way a developer intended.

Cascading Style Sheets (CSS) are an addition to HTML that makes it easier for developers to preserve consistency in the appearance of text. Like HTML, style sheets are text files that provide instructions to a browser as to how to draw a page. When used in conjunction with HTML, the style sheet specifies the *appearance* of the web page, while HTML specifies page *structure*. Instead of including coding for font color directly using HTML, the developer specifies this property for a category of text (such as a main heading) in the style sheet. HTML is used to specify paragraphs, tables, images, and other structural elements of the page. Changing the font, size, or style of text on the site can then be easily accomplished by simply changing the style sheet, rather than editing each of the many tags that would otherwise appear in the HTML code. Style sheets also make it simpler for organizations to maintain a consistent appearance across a wide range of web pages.

Style sheets are an integral component of the successor to HTML, XHTML. **XHTML**, eXtensible Hypertext Markup Language, is a blending of HTML with XML (eXtensible Markup Language). **XML** is a *metalanguage*, a set of specifications or rules for creating other languages. The metalanguage allows developers to create more specialized languages for the specific needs of their field or project. Such languages can then be used in browsers that support the XML specifications. XML supports powerful data manipulation options that are useful for searching, sorting, and delivering data from various sources such as spreadsheets, databases, or content delivered from other websites. XHTML has the advantage of supporting user-defined tags that can improve page displays on computers or adapt to new mobile devices for Web access such as PDAs and cell phones. XHTML has replaced HTML as websites incorporate more sophisticated uses of data and as greater numbers of users access the Internet with small, portable devices.

PDF

It is often important to maintain the original formatting of documents delivered via networks. Business and government forms, for example, are difficult to use if the browser alters the original typefaces, spacing, and placement of graphics. Other text documents may be carefully designed to convey a particular mood or style, features that may not survive HTML display.

PDF, or Portable Document Format, was developed by Adobe Systems to preserve the original formatting of text documents. PDF documents are both platform and application independent. They will maintain the same appearance whether they are displayed on a Macintosh, Windows, or Unix computer regardless of the program used to create the original files.

PDF supports multiple media and a range of user interactions. These include:

- Sound
- Animation
- Video
- Hyperlinks
- Speakable files for the visually impaired
- Copy/paste prohibitions

With its wide range of features, PDF quickly became a standard for electronic document exchange.

Two different forms of software are required for the creation and use of PDF documents. The *Acrobat* program, offered for sale by Adobe, is used to translate documents to the PDF format, add hypermedia features such as sound and interactivity, and implement options such as password protection and digital signatures. The translation process produces a file that can contain text in editable format, fonts from the original document, vector graphics, and bitmapped graphics. The locations of these elements on a page are encoded and compression is applied to graphics. The result is a file that preserves the original formatting of all page elements and also supports text searches and editing. PDF converters can also be found within popular word processors and as shareware utility programs.

A second program, *Acrobat Reader*, makes it possible to open and use any PDF document. Acrobat Reader is available for different operating systems including Macintosh, DOS, Windows, and Unix, and is distributed free of charge by Adobe.

5.5 Adding Text to a Multimedia Application

An *authoring program* is the software used to integrate individual media (text, sound, graphics, video, animation) and build the user interface (menus, hyperlinks, video controllers, etc.). Authoring applications such as Director, Authorware, or PowerPoint provide several ways for developers to incorporate text. These include direct entry, copy and paste, and file importing.

Direct Entry of Text

In direct entry, the developer simply types the desired text in the authoring program. Editable text is generally typed into an area defined for this purpose, a *text box* or *text field*. Text boxes or fields may have different properties depending upon the authoring program and the purpose of the application being developed. Some may be intended simply to display text information to the user. Others provide areas for users to enter information of their own such as responses to questions or search queries. Graphics text is often simply typed onto any area of the screen and then positioned or further manipulated by rotating, stretching, filling with color and so on, like any other graphic.

Copy and Paste

Copy and paste allows developers to select text from another source, copy it to the computer's "clipboard," and paste it directly into their project. Copy and paste is an essential, time-saving tool for the multimedia developer that is used not only for text, but also for all media.

File Import

Finally, text can be entered by file import. In this case the text to be incorporated already exists as a file, having been previously typed, scanned, or converted from speech. The authoring application will typically provide a dialogue box in which the developer selects the file to be imported. File import is particularly useful for larger amounts of text because it is much faster than reentering text and more direct than copy and paste.

Scanning and OCR

Developers often need to incorporate text that exists only in its traditional format, the printed page. Scanning and optical character recognition (OCR) produce a computer text file from printed sources.

Scanning text for use in multimedia applications is a three-stage process. First, the text is scanned using one of several different types of devices (hand scanner, flatbed scanner, etc.). In this process, light and photoreceptors are used to produce, in effect, a picture of the page. Like the graphics text described above, the scan only records the shapes that make up the text and not the identity of the individual characters.

In the second stage, specialized software is used to identify the characters represented by the scanned shapes. This is called optical character recognition, or **OCR**. The accuracy of OCR varies because, with so many different typefaces available, significantly different shapes may represent a particular letter, number, or symbol. In addition, imperfections on the printed page complicate accurate character recognition. OCR programs have continually improved and the best among them correctly identify a high percentage of characters. Some mistakes are nearly inevitable, however. This leads to the final stage of the process, proofing the text file produced by OCR.

Proofing is usually expedited by first using a spell-checker on the text file. Characters that have been misidentified (a "t" for an "i," for instance) will often show up as spelling errors. Spell-checkers will not catch all errors, however. Scanned files should always be carefully proofread.

5.6 Guidelines for the Use of Text

The effective use of text in multimedia applications is governed by the principles of good writing in general. Readers appreciate carefully crafted words whether they find them on screen or on paper. Conversely, poor word choices, spelling mistakes, and grammar errors rapidly undermine user confidence in the content of a multimedia application.

Multimedia also raises writing challenges and opportunities of its own. Some of the more important of these are addressed in the following guidelines.

1. **Be selective.** Use text where it conveys information more effectively than other media:
 - To present facts and abstract concepts.
 - To label unfamiliar icons.
 - To solicit or respond to user input.
2. **Be brief.** Reading large amounts of text on a computer screen soon tires the user.
 - Eliminate unnecessary words.
 - Choose words carefully. Strive for precision and economy.
 - Break text into short, logical segments.
 - Use bullets.
3. **Make text readable.**
 - Preserve open space. Don't crowd the screen with too much text.

- Test fonts for legibility.
 - Use anti-aliased text for a cleaner, more professional appearance.
 - Match fonts to backgrounds:
 - Choose font/background colors carefully—for instance, red on black is much harder to read than yellow on black.
 - Avoid small fonts on textured backgrounds—the texture will obscure letter shapes.
 - Adjust tracking and leading when changing line length.
 - Limit the number of fonts. Too many fonts (“ransom-note typography”) will distract the user.
4. **Be consistent.**
- Maintain a tone to match the purpose of the application: professional, formal, casual, or humorous.
 - Use the same fonts for each of the major categories of text: page headings, menus, body-text, buttons, etc. Font consistency helps to orient users.
 - Vary font size to reflect the relative importance of information.
 - Use a grid to consistently locate different types of text (headings, body text, navigation aids, text-entry boxes).
5. **Be careful.**
- Proofread. Spelling and grammatical errors quickly undermine your credibility.
 - Avoid plagiarism. Identify and credit your text sources.
 - Check for font availability on playback systems.
 - Check for font compatibility on cross-platform applications.
6. **Be respectful.**
- Avoid stereotypes and disparaging usages (for instance, racist or sexist language).
 - Use humor with care. What is funny to one person may be offensive to another.
 - Limit the use of animated text and “word art.” These can easily become distractions, shifting the user’s focus away from the meaning or message of the text.
7. **Combine text with other media.** Use sound, graphics, video, or animation to reinforce, explain, or extend the text message. For instance:
- Spoken word pronunciation.
 - Animation of a physical process (cell division, nuclear fission).
8. **Make text interactive.** Much of the power of multimedia derives from interactivity. Try to engage users with text.
- Solicit user input.
 - Use hyperlinks to tie words to related information.
 - Use mouse-overs:
 - To display definitions of unfamiliar terms.
 - To pose a question.
 - To make a comment.

5.7 Summary

Often considered the least glamorous of the various media, text is nonetheless an important element in many multimedia applications. Text is often the most efficient communication medium and it is essential for the presentation of abstract ideas and theories. Well-crafted words can also be powerfully engaging and provocative.

Multimedia text is built on a long-standing text tradition and on the powerful editing tools of computer-generated text, but it has also made its own contributions to the expanding uses of the written word. These include many dynamic elements. Multimedia text can be animated, morphed, linked to any other medium, and automatically generated from speech. Like all written communication, multimedia text should be clear, grammatically correct, and delivered in a style appropriate to its audience.

Text is effectively combined with other media through a variety of resources including HTML and XHTML for web pages, PDF files for consistent delivery of highly formatted multimedia documents, and a wide range of authoring programs. Scanning and file import complement direct-entry techniques to expedite the inclusion of text in multimedia applications.

Key Terms

Alignment	Link markers
Anti-aliasing	Monospaced font
ASCII	Nodes
Bitmapped fonts	OCR
Browser	Outline fonts
Case	PDF
Condensed text	Point
Editable text	Proportional font
Extended text	RTF
Font	Sans serif
Font technologies	Serif
Graphics text	Speech recognition
HTML	Speech synthesis
Hypermedia	Style
Hypertext	Tracking
Jaggies	Typeface
Justification	Unicode
Kerning	Weight
Leading	XHTML
Link anchor	XML

Resource

The Unicode Consortium. (1991–2012). The Unicode Standard, Version 3.0. <http://www.unicode.org/book/uc20ch1.html>.

Review Questions


1. What are the main text properties derived from the print industry?
2. What are the two main font technologies?
3. Identify an advantage and disadvantage for each of the two main font technologies.
4. What is the process of anti-aliasing?
5. What is a benefit of graphics text?
6. What is one limitation of graphics text?
7. What is the main distinction between ASCII and RTF text files?
8. When should a person save a file created in Word as an RTF file?
9. What is hypertext?
10. What is one benefit and one limitation of OCR text input?
11. What are two advantages of PDF files?
12. What is the problem of installed fonts? How can multimedia developers resolve this problem?
13. What are two advantages of XHTML?
14. Identify and define the two principal uses of combining text and speech.
15. What are four methods to add text into a multimedia authoring application?

Discussion Questions

1. The characteristics of typography have their origins in the manual print industry. Identify and explain three features of typography that began in the print trade.
2. When should you consider using graphics text in a multimedia application? Why?
3. Locate and print the first page of your campus website. Circle two examples of graphics text and highlight two examples of editable text. Explain why these specific text elements were presented as graphics or editable text.
4. As the text editor of a multimedia tutorial, explain why you will only accept file formats that are .rtf.
5. As the text editor of a multimedia book, why will you convert your final chapters to a .pdf format?
6. Provide three guidelines you would follow to create the text-based content in a PowerPoint multimedia kiosk to announce your campus events.

Chapter 6

Graphics



Topics you will explore include:

- Traditional Graphics
 - Contone and Line Art
 - Image Reproduction
 - CMYK Color
- Computer Graphics
 - Bitmapped Graphics
 - Spatial Resolution
 - Color Resolution
 - Types of Bitmapped Graphics
 - Sources of Bitmapped Graphics
 - Vector-Drawn Images
 - Draw Shapes and Layers
 - Autotracing
 - Comparing Bitmapped and Vector Graphics
- 3-D Graphics
 - Modeling
 - Surface Definition
 - Scene Composition
 - Rendering
- Guidelines for Using Graphics

In multimedia development, the term *graphics* covers a wide range of pictorial representations from simple line drawings to blueprints, charts, graphs, logos, paintings, photos, and the individual frames of animations and movies. Graphics were the first of the non-text media to be effectively processed by computers. The GUI (graphical user interface) and early paint and draw programs transformed computers into multimedia machines.




Figure 6.1 Photoshop tools.

Once images were represented digitally, computers were able to carry out many of the traditional tasks of artists and graphic designers. Graphics could be created using digital versions of tools such as paintbrushes, spray guns, image masks, and Bezier curves. They could be copied, cropped, rotated, skewed, and otherwise modified. More complex modifications, such as blurring and sharpening images, applying gradient fills, and embossing, could be carried out much more rapidly with computers than with traditional technology (Figure 6.1).

The arrival of multimedia authoring applications provided new uses for graphics. An image could now be a button and buttons could be linked to text, other images, sounds, or video. Animated graphics could attract attention. Pie charts, diagrams, maps, and other images could be linked to text for ready illustration of facts and ideas. Graphics facilitate navigation, stimulate interest, and convey information. They are an essential component of nearly every multimedia application.

The use of computer images also poses a number of challenges. Digital image files are often very large, slowing downloads and processing. Sometimes they are noticeably inferior to their traditional counterparts. The variety of file formats in use leads to compatibility problems.

Images display differently on different monitors and printed versions often vary even more, sometimes emerging in different colors and sizes.

Multimedia developers routinely navigate between the worlds of traditional graphics and the newer digital formats. They scan images from photos or printed media and they sometimes also need to convert their digital images to formats suitable for printing. Performing these tasks efficiently and effectively requires an understanding of basic features of traditional graphics as well as mastery of current digital techniques.

In this chapter we briefly review some key features of traditional graphics and discuss the major varieties of digital images. After completing this chapter you should understand:

- Key elements of traditional print graphics such as contones, line art, linescreen, and CMYK color
- Features, uses, and development considerations for bitmapped graphics including spatial resolution, color resolution, device dependence, indexing, dithering, and file formats
- Features, uses, and development considerations for vector-drawn graphics including vectors, layers, grouping, device independence, and autotracing
- Essentials of 3-D graphics such as modeling, surface definition, scene composition, and rendering
- Basic guidelines for the use of graphics in multimedia applications

6.1 Traditional Graphics

There are several traditional graphics concepts that are important for multimedia developers. These include image types (contones, line art) and basic aspects of the process of reproducing images (linescreen, halftones, CMYK color).

Contones and Line Art

A **contone** is an image that is composed of continuously varying shades of color. A traditional black and white photo, for instance, is a contone image made up of continuously varying shades from white, to grays, to black (Figure 6.2). In computer graphics, these are called **grayscale** images.

Another technique for producing images is line art. In **line art**, combinations of lines are used to create images. Because each line is distinct, line art is not continuous tone. Line art uses only two colors. These are usually black and white, though other combinations may be used (for example, blue on yellow). The terms *1-bit* and *bitmap* are often used for line art in computer graphics (Figure 6.3).



Figure 6.2 A contone image.

Image Reproduction

There are several traditional techniques for reproducing images. Sometimes copies are made using the same technology that produced the original: a painter copies an original masterpiece; another photographic print is made from an original negative. These methods can produce high-quality reproductions but they are not suitable for making copies for mass distribution. To reproduce paintings, photos, drawings, and other graphic works in books, magazines, and newspapers, another strategy is needed.

Making a negative image of the drawing, as in a woodcut, is one way of reproducing line art. The wood block is then inked and pressed to a paper surface. Creating the block is time consuming and a new woodcut is needed for each new image. A more flexible approach uses lines of very small dots to reproduce the image. These are then rearranged to reproduce other line art images. This is the technique used by printing presses—images are made up of dots of ink. Large dots produce a coarser copy with less detail; small dots preserve more of the original image.

The size of the dots making up an image is indicated by the *linescreen* or lines per inch (lpi) used in the printing press. Newspaper presses use larger dots, for instance, 85 per inch (an 85 linescreen, or 85 lpi). Higher-quality magazines use smaller dots, resulting in linescreens of 150 lpi or more.

Contone images can also be reproduced with dots of ink. The various shades of gray in a printed black and white photo use dots of black on a white background.



Figure 6.3 Line art.




Figure 6.4 Halftone image. Grays are made from dots of black and white.

Concentrating the dots produces darker grays, wider spacing results in lighter tones. These images are called **halftones** because only half of the original tone is used to print the image—black/white, no grays (Figure 6.4).

The black dots making up these images are not necessarily the same size. Larger dots may be used for darker areas. The shape and pattern of dots is also often varied—dots may be round or elliptical and may be arranged as lines or crosses, for instance. The particular pattern used is called the *halftone screen* (Figure 6.5).

The various sizes and patterns of the dots used in printing can be seen using a magnifying glass and may be apparent to the naked eye in lower linescreens such as news-




Figure 6.5 (A) Halftone—Line shape (35 lpi); (B) Halftone—Cross shape (35 lpi).

papers. One reason that a basic knowledge of linescreens is important to multimedia developers is that scanners can also detect these patterns. This sometimes results in distortions in scans made of printed images.

CMYK Color

Color contone images are also printed with dots of ink, but in this case more than two colors are used. In the common “four-color” printing process, dots of four different transparent inks are combined to reproduce the various colors of the original. The colors used are cyan, magenta, yellow, and a key color, which is usually black. This is so-called **CMYK** color (Figure 6.6). Very small dots of the correct combinations of these few pigments can reproduce many different colors. (Equal amounts of cyan and magenta, for instance, will produce a blue.)

Color is created on printed surfaces through a **subtractive** process—light from an independent source (the sun, incandescent or fluorescent light, etc.) is reflected from the surface. The pigments used to form the image absorb (or *subtract*) some of the colors from the white light. The remaining colors reach the eyes to produce the image.

The color on computer monitors, by contrast, is **additive**—color is produced by adding together varying amounts of red, green, and blue light. Developers of computer graphics often have to convert from the RGB (red, green, blue) format used on monitors to CMYK when their images need to be professionally printed. Many graphics programs can convert between the two color models but the match may not be exact. One reason for this is that the two approaches use fundamentally different forms of color production. Computer monitor color is additive; printed color is subtractive.




Figure 6.6 CMYK color. See Color Plate 6.

6.2 2-D Computer Graphics

Computers create either 2-D (width and height) or 3-D images (width, height, and depth). There are two main types of 2-D computer graphics: *bitmapped* and *vector drawn*.

The bitmapped approach is particularly well suited for images with fine detail, such as paintings or photographs. Vector drawing is used for graphic designs ranging from simple drawings and logos to sophisticated artistic creations (Figure 6.7).

Bitmapped Graphics

A bitmapped graphic is very similar to a traditional mosaic. A *mosaic* is an image made up of many small, colored elements such as pieces of stone, tile, or glass (Figure 6.8). The overall image is a blend of each colored element.

Bitmapped images are also created as a pattern of discrete elements. The elements in this case are called **pixels**, or “picture elements.” Pixels are usually defined as small squares. Each pixel is assigned a code that designates its



Figure 6.7 Vector graphic (Adobe Illustrator sample file).



Figure 6.8 Ancient mosaic (Ephesus). See Color Plate 7.

color. The number of bits used in the code determines the number of different colors that can appear in the image. One bit allows any two colors to be represented. Each additional bit doubles the number of colors: 2 bits broaden the color range to 4, and so on. The location and color of each pixel is recorded in a rectangular grid of rows and columns called a *matrix* or *array*. The array is a mapping of the locations and colors of the pixels that compose the image, or a **bitmapping**.

Types of Bitmapped Images

There are three major types of bitmapped images: line art, grayscale, and color.

The term *bitmap* is misleading because 1-bit images are only one kind of bitmapped graphics—but the term is well entrenched in the computer industry.

Line Art As in traditional printing, computer-generated line art is produced using just two colors, usually black and white. For each pixel of the image only a single bit is required—for instance, 0 for black or 1 for white. Because only one bit is used, line art images are also often called **bitmaps**.

Line art provides crisp, clear images and is useful whenever the sharp division between black and white is appropriate. Diagrams, charts, handwritten signatures, and pen and ink illustrations are often represented in bitmap mode. Images that use color or shades of gray can also be converted to bitmaps when a reproduction that reduces the image to simple lines is desired. In these cases, darker colors or shades of gray are represented as black, with lighter shades all converted to white. Graphics programs allow users to specify the threshold at which a shade will be converted to black or white. Another important advantage of line art is its relatively small file size.



Figure 6.9 A grayscale image.

Grayscale Images Grayscale images are composed of black, white, and different shades of gray (Figure 6.9). These are the so-called black and white images of traditional graphics. Computer grayscales are generally 8-bit images. This makes possible 256 gradations of shading, enough for excellent digital versions of black and white photos. Grayscale is also effective in representing the variations of shading in many drawn and printed noncolor images.

Grayscale versions of pure black and white line drawings, on the other hand, are often less clear than line art would be. The incorporation of slight shifts away from pure black or white tends to make the edges of the lines somewhat blurry in grayscale images.

Color Bitmapped Images Bitmapped color images consist of patterns of colored pixels. The number of colors that can be represented depends on the number of bits used to encode each pixel. This is known as the **bit depth** of the graphic. As previously noted, a 1-bit image can produce black and white line art images. One bit may also be used to designate two other colors—red and blue, for instance. The most common bit depths for color images are 8-bit (256 colors) and 24-bit (16.7 million colors). If the range of color in an image is limited, 8-bit images are often adequate. For photo-realistic results, however, 24-bit color is usually required.

A **color palette** is a set of specific colors available to the computer at any given time. Just as painters can choose to place different colors on their palettes for different paintings, so too can computer artists designate different palettes for their digital images. Specifying a palette (sometimes also called a *CLUT*, or Color Look-Up Table) of 256 (2^8) selected colors produces 8-bit color. Macintosh and PC computers use different 8-bit palettes. As a result, images displayed on monitors using 8-bit color may differ on the two types of machines. The “web-safe” palette is made up of a selection of colors that are common to these two types of computers. Images that are created using this specialized palette will appear more or less the same on both platforms. This is a significant advantage for developers of web-based applications.

Twenty-four bit color images are defined by a different technique. Computers display color by combining different amounts of red, green, or blue light. Most 24-bit color encodings assign 8 bits to each of the three color channels, telling the computer how much of each type of light to blend together to produce a particular color. A value of 0 for each channel produces black. The maximum value (255) for each channel produces an intense white (equal amounts at lower values produce various shades of gray). Other values produce all the colors in-between. For instance, values of 255 for red and green and 0 for blue produces a bright yellow. The result is 16.7 million possible colors ($256 \times 256 \times 256$). Higher bit depths are also used. Thirty-two bit color makes another 8-bit channel available for additional image properties such as transparency or special effects. Forty-eight bit color assigns 16 bits to each of the three channels. This produces a possible range of over 281 trillion different colors, permitting more accurate sampling and color reproduction by scanners and cameras.

Bitmapped graphics programs generally allow developers to choose colors by specifying values for each of the three color channels. They also often support other popular color models such as CMYK and HSB (see Figure 6.10 and “HSB Color”).




Figure 6.10 Color picker with HSB, RGB, and CMYK color models (Photoshop). See Color Plate 8.

Bitmapped Image Quality and File Size

Because bitmapped graphics files contain information about each individual pixel in the image, they are often very large. A full-screen black and white picture on an 800×600 resolution monitor requires 480,000 bits (800×600) or nearly 60 kilobytes (KB) of

HSB Color

Color can also be defined by hue, saturation, and brightness. This is the HSB color model.

Hue is spectral color. Hue is specified by degrees beginning with reds (0 degrees) and ranging through yellows, greens, blues, and violets back to reds (359 degrees).

Saturation is the strength or purity of a color. Saturation is determined by the amount of gray added to a hue. The purest color is fully saturated—it contains no gray.

Brightness is the lightness or darkness of the color. Brightness is determined by the amount of white added to a hue. More white creates a brighter color.



The HSB model allows developers to specify colors using sliders for hue, saturation, and brightness. The HSB sliders above are from Flash MX. A medium green has been specified with a hue of 124 degrees, saturation at 91%, and brightness of 69%.

information. Full-fidelity color (24 bits per pixel) increases the file to 1.4 megabytes (MB). The size of a multimedia application can swell rapidly as high-quality graphics are added. To conserve storage and processing resources, developers often must make compromises in the quality of bitmapped graphics. Making the right choices requires an understanding of the factors that determine image quality.

The Quality of Bitmapped Images: Spatial and Color Resolution

The quality of a bitmapped image is determined by two factors: the density of the pixels, or **spatial resolution**, and the number of different colors each pixel can display, or **color resolution**.

Spatial Resolution The spatial resolution of images displayed on monitors is measured in **ppi** (pixels per inch). When the image is printed, spatial resolution is given as **dpi** (dots per inch). Scanners, digital cameras, and software for creating bitmapped images typically allow for different spatial resolution settings.

In general, higher spatial resolution captures more detail and produces sharper, more accurate images. This is because high-resolution images are made up of many very small, closely packed pixels. Lower spatial resolution uses fewer pixels, each of which must be larger than those of a high-resolution image. Because pixels can have only one color, an image with a low spatial resolution has larger areas of any given color and will capture less detail. Low spatial resolution produces images that appear fuzzy or blurred compared with their higher-resolution counterparts (compare Figures 6.11 and 6.12).



Figure 6.11 An image at 200 ppi. See Color Plate 9.



Figure 6.12 The same image at 50 ppi. See Color Plate 10.

Although higher spatial resolution produces more detailed images, it is not always desirable to create or capture a bitmapped graphic at the highest possible ppi. One reason for this is that file sizes are larger for high-resolution images. If a lower resolution produces an acceptable image, it should generally be used to reduce the overall file size of the application. A second important consideration is that bitmapped graphics are *device-dependent*.

Spatial Resolution and Device Dependence In discussions of spatial resolution, **device-dependent** means that the dimensions at which an image is displayed depend on the spatial resolution of the output device. Computer monitors, for instance, are designed for relatively low spatial resolution, generally in the range of 72 ppi (Macintosh) to 96 ppi (PC). Printers, on the other hand, often produce output with much higher spatial resolution. A bitmapped image with a spatial resolution of 300 ppi will print in its original dimensions (for instance, 3" × 4") on a 300 dpi printer. On a computer monitor, however, the image will be greatly enlarged. The 300 pixels in 1 inch of the image are spread over more than 4 inches of a Macintosh screen (Figure 6.13). To display the image at its intended size we must reduce the spatial resolution to match the monitor's capabilities. In the case of a Macintosh monitor, this would mean resampling the image to a resolution of 72 ppi. The practical consequence of device-dependence is that different files are needed to produce the same size output on devices with different resolutions. Multimedia developers therefore often produce bitmapped images in several spatial resolutions to match their intended use (monitor, projector, low- or high-resolution printing, etc.).

Resampling a Bitmapped Graphic The need to produce bitmapped graphics files at different spatial resolutions often leads to **resampling**, the process of increasing or decreasing the number of samples described in the file. Popular image-editing programs such as Photoshop allow users to select or deselect resampling when they alter image dimensions (Figure 6.14). Adding samples to increase the spatial resolution of a file is known as **upsampling**. Reducing the number of samples in an image is called **downsampling**. Because each sample represents a pixel, upsampling increases the number of pixels described in the file while downsampling reduces the number of pixels.




Figure 6.13 The same image on a Macintosh screen at 72 ppi (top) and at 300 ppi (bottom).




Figure 6.14 Photoshop dialogue box to select or deselect the resampling option.

Upsampling is used to enlarge the physical dimensions of an image on a given device. Figure 6.15 shows a dialogue box from Photoshop in which image dimensions were increased from 2" × 2" to 3" × 3" using resampling.




Figure 6.15 Image dimension is increased from 2" to 3". Note the change in pixel dimension and file size.

Because the image was enlarged, upsampling was required to produce the additional pixels. The "pixel dimensions," or number of pixels described in the file, increased from 300 to 450 while the file size increased from 88K to 198K. Upsampling is also used to maintain the original physical dimensions of an image when it is produced on another, higher-resolution device. For example, an image that is displayed on a computer monitor at 2" × 3" will require additional pixels to be produced at the same physical dimensions on a 300 dpi printer.

Unfortunately, upsampling usually degrades the appearance of a graphic. In effect, the computer has to guess the color values for the additional pixels. While there are a variety of sophisticated algorithms for upsampling, the process usually produces an image that is noticeably inferior to one originally captured by a scanner or camera at the higher resolution. This is the reason that multimedia developers pay close attention to the intended use of bitmapped graphics: images that may need to be enlarged on screen or printed at high quality should always be captured or created at high spatial resolutions.

Downsampling, on the other hand, generally results in smaller images of very good quality. In this case, the computer is dropping information that is contained in the file, rather than adding new information. An image captured at a high resolution can be readily reduced to display with excellent quality at the lower resolution of a computer monitor. For instance, a developer may have a high-resolution source image from a digital camera to add to a website. Reducing spatial resolution to 72 ppi with downsampling will create a new, smaller file that displays a high-quality screen image at the intended dimensions. Given the advantages of downsampling over upsampling, a general rule of thumb is to capture at the highest possible spatial resolutions whenever possible.

The effects of upsampling and downsampling can also be observed on-screen when bitmapped graphics are resized in image-editing programs. Stretching the bounding box of a bitmapped graphic forces the computer to generate more pixels to fill the larger area, degrading image quality. Reducing a bounding box dimension produces a smaller image that usually retains the quality of the original (see Figure 6.16).




Figure 6.16 Stretching the bounding box of a bitmapped graphic degrades the image quality. See Color Plate 11.

Resizing Bitmapped Graphics without Resampling A bitmapped graphic can also be resized without resampling, that is, without changing the total number of pixels described in the file. This is usually done to change the size of a printed image without

introducing the distorting effects of upsampling. The printer produces the larger image at a lower, but acceptable, resolution. There are limits to enlargement without resampling. The lower-resolution printout contains the same number of pixels, which must now be physically larger to fill the expanded area of the new image. Excessive enlargement distorts images by producing a blocky, mottled surface appearance and accentuating the stair-stepped, jaggy appearance of diagonal lines (Figure 6.17). Photoshop warns users when resizing without resampling that it will reduce the resolution of printed output to unacceptable levels (for instance, to less than 150 dpi). Reducing the size of a bitmapped image without resampling, on the other hand, generally produces very acceptable results. Pixels are packed more closely together, producing a high-quality printout.

Resizing without resampling has no effect on an image displayed on a monitor. With no change in numbers of pixels, a computer monitor will display the image just as it did before, at exactly the same physical dimensions on screen.

Color Resolution The second factor determining the quality of a bitmapped image, color resolution, is a measure of the number of different colors that can be represented by an individual pixel. As noted above, the number of bits assigned to each pixel, or bit depth, determines color resolution.

Simple images with a limited range of colors do not require high color resolution. A drawing using 16 distinct colors, for example, would only require 4 bits per pixel. Using a code with greater bit depth produces a larger file with no increase in quality.

Other types of images, such as photographs, often contain a very wide range of distinguishable colors and do require greater color resolution. In fact, producing “photo-realistic” digital images typically requires millions of possible variations of color for each pixel.

The Effects of Low Color Resolution Low color resolution means that fewer colors will be available. If the image being displayed contains a small number of colors, low color resolution is not a problem. Black and white line art images, for instance, can be precisely duplicated on a computer using a 1-bit palette containing the colors black and white.

In many cases, however, images will contain colors not found in a lower resolution palette. Missing colors will have to be matched to the closest color available in the palette. This is called *quantization*.

Quantization is the process of rounding off a sample to the closest available value in the digital code being used. A grayscale image, for instance, contains shades of gray as well as black and white. If a grayscale is displayed on a computer using the lowest color resolution of 1-bit, darker shades of gray will be quantized as black with lighter shades



Figure 6.17 Excessive enlargement distorts images by accentuating the stair-stepped appearance of diagonal lines (chair spindles).



Figure 6.18 Grayscale image (8-bit).



Figure 6.19 Image converted to a bitmap (1-bit).

becoming white. Significant image detail may be lost in the process (compare Figures 6.18 and 6.19).



Figure 6.20 Quantization may produce color banding. See Color Plate 12.

The effects of quantization in color images will vary greatly depending on the range of colors in the image and the specific color palette being used. In general, quantization leads to noticeable breaks in shades of continuous color because it is the subtle variations that are lost when values are rounded. This is known as **color banding**. In Figure 6.20, the bit depth of the lower image was reduced, resulting in bands of separate colors rather than the smooth transitions of the upper image.

In photographs, quantization often produces larger areas of a single color. This may create a “mottled” or “blotchy” effect. Figure 6.21 is a 24-bit image. With millions of possible colors to choose from, the photo captures the different shades of brick and nicely reproduces the surfaces of the plants and water. Figure 6.22 shows the effects of quanti-



Figure 6.21 Venice canal—24 bit. See Color Plate 13.



Figure 6.22 Venice canal—3 bit. See Color Plate 14.

zation. This 3-bit indexed version of the original presents the image using only 8 colors. Large areas now share a common color producing a less-detailed, coarser image.

Color Resolution: Indexing and Dithering The effects of low color resolution can often be mitigated by color indexing or by another process known as dithering.

In **color indexing** a specific palette of colors is chosen to optimize the appearance of the lower-resolution image. The choice of colors for this special palette is made in several different ways. In **adaptive indexing**, colors are selected based on an analysis of the dominant colors in the original. If the image contains many shades of green, the indexed palette will use more greens. In another approach, **perceptual indexing**, the selection is based on the colors to which the eye is most sensitive. Another form of indexed color is the **web-safe color palette**. This palette specifies 216 colors that will be displayed more or less the same by different web browsers and operating systems (notably Macintosh and the PC) on computers that are limited to 8-bit color. Image-editing programs allow users to select different indexing options, including the number of colors in the indexed palette.

Indexing significantly improves the quality of images with lower color resolution but it can have a price. If a series of images with different optimal color palettes is displayed to a monitor, a flash of unusual colors may occur as the display shifts to the new palette. This is known as **palette flashing**. Using the same indexed palette for all images eliminates palette flashing, but some images may have less than optimum appearance.

Dithering is the process of combining pixels of different colors to produce another color that is not available. Dithering is based on the fact that the eye will perceive a grouping of small areas of different colors as a blend of those colors. For example, different shades of gray can be produced from different patterns of closely spaced black and white pixels. Combinations of red and yellow pixels can produce orange, and so on. This technique is also often used in color printing. Dithering can significantly improve image quality without increasing bit depth. As in indexing, a variety of strategies for dithering are available. Dithering can be applied in regular patterns or diffused to random patterns. Developers can also control the amount of dithering applied to optimize the appearance of their images.

Color indexing and dithering are still important considerations for developers who need to reduce image file sizes to optimize the performance of their applications, particularly on the Web. Much of the original impetus for these strategies, however, was based on the limitation of earlier multimedia computers to 8-bit color. As the availability of 24-bit “true-color” computers expands, concern about issues such as web-safe palettes and palette flashing will continue to diminish.

Sources of Bitmapped Images

Multimedia developers have five main sources for bitmapped images: paint programs, digital cameras, scans, clip art, and screen grabs.

Paint Programs A **paint program** is specialized software for creating and editing bitmapped graphics. Paint applications such as Corel Painter or Adobe Photoshop include many tools built on a painting metaphor—brushes of various sizes and shapes, color palettes, paint buckets, airbrushes, and so on. Paint programs allow developers to create original art and edit existing images. In addition to tools for creating shapes, typical

editing options include paint opacity (the degree of transparency), color adjustments (brightness, contrast, saturation), fill patterns (such as checkerboard, bubbles, and wrinkles), gradient fills (fills with different colors blending from one to another), and special effects such as sharpen, smear, or emboss. Paint programs provide exceptional editing control by allowing users to manipulate each pixel of an image.

Because digital photographs are also bitmapped images, photo editing is a popular application of paint programs. Rotating, cropping, adjusting brightness and contrast, applying specialized effects (sharpen, blur, fill flash), and a host of other transformations can be easily previewed and carried out. The same procedures can be applied to other types of bitmapped images such as scanned objects and original digital artwork. Paint programs allow users to save bitmapped files in a variety of formats to match the intended use of the image (see the upcoming section “Bitmapped File Formats”).

Digital Cameras Digital cameras create bitmapped images by capturing information about the color and brightness of many very small samples of an image. The size of the individual picture elements, or pixels, sampled by the camera determines the camera’s spatial resolution. This is usually measured in **megapixels**, or millions of pixels. A 10-megapixel camera is capable of capturing an image at a spatial resolution of 4216×2368 pixels ($4216 \times 2368 = 9.9892$ million). Pixels are usually sampled by charge-coupled devices (CCDs). A CCD measures the light from a segment of the image and records it as an electrical signal. This information is then digitally encoded and stored as one of the samples making up the image (see Chapter 3).

Still cameras with much higher spatial resolution are available. High-end digital studio cameras are intended for highly detailed professional work. These models support resolutions of 8944×5032 (45 megapixels) or more. Consumer-grade cameras in the 10- to 15-megapixel range have hastened the shift from traditional to digital photography.

As with all bitmapped images, higher spatial resolution translates to larger files. Different quality settings allow digital cameras to produce lower-resolution images with smaller file sizes. This allows more images to be stored in a camera’s memory. Because bitmapped files are device-dependent, the choice of the camera quality setting will be determined by the intended use of the image. Images that will be printed at high resolution or larger sizes will require higher spatial resolution than those intended for display on monitors. For instance, a $3'' \times 5''$ print at 300 dpi requires an initial spatial resolution of $900 \text{ ppi} \times 1500 \text{ ppi}$; the same size image on a Macintosh monitor requires a resolution of only $216 \text{ ppi} \times 360 \text{ ppi}$.

Cameras may include built-in memory and generally also support removable memory cards. Cards are manufactured in several different standards (CompactFlash, SmartMedia, etc.) and in different capacities ranging from 2 gigabytes (GB) to 64 GB or more. The images stored in a camera’s built-in or removable media can be uploaded to a computer directly using interfaces such as USB or FireWire.

For a description of scanning technology and different types of scanners, see Chapter 3, “Computer Hardware.”

For a description of the scanning process see Appendix B.

Scanning Scanning is an important source of graphics in multimedia applications. In addition to photographs and printed images, scanners can also be used to produce digital versions of original works such as crayon sketches or paintings. Unusual designs can also be created from scans of three-dimensional objects such as coins or flowers.

Clip Art **Clip art** is “canned” artwork available on disk, online, or as part of paint or draw programs. Clip art has many advantages. It is ready to use, easily obtained, and available in many file formats. It offers a wide choice of subjects and styles and can often be distributed as part of a multimedia application at low cost. In fact, some clip art is royalty-free. Licensing agreements for clip art do vary widely, however, and developers need to review the terms of use carefully.

The principal drawback to clip art is that others have access to it as well. Extensive use of clip art makes it difficult to maintain the unique or distinctive appearance of a multimedia production.

Screen Grabs The images displayed on a computer monitor are bitmapped graphics. Both Macintosh and Windows computers can capture these screen images and save them as files that can then be used in multimedia applications.

Almost anything displayed on screen can be captured. **Screen grabs** or “screen dumps” are often used to illustrate steps or procedures in manuals or tutorials (Figure 6.23). Using paint programs, any part of the screen image can be selected and edited. The principal disadvantage of screen grabs is that they are relatively low-resolution images that do not enlarge well and are often not suitable for printing.

Bitmapped File Formats

Bitmapped file formats fall into three broad categories: native formats used by image-editing programs, general-purpose bitmapped-only formats, and metafiles. *Native formats* (such as Photoshop .psd) contain information essential to specific editing software. Generally, files in a native format cannot be used by other applications unless they are converted to a general-purpose format. *General-purpose formats* support widespread distribution either within or across platforms. Many different types of programs will be able to use these files. *Metafiles* are formats that can contain both bitmapped and vector images.

One of the most important characteristics of bitmapped graphics is relatively large file size. Many multimedia applications, particularly those intended for delivery on the Web, require significant image compression for efficient delivery. Several compressed file formats have been developed for bitmapped graphics. Some are lossy while others are lossless. **Lossy** formats discard some of the information in the original image. **Lossless**




Figure 6.23 A screen grab.

Using the Mac OS:

- Press “Command-Shift-3” to capture the entire contents of the desktop. File “Picture1.png” is saved on the desktop.
- Or, select Finder/Services/Grab option to select a portion of the screen to save as “Picture.png.”
- Images can be further edited in any bitmapped application.

Using Windows OS:

- Press “Print screen” command to save the contents of the desktop to the clipboard.
- Open Word or image editor, paste the image to a new file. Edit and save.
- Or, choose the “Start Menu” to locate the *Snipping Tool*. This program allows selection, editing, and saving of a screen display segment.

formats reencode image information in a new, compressed form but recover all the original information on decompression.

Commonly used bitmapped and metafile formats include: PICT, BMP, TIFF, JPEG, GIF, and PNG. Developers choose among these formats based on application requirements, file compatibility with editing and authoring software, and compatibility with delivery platforms (Windows, Macintosh, etc.).

PICT—Macintosh PICTure format. PICT is a relatively old format that is widely supported by Macintosh applications. It supports different compression levels and 24-bit color depth. PICT is a metafile format: files can be either bitmapped or vector-drawn images. PICT is a flexible format, appropriate for most applications on the Macintosh platform.

BMP—Windows BitMaPped file. BMPs support several color resolutions including monochrome bitmap, 4 bit, 8 bit, and 24 bit. Compression is optional. BMPs are often used for Windows screen grabs and screen background images (wallpaper). BMP is a well-established format that is supported by many PC applications.

TIFF—Tagged Image File Format. TIFF is a very versatile cross-platform format that supports all major color modes (bitmap, grayscale, all color depths, and both RGB and CMYK). TIFF was originally designed for use with scanners. It is the format multimedia developers usually use both for scanned images and for files to be used in authoring applications. TIFFs can be compressed using a lossless compression called *LZW* (for the names of the developers, Lempel, Ziv, and Welch). The TIFF format is also suitable for professional printing, unlike PICT or BMP. TIFF is a good choice for the vast majority of non-web images.

JPEG—Joint Photographic Experts Group. JPEG is a cross-platform format designed to efficiently compress bitmapped images such as photographs that contain a wide range of colors. It is widely used in digital cameras and is the format of choice for photo-quality images on the Web. JPEG supports 24-bit color and interlacing.

Interlacing, as applied to network transmission of images, is the process of progressively displaying an image: incomplete, low-resolution versions can be seen before the complete file is downloaded. This avoids having a blank screen while the download process is underway.

JPEG compression is lossy—some information is discarded and cannot be recovered. Developers can control the amount of information lost. A JPEG image can be saved without compression or with one of several different levels of compression. Saving without compression preserves all the information from the original. This is usually not advisable, however, because minimal compression produces a much smaller file with little loss of quality.

Repeatedly saving a JPEG image with compression progressively degrades the image. For this reason, developers should edit images in another file format, such as the native format of the editing software or TIFF. Only when the editing process is complete should the image be saved as a JPEG.

GIF—Graphics Interchange File (pronounced either “jif” or “gif,” with a hard “g” as in “gift”). GIF is a cross-platform format with lossless compression. CompuServe originally created it for images transmitted over relatively slow Internet connections. The maximum color resolution for a GIF is 8 bits (256 colors). Lower bit depths can

be used, further reducing file size. GIF supports interlacing, transparency, and a simple form of animation. GIF animation uses a “page-flipping” approach, rapidly displaying a series of different still images to suggest motion. GIF animations are very popular on the Web because of their low file size. GIF is a good choice for line art, grayscale, and color images with a small number of solid colors. It is not appropriate for most color photos because of its limited color resolution.

PNG—Portable Network Graphic (pronounced “ping”). PNG is a cross-platform, lossless compression format that was created as a free replacement for GIF, which required commercial developers to pay licensing fees. PNG supports indexed color, grayscale, and true-color images with resolutions up to 48 bits. PNG also supports transparency and interlacing. It does not directly support animation. PNG is a much more versatile format than GIF because of its support of high-resolution color images. Although intended primarily for web applications, PNG rivals the flexibility of TIFF and is very popular with multimedia developers.

The RAW File Format

RAW is a bitmapped graphic format that is becoming more familiar in multimedia development. Actually, RAW is a family of formats, rather than a single standard. They are proprietary file formats used by camera manufacturers to save digital photos in a form that preserves more image information than is captured by JPEG. RAW image files are generally larger than those of other formats. They are intended for use in photo-editing software where they support a wider range of editing options because they contain more information about brightness and other image properties. RAW images are converted to JPEG, TIFF, and other formats for use in multimedia applications.

6.3 Vector-Drawn Graphics

In bitmapped graphics, the computer is given a *detailed description* of an image that it then matches, pixel by pixel. In vector-drawn graphics, the computer is given a *set of commands* that it executes to draw the image.

Vectors, Shapes, and Drawn Images

A **vector** is a line with a particular length, curvature, and direction. **Vector graphics** are composed of lines that are mathematically defined to form shapes such as rectangles, circles, triangles, and other polygons. Vector-drawn images are made up of combinations of these shapes. **Draw programs** are the software used to create vector-drawn graphics. They can produce a wide range of images from simple line drawings to complex architectural renderings and original art works (Figure 6.24).

For relatively simple images, the list of drawing commands takes up much less file space than a bitmapped version of the same graphic. A draw program might use a command similar to “RECT 300, 300, RED” to create a red square with sides of 300 pixels. The file for this image contains 15 bytes that encode the alphanumeric information in the command. The same image could also be created with a paint program as a bitmapped graphic. Using 8-bit color resolution (one byte per pixel), this file would require 90,000 bytes




Figure 6.24 Adobe Illustrator image with Tool and Layers palettes.

(300 × 300). The much smaller file sizes of drawn images can be a significant advantage for multimedia developers. Another advantage of vector-drawn graphics is smooth scaling. Vector images are enlarged by changing the parameters of their component shapes. The new image can then be accurately redrawn at the larger size without the distortions typical of enlarged bitmapped graphics. Images that are needed in several sizes, such as a company logo, are often best handled as vector-drawn graphics.

The principal disadvantage of vector-drawn graphics is lack of control over the individual pixels of the image. As a result, draw programs cannot match the capabilities of bitmapped applications for display and editing of photo-realistic images.

Tools, Layers, and Grouping

Many of the tools used in draw programs resemble those of the traditional draftsman. These include pen tools; fixed shapes such as circles, ellipses, and rectangles; polygons; and Bezier curves. The shapes created in draw programs include anchor points called **handles**. Handles are “grabbed” and pulled to resize or reshape an object. “Hot spots,” such as the corners of rectangles, are used to rotate an object by clicking and dragging.

Objects are drawn on **layers**. Objects on higher layers overlap and usually cover those in lower layers. Layers make it possible to edit each object separately without affecting other components of the image. When all the objects are properly shaped, scaled, colored, and placed, they are grouped. *Grouping* objects freezes their properties by joining them together on a single, new conceptual layer. Grouped objects can then be moved or combined with other objects as a unit. *Ungrouping* returns the component objects of an image to their individual layers where each can once again be edited.

Device Independence

Draw images are **device-independent**—the same file can be used with different devices without altering the size of the image. Bitmapped images require different files for devices using different resolutions. For example, a 72-ppi file is appropriate for use on a monitor but a higher spatial resolution is preferred for printers. Draw files are commands for drawing. Different devices simply follow those commands at their own output resolutions. This preserves the original dimensions of the image.

Making Drawn Graphics from Bitmapped Images: Autotracing

Drawn graphics can also be produced from bitmapped images through autotracing. In **autotracing**, the original bitmapped image is analyzed for separate areas that can be treated as shapes. These shapes are then mathematically defined to convert the image to a vector graphic.

Autotracing is quite efficient with relatively simple bitmapped images. But if the image is complex, containing many constituent shapes and subtle shifts of color, the new vector file will not preserve the appearance of the original and may actually be larger. Judicious use of autotracing can significantly reduce file sizes and can also create interesting artistic effects (Figure 6.25). Autotraced files are particularly useful in web-based applications where their smaller size reduces download times.

Making Bitmapped Graphics from Vector Graphics: Rasterizing

Vector graphics are readily converted to bitmapped images by a process called **rasterizing**. Rasterizing rapidly samples the vector image and saves it in bitmapped form.



Figure 6.25 Autotracing a bitmapped image (left) can reduce the file size and create interesting artistic effects (right). See Color Plate 15.

Vector-based editing programs such as Adobe Illustrator can perform the conversion. Vector graphics displayed on screen can also be captured as bitmaps through simple screen grabbing. Developers often create graphics in draw programs to take advantage of strengths such as scalability and small file size and then convert them to the more widely used bitmapped format.

File Formats for Vector Graphics

Like bitmapped formats, vector graphics files fall into three categories. Native formats, such as Adobe Illustrator .ai, support the needs of specific editing software while general-purpose formats are either vector-only or metafiles. General-purpose vector formats include EPS, PDF, and SVG.

EPS—Encapsulated PostScript. EPS is a variant of PostScript (PS) that supports page preview. EPS uses PostScript’s page description language to draw vector graphics. It can also contain bitmapped information, though it is not itself a bitmapped format.

PDF—Portable Document Format. PDF is a widely used, very versatile cross-platform file format for encoding full pages of text and graphics. PDFs can contain both bitmapped and vector images. Adobe Illustrator vector images can be saved in a form that preserves the editing capabilities of the native .ai format but, in general, PDF files support only limited editing. PDF files require Acrobat reader or a similar program to be viewed. Acrobat is free and widely distributed, making PDF a very practical distribution format.

SVG—Scalable Vector Graphics. The newest of the general-purpose vector formats, SVG supports 2-D graphics on the Web. SVG is built on XML (eXtensible Markup Language) and supports still images, animations, and various forms of user interactivity.

6.4 Bitmapped and Vector Graphics Compared

The two major types of graphics are each optimized for particular uses. Multimedia developers choose between paint (bitmapped) or draw (vector) programs based on their knowledge of the strengths and weaknesses of each and the needs of the project. The relative advantages and disadvantages of the two approaches can be summarized as follows.

Paint Advantages

- Accurate representation of complex contone images such as photographs
- Full-featured photo editing (sizing, cropping, tone and color adjustments, special effects, etc.)
- Wide range of artistic effects (gradient fills, smudges, blurs)
- Precision editing (can edit individual pixels)

Paint Disadvantages

- Large file sizes
- Loss of precise shape when scaled or rotated
- Device-dependent image resolution

Draw Advantages

- Smooth scaling and reshaping (no jaggies)
- Ease of editing objects
 - Layers
 - Grouping/ungrouping
- Low file sizes
- Device-independent image resolution

Draw Disadvantages

- Less detailed representation of complex contone images
- No photo-editing capability
- Limited artistic control

Paint and draw programs continue to improve. In the process, software developers often find ways to incorporate the strengths of the alternative approach while limiting some of the inherent disadvantages of their own. For instance, the layers used in draw programs make editing an image much more efficient because one part can be changed without affecting others. Paint programs, such as Photoshop, have also adopted layers by including specialized information in their native file formats. Similarly, the subtle shifts of color in gradient fills were once the exclusive purview of paint programs. This capability has now been added to many draw programs.

Despite these improvements, fundamental differences remain. A multimedia developer would not use a draw program to adjust colorcast in a photograph. And a paint program is still a poor choice for a logo that will be resized for different uses on a website or for different types of printed output such as business cards, pamphlets, or posters.

6.5 3-D Computer Graphics

3-D graphics add realism and visual impact and they are an increasingly important area of multimedia development. They are also challenging. 3-D graphic artists must visualize

scenes in which objects can move in any direction, floating in a potentially infinite space. They must select a point of view and arrange objects to match it. They must think about light sources—the type of light, its intensity, location, and strength. Surfaces and their interaction with light must be defined. And all these elements have to be combined to produce the illusion of depth on the flat surface of a monitor or printed page.

3-D graphics applications are the sophisticated, powerful programs that make all this possible. In 2-D graphics, the computer is a helpful assistant. In 3-D graphics, it becomes a virtual partner in the creative process, using complex algorithms to create the finished images specified by the artist. There are four interconnected steps in the creation of 3-D images: modeling, surface definition, scene composition, and rendering.

Modeling

Modeling is the process of specifying the shape of a 3-D object. There are two major approaches to modeling. The first is to create a new object by combining simple cubes, cones, cylinders, and other 3-D shapes that are supplied with the graphics program. These objects are called **primitives** (Figure 6.26). *Parametric primitives* are objects that can be changed by specifying different parameters, such as the radius of a sphere. Parametric primitives can be scaled, rotated, moved, and combined to form a wide range of objects. In *constructive solid geometry (CSG)*, primitives are added to or subtracted from one another using Boolean operators (Figure 6.27). Boolean *union* joins two or more objects; Boolean *difference* subtracts one from another, and Boolean *intersection* produces just the shape shared by the objects.

More complex forms of parametric primitives may also be provided. These include objects such as plants or trees that can be adjusted according to species, trunk angle, number and size of leaves, and so on. Environmental primitives such as clouds and fire can be similarly adjusted to produce a wide range of shapes, colors, and opacities.

The second approach to modeling is to create shapes directly using a **modeler**. Four popular 3-D modeler options are *polygons*, *splines*, *metaballs*, and *formulas*.

In **polygon modeling**, the object is defined as a pattern of straight-edged polygons, usually triangles or quadrilaterals (Figure 6.28). To produce an image of the 3-D object, the computer first calculates which surfaces will be visible based on a viewing angle specified by the artist. Viewable surfaces are then divided into small polygons that define the shape of the object.

The polygon approach is similar to bitmapped 2-D graphics in that the object is defined by a fixed number of elements—polygons for 3-D graphics and pixels for 2-D bitmapped graphics. One advantage of polygon modeling is precise editing control: the individual lines and surfaces of polygons can be manipulated directly by the




Figure 6.26 Primitives. See Color Plate 16.



Figure 6.27 Boolean CSG: union (top), difference (center), intersection (bottom). See Color Plate 17.




Figure 6.28 Polygon object. See Color Plate 18.

NURBs:

- Non-Uniform—more easily bent in some areas than in others
- Rational—based on mathematically defined ratios
- B-splines—variants of Bezier curves

artist. The technique can also produce high-quality, realistic surfaces by increasing the number of polygons and manipulating their shapes and shading. The main disadvantages of polygon modeling are relatively large file sizes and scaling distortions. Increasing the number of polygons may produce files too large for some applications, such as 3-D game playing, in which images need to be generated in real time. And just as a bitmapped graphic deteriorates as it is enlarged, so too does a polygon model.

Spline modeling is curve based and is similar to two-dimensional vector graphics. The term derives from *splines*, thin strips of wood or metal that can be readily bent to guide the drawing of curves. Different forms of spline modeling are available. One popular approach is the NURB. A **NURB** is a Non-Uniform Rational B-spline. Like a vector graphic, a NURB defines an image using mathematical formulas that can be adjusted to vary its size and shape. Spline modeling does not provide the precise editing control of polygons. On the other hand, this method produces smaller files and more flexible objects. A NURB-based object can be readily enlarged without the deterioration in quality associated with the polygon approach.

Metaball modeling creates objects as combinations of elements called *blobs*. Blobs are variously shaped (spheres, cubes, cylinders, etc.) and are either positive or negative. A positive blob adds its shape to the object, a negative blob subtracts its shape. Building an object with metaballs is similar to working with lumps of clay. The technique is useful for creating objects with soft edges, such as cushions, and organic shapes, such as animal bodies (see Figure 6.29).




Figure 6.29 Negative metaball cylinder and sphere modifying a positive cube.




Figure 6.30 Formula model.

Formula modeling creates objects by specifying mathematical formulas that are subsequently drawn by the computer. This approach requires knowledge of programming and advanced mathematics. Formulas produce either simple or very complex objects that require very little file space and are drawn quickly by the computer (Figure 6.30).

3-D graphics programs typically provide a choice of modelers. Developers choose a modeling method based on the type of object to be created and the way it will be used in the multimedia application. Many objects, such as buildings or furniture, are readily modeled as polygons. Others, like animal bodies or bushes, are better represented using spline curves or metaballs. Sometimes the type of application (interactive game vs. static image) or delivery considerations (Web or DVD) favors one modeler over another. Spline and formula objects typically have smaller files and can be rapidly drawn. They are often used for games or web applications.

A modeler may also be chosen for its ability to extrude or lath. **Extrusion** is the process of extending a two-dimensional shape through space to create a three-dimensional object. For a simple illustration of extrusion, think of a two-dimensional rectangle raised in a straight path from its surface to create a three-dimensional box. Similarly, a circle can be extruded to form a cylinder. Any two-dimensional line or object can be extruded. In addition, an extrusion can be oriented to a particular view. For example, a curved line can be viewed from the top and extruded lengthwise to produce a corrugated panel or a curtain (Figure 6.31).

Lathing is the process of creating a three-dimensional object by rotating a two-dimensional line on an axis. For example, the profile of one-half of a bowl can be rotated 360° to trace the surface of the three-dimensional object (Figure 6.32).




Figure 6.31 Extrusion. A line (top right) extruded lengthwise to produce a curtain. See Color Plate 19.




Figure 6.32 Lathing. A bowl lathed from a 2-D line. See Color Plate 20.

Surface Definition

Modeling defines the three-dimensional shape of an object but not its surface texture. In **surface definition**, developers specify textures that are then applied to the model's

surface. Surfaces can be defined according to a range of materials available as menu choices—fabric, wood, stone, glass, metal, and others. These different surfaces will vary in color, in transparency, and in the ways they reflect light. Metal surfaces, such as stainless steel, for example, may be highly reflective, whereas glass may be only partially reflective. Graphic artists can vary the appearance of these surfaces by changing properties such as color, opacity, and reflectivity.

Custom surfaces can also be created as *image maps*: photos, drawings, or other images that are transferred or “mapped” to an object (Figure 6.33). Scanned photos, drawings produced with bitmapped or vector programs, and bump maps are some of the more popular sources for image maps. A *bump map* is a three-dimensional texture produced by varying shades of color. Lighter shades appear to be higher, while darker areas appear lower. Bump maps are readily created in image-editing programs such as Photoshop. The “bumpy” surface of a basketball, for instance, can be simulated as an image map and then transferred to a sphere (Figure 6.34). Another common use of image maps is the creation of labels, logos, and other designs that are then applied to the surfaces of objects such as bottles, cans, and boxes. Some programs also support the use of video as an image map, allowing animators to create realistic 3-D television or movie screens by mapping the video to previously created cabinets or walls.



Figure 6.33 Image map (above) applied to a cup.




Figure 6.34 Bump map applied to a sphere. See Color Plate 21.

Scene Composition

In **scene composition**, objects are arranged, backgrounds are introduced, environmental effects are added, and lighting is established. Arranging objects includes situating them on the *x*, *y*, and *z*-axes as well as operations such as alignment, grouping, and linking that are familiar from 2-D drawing.

Much of the realism of a 3-D graphic is produced by accurately representing the interplay of light with the various objects that compose a scene. This includes specifying the type of light, its direction, and its behavior as it interacts with the object. Types of lighting include: *omni lights* that spread light equally in all directions, like the light of the sun; *directional lights* that spread light in a specified direction; *spot lights* that focus a cone of light on a relatively small area; and *volumetric light* to represent the shafts of light from movie projectors, street lamps, and other sources. The various forms of light can usually be adjusted for properties such as brightness, color, and *attenuation*, the rate at which light intensity falls off with distance. Being able to control the color and intensity of light allows digital artists to simulate a variety of natural and artificial light sources. Lights can be located at virtually any angle and their effects—for instance, the types of shadows they cast or the way in which light is reflected or absorbed by surfaces—can also be controlled.

Rendering

Rendering is the process through which the computer creates the scenes specified by the artist. There are two main approaches to rendering: *prerendering* and *real-time rendering*. Prerendering is used for most still graphics and for animation and video with limited interactivity. Prerendering is discussed below. Real-time rendering is used for highly interactive 3-D applications such as video games. This is covered in Chapter 9, “Animation.”

Rendering is always the final step in creating a 3-D graphic but it is also a critical element in earlier stages. Artists need to be able to visualize their scenes as they place objects, plan their camera angles, add textures, and adjust lighting. They use various forms of rendering to create these test scenes (Figure 6.35).

Wire frame rendering is the simplest technique. A wire frame is a series of lines used to define the shape of an object without defining its surface. Wire frame rendering is a good choice for testing an object’s basic geometry and placement because the computer can draw a wire frame model very quickly.

To test lighting effects, surfaces must be added. To create a surface, a model is usually *tessellated*, that is, broken into a pattern of polygons. Different shading algorithms, or **shaders**, may then be used to calculate the color values of the pixels making up these polygons. *Flat shaders* render an image relatively quickly but with imperfections such as jaggies. *Smooth shaders* produce a higher quality image but at the cost of slower rendering and larger file sizes. *Ray tracing* creates a more realistic surface by tracing each ray of light and calculating its path as it interacts with objects in the scene. *Radiosity* adds even more realism to a scene by recreating the changes resulting from the interaction of different wavelengths of light. When light is reflected from an object, both its path and its quality are changed. Light striking a blue object on a white surface, for example, creates a faint glow of blue in the immediate vicinity of the object. Radiosity applies mathematical formulas to calculate the effects of the thermal radiation responsible for these color transfers. Ray tracing and radiosity are computationally demanding forms of rendering. They are sometimes used to test particular scenes but are most often reserved for the final rendering process.

After scenes have been tested and refined, the final rendering process translates 3-D information to a 2-D image for use as a still graphic or as a frame in an animation or movie. 3-D graphics programs typically provide users with a variety of controls over the final rendering process. Many finished works are intended to be photo-realistic, but other forms of rendering that simulate painting or classic cartoons, for example, may also be available. These different rendering styles are described as *rendering engines*. Once an engine is selected, the user can control a series of rendering parameters. Important photo-realistic parameters include ray tracing, shadows, reflection and refraction, bumps, transparencies, and lighting effects such as indirect lighting and skylight. Users can choose to include or omit individual effects and they can specify quality settings for those that they do include. Each effect adds to the rendering process, which can easily stretch to hours for complex images. Shadows, reflections, radiosity, realistic textures, and a host of special effects potentially affect each individual pixel of the rendered image. This results in extraordinary processing demands.



Figure 6.35 Rendering options: wire frame (top), smooth shading (middle) and ray tracing (bottom). See Color Plate 22.

Compromises are often necessary, further reinforcing the need for test renderings of image samples.

3-D graphics is one of the most creative and challenging areas of multimedia development. In the hands of skilled artists, ever more powerful hardware and software can create convincing reproductions of the world around us. They can also produce an unending stream of engaging fantasy worlds. The uses of 3-D graphics, both as still images and as the frames of sophisticated animations, will continue to expand, making it increasingly important for developers to master the complexities of modeling, surface definition, scene composition, and rendering.

6.6 Guidelines for the Use of Graphics

Graphics are a critical element in nearly all multimedia applications. Both the development process and the final product can often be improved by observing basic graphics guidelines.

1. **Identify the purpose of the graphic.**
 - To inform (maps, diagrams, pie charts).
 - To attract attention.
 - To warn.
 - To guide (navigation buttons, progress indicators, image maps).
2. **Choose the best format for each image.**
 - Paint (bitmapped) for:
 - Complex contone images (photographs, paintings).
 - Scanned images.
 - Draw (vector) for:
 - Images composed of regular shapes.
 - Images to be scaled.
3. **Match graphic design to purpose.**
 - Avoid gratuitous decoration.
 - Match style to application content and audience:
 - Whimsical, artistic, sophisticated, primitive, professional.
4. **Locate graphics. Establish a layout grid.**
 - Use similar locations for graphics with similar purposes (navigation buttons, user alerts, explanatory drawings).
5. **Preserve image quality.**
 - Store original photos, prints, and other scanned graphics carefully.
 - Avoid multiple saves in lossy compression formats (e.g., JPEG).
 - Retain copies of original, high-resolution scans.
 - Keep copies of images in native file formats of editing applications (e.g., .psd).
6. **Economize. Use graphics efficiently.**
 - Match resolution to output device.
 - Reduce sizes in image-editing software, not by dragging a new size in authoring software.

7. Organize graphics.

- Maintain folders for original images, edits, and final production versions.

6.7 Summary

Although most multimedia graphics are created for screen display, developers sometimes distribute images in printed form. They also often capture printed originals using scanners. For these reasons, key elements of traditional printing, such as contones, line art, halftones, and CMYK color remain important considerations for multimedia developers.

Digital graphics can be either two-dimensional or three-dimensional. There are two major types of 2-D computer graphics: bitmapped and vector-drawn. Bitmapped graphics are defined as patterns of pixels, or picture elements. They can include very fine detail and can be extensively edited. Developers pay close attention to spatial resolution and color resolution as they create bitmapped images using paint programs, or capture them using scanners, screen grabs, or digital cameras. The bitmapped approach is essential for highly detailed images such as photographs, but it also produces very large file sizes. These large files have given rise to a variety of compression strategies and file formats to match bitmapped graphics to their intended uses. Other challenges in the use of bitmapped graphics include device-dependence and scaling limitations.

Vector-drawn graphics are defined as a set of commands that the computer uses to produce an image for display or printing. Drawn graphics range from simple blueprints to sophisticated, naturalistic images produced by skilled illustrators. The advantages of vector-drawn images include much smaller file size, excellent scaling, and device-independence. Their principal disadvantage is that they do not support the detailed, pixel-level editing of bitmapped graphics and so are not suitable for photographic images.

3-D graphics take advantage of powerful computer processing to create a different type of digital image. In 2-D graphics, whether bitmapped or drawn, the artist uses digital versions of traditional tools to directly create a finished image. In 3-D graphics, the artist skillfully combines elements to specify an image that only the computer itself can produce in finished form. This new relationship between artist and computer is reflected in the multistage process of producing 3-D graphics: modeling, surface definition, scene composition, and rendering. 3-D graphics applications have steeper learning curves and require more powerful computers than their 2-D counterparts, but 3-D image making is advancing rapidly and is an increasingly important part of modern multimedia development.

Key Terms

Adaptive indexing
Additive color
Autotracing
Bit depth
Bitmap
Bitmapping
BMP

Clip art
CMYK
Color banding
Color indexing
Color palette
Color resolution
Contone

Device-dependent	Palette flashing
Device-independent	PDF
Dithering	Perceptual indexing
Downsampling	PICT
dpi	Pixel
Draw program	PNG
EPS	Polygon modeling
Extrusion	ppi
Formula modeling	Primitives
GIF	Quantization
Grayscale	Rasterize
Halftone	Rendering
Handles	Resampling
Interlacing	Scene composition
JPEG	Screen grab
Lathing	Shader
Layers	Spatial resolution
Line art	Spline modeling
Lossless	Subtractive color
Lossy	Surface definition
Megapixel	SVG
Metaball modeling	TIFF
Modeler	Upsampling
Modeling	Vector
NURB	Vector graphics
Paint program	Web-safe color palette

Review Questions

1. What is the difference between contone and line art images in traditional print graphics?
2. Why is CMYK called subtractive color?
3. Why is RGB called additive color?
4. Explain how bitmapped computer graphics are formed.
5. What are three forms of bitmapped graphics?
6. What is a color palette?
7. Why are color palettes significant considerations for developers?
8. What is spatial resolution?
9. How does spatial resolution affect the quality of a bitmapped image?
10. How does bit depth determine color resolution?
11. How can quantization produce color banding?
12. What is color indexing? What is the benefit of using indexed colors?
13. What is dithering and how can it improve a color image?
14. Why might a developer use a series of screen grabs in an application?
15. What is the difference between lossy and lossless graphic file formats? Give an example of each.

16. How are vector graphics formed?
17. What are three major advantages of vector graphics?
18. What is autotracing? How is it related to vector images?
19. What is rasterizing? How is it related to vector images?
20. What are the benefits of a .pdf file format?
21. What is 3-D modeling?
22. How does an extrusion modeler create a shape? Give a specific example.
23. What is lathing?
24. Why is surface definition a key step in 3-D graphics?
25. What is rendering and why is it the final step in 3-D graphics?

Evaluate the following as True or False.

1. Contone images reproduced with dots of black ink are called halftones.
2. Color is created on a printed page using an additive process.
3. Vector drawing is typically used for illustrations and logos.
4. Monitor resolution of a bitmapped image is given in dots per inch.
5. Line art is produced using two or more colors.
6. A 4-bit color image can display 32 possible hues.
7. If each channel of RGB color is set to 255, the result is white.
8. Spatial resolution of bitmapped images determines the color quality of an image.
9. PPI means points per inch.
10. Higher spatial resolution results in sharper, more accurate images.
11. Quantization is likely to occur in images with high bit depth.
12. Dithering is used to produce web-safe colors.
13. Paint programs provide editing control at the pixel level.
14. GIF files have greater color resolution than PNG files.
15. Draw programs produce device-independent images.
16. Polygon modeling produces large 3-D file sizes.
17. A circle can be extruded to form a sphere.
18. Custom surfaces on a 3-D object are made from NURBs.
19. Spline modeling is similar to vector graphics.
20. Real-time rendering is used in highly interactive 3-D applications.

Discussion Questions


1. Identify three challenges of using images in multimedia documents and explain how each challenge is overcome.
2. Locate a copy of the *Wall Street Journal* in your library and magnify an image of one of their writers. Based on your understanding of contone image reproduction, explain how that image is constructed.
3. Identify and explain one advantage and one disadvantage for both line art and color bitmapped graphics.
4. What does it mean to say that a bitmapped image is device-dependent? What is the connection between device-dependence and spatial resolution? Give an

example from your experience with digital cameras, inkjet printers, or computer display devices.

5. Explain how color indexing and dithering can improve a bitmapped graphic with low color resolution.
6. What are the main sources of bitmapped images? Give a benefit or feature of each source.
7. Explain to a digital photographer why (s)he should not edit and resave multiple versions of a JPEG image file.
8. Do you think the PNG file format will replace JPEG and GIF formats for web graphics? Explain your position.
9. Why are 3-D graphics applications called a “virtual partner in the creative process”? Locate a 3-D graphic image and identify several features that were possible because of a 3-D application.
10. Identify and explain the two basic approaches to 3-D modeling.
11. In what ways is polygon modeling similar to 2-D bitmapped graphics?
12. In what ways is spline modeling similar to 2-D vector graphics?
13. Using 3-D graphic terminology, describe how you would use 3-D graphics applications to create an image of a beach ball with your college logo on it resting on a sandy beach.
14. Why does 3-D rendering require powerful computers?
15. Identify three guidelines for using graphics that you think a graphic artist developing a college website should follow. Specifically explain the importance of each guideline in relation to creating a college website.

Chapter 7

Sound



Topics you will explore include:

- Nature of Sound
- Traditional Sound Reproduction
- Digital Sound
 - Sampled
 - Sample Rate
 - Sample Resolution
 - Sample Sound Challenge
 - Synthesized
 - MIDI Sound System
 - MIDI Messages
- Comparing Sampled and Synthesized Sound
- Advantages of Digital Sound
- Guidelines for Using Sound

Digital technology dramatically changed the creation, distribution, and uses of sound. From the earliest CDs of the 1980s to digital phone services, Internet and satellite radio, and the MP3 players and podcasts of the early 21st century, digital sound transformed whole industries.

Podcasting is a means of distributing audio content over the Internet. Podcast software (such as iPodder or iTunes) allows users to subscribe to regularly updated feeds of digital audio files (often MP3s) or to download selected episodes.

Virtually any kind of audio—a child's first words, broadcast news reports, interviews, town meetings—can be quickly distributed worldwide through podcasting.

Early visionaries like Alan Kay understood the potential of the computer to capture, create, and distribute sound. Just as his Dynabook would allow people to express themselves in words and images, so, too, would it empower them to speak and to compose. But sound is a dynamic medium—it changes over time. Keeping up with the demands of real-time capture and delivery of sound required improvements in processors and memory. Making the computer speak was a surprise (and an effective marketing ploy) when Steve Jobs let the Macintosh introduce itself to the world in 1984.

Rapid progress in computer hardware was the key to expanding the sound capabilities of personal computers. Soon, “speaking” computers were commonplace, and it wasn't long before they were expected to listen as well. Built-in microphones allowed users to speak to their machines and ports were provided to connect musical keyboards. The microcomputer, with its processor devoted to a single user, now enabled one person with a single keyboard to create the sounds of an entire orchestra. For many observers, it was sound that transformed the computer from a workstation to a full-fledged communication device that could entertain, move, and persuade as well as calculate, sort, and inform.

The sophisticated sound production capabilities of modern computers allow multimedia developers to pursue a wide range of expressive possibilities. Sound can set a mood or a pace, as it routinely does in films. It can suggest a time (the crowing of a rooster) or a space (the canyon echo). It can reinforce simple interactions, as in the audible click of a button, or it can provide a fully developed alternative experience, as in programs for the visually impaired. Sound can engage and inspire all by itself, as the enthusiasm for digital sound libraries and MP3 players well attests. And it can be powerfully combined with other media to produce the compelling immersive experiences of video games and other interactive multimedia products.

In this chapter we consider the fundamental concepts, tools, and techniques of multimedia sound. After completing the reading you should understand:

- Key elements of sound such as frequency and pitch, amplitude and volume, and sine waves
- Defining features, uses, and limitations of sampled sound: sampling, sample resolution, quantization, clipping, sample rate, aliasing, and file formats
- Defining features, uses, and limitations of synthesized sound: MIDI, messages, synthesizer, sequencer, frequency modulation, and wavetable synthesis
- Sound on the Internet such as downloads and streaming audio
- Basic guidelines for the use of audio in multimedia applications

7.1 The Nature of Sound

Sound is a form of mechanical energy transmitted as vibrations in a medium. The medium is usually air, though sound can also be transmitted through solids and liquids. A clap of the hands produces sound by suddenly compressing and displacing air molecules. The disturbance is transmitted to adjacent molecules and propagated through space in the form of a wave. We hear the hand clap when these vibrations cause motions in the various parts of our ears.

Sound waves are often compared to the ripples produced when a stone is thrown into a pond. The stone displaces the water to produce high points, or wave peaks, and low points, or troughs. We see these alternating peaks and troughs as patterns of waves moving outward from the stone's point of impact. The clap of the hand also produces peaks and troughs as high air pressure is followed by a return to lower pressure. These changes in air pressure produce patterns of waves spreading in all directions from the sound's source.

The simplest sound wave patterns belong to so-called **pure tones**. A pure tone (such as the note produced by a tuning fork) can be represented as a simple wave that regularly repeats a smooth transition from high to low pressure. Such "periodic" waves are called *sinusoidal* or **sine waves**. A sine wave can be envisioned through a simple drawing in which the horizontal, or *x*-axis, represents the passage of time and the vertical, or *y*-axis, represents changes in air pressure (Figure 7.1).




Figure 7.1 A sine wave.

A sine wave captures three essential features of sound: *amplitude*, *frequency*, and *duration*. **Amplitude** is a measure of sound pressure or the amount of energy associated with the sound. This is represented by the vertical, or *y*-axis, of the sine wave. Amplitude is perceived as the sound's **volume**, which is usually measured in **decibels** (dB). In general, sounds with higher amplitudes are experienced as *louder*. The range of human hearing is approximately 3 to 140 dB. Each 10-dB increase roughly doubles the perceived volume of a sound.

Frequency is the number of times a waveform repeats in a given interval of time. This is represented on the horizontal axis as the distance between two wave peaks or troughs. Frequency is measured in *hertz* (Hz). One **hertz** is one repetition of a waveform in one second of time. Frequency is perceived as **pitch**. High frequencies produce sounds of higher pitch, and low frequencies produce low pitch. Pitch is the psychological perception of sound frequency. Humans can perceive a frequency range of 20 Hz to 20,000 Hz (or 20 *kilohertz* (kHz), *thousands* of hertz), though most adults cannot hear frequencies above 16 kHz.

The *duration* of the sound is the length of time it lasts. The total length of the horizontal axis represents duration (Figure 7.2).

Most sound waves are much more complex than the simple waveforms of pure tones. Different musical instruments playing the same note, for instance, produce different wave patterns (Figure 7.3). This is how we can tell the difference between a piano and a




Figure 7.2 Amplitude, frequency, and duration.

trumpet. The sound of an entire symphony orchestra is an extremely complex blending of varied waveforms.




Figure 7.3 Comparison of the same note played on different instruments.

Sine waves, nonetheless, are central to acoustical theory and to the reproduction of sound. This is because *every* sound—a whisper, a lion’s roar, a symphony, a crack of thunder—can be re-created as a combination of sine waves at particular frequencies.

7.2 Traditional Sound Reproduction

Sound waves are continuously varying, or analog, phenomena. Traditional approaches to capturing and reproducing sound were also analog. Sound waves vibrated the diaphragms of early microphones, which in turn caused a stylus to inscribe a continuous pattern on tinfoil or on a wax cylinder. To reproduce the sound, the process was reversed. The drum was rotated while in contact with a stylus. The movements of the stylus were electrically amplified to vibrate the drum of a speaker, which created the changes in air pressure that produce sound.

Over time, analog sound systems became very sophisticated. Technical improvements in sound capture and reproduction made possible very high-quality or *high-fidelity* sound. Hi-Fi components such as amplifiers and speaker systems remain important in modern multimedia. These analog devices are still used in the final output of digital sound.

7.3 Digital Sound

Digital techniques represent sound as discrete (or discontinuous) elements of information. There are two major types of digital sound: *sampled* and *synthesized*.

Sampled sound is a digital recording of previously existing analog sound waves. A file for sampled sound contains many thousands of numerical values, each of which is a record of the amplitude of the sound wave at a particular instant, a *sampling* of the sound.

Synthesized sound is new sound generated (or synthesized, “put together”) by the computer. A file for synthesized sound contains *instructions* that the computer uses to produce its own sound.

Multimedia developers usually use sampling to capture and edit naturally occurring sounds such as human speech, musical and dramatic performances, bird calls, rocket launches, and so on. Synthesized sound is generally used to create original musical compositions or to produce novel sound effects.

Sampled Sound

In digital sampling, sound is captured by recording many separate measurements of the amplitude of a wave using an **ADC**, or *analog-to-digital converter*. An analog device, such as a microphone or the amplifier in a speaker system, generates a continuously varying voltage pattern to match the original sound wave. The ADC samples these voltages thousands of times each second. The samples are recorded as digital numbers. These digital values are then used to re-create the original sound by converting the digital information back to an analog form using a **DAC**, or *digital-to-analog converter*. The DAC uses the amplitude values to generate matching voltages that power speakers to reproduce the sound.

Digital sampling replaces the continuous waveform of the original sound with a new wave created from a fixed number of discrete samples (Figure 7.4). Some information is always lost in sampling, because a continuous wave is infinitely divisible and sampling always yields a finite number of values. The quality of sampled sound is dependent on two factors directly connected to this sampling process: *sample resolution* and *sample rate*.




Figure 7.4 Sound sampling.

Sample Resolution Each measurement of amplitude made by an ADC is recorded using a fixed number of bits. The number of bits used to encode amplitude is known as **sample resolution**. Sample resolutions for digital audio range from 8 to 32 bits, with the most common being the 16-bit CD-Audio standards and 24-bit DVD-Audio standards.

Eight bits can record 256 different amplitude levels. This is adequate to capture the variations in limited decibel ranges, such as those between a human whisper and a shout, but higher sample resolutions are needed to accurately reproduce sounds with a wider range of amplitudes, such as musical performances. Thus, 8-bit audio is generally used only for simple sounds or in multimedia applications requiring very small file sizes.

The CD-Audio standard, with its 16 bits per sample, supports over 65 thousand different amplitude levels, whereas the 24-bit DVD-Audio standard can represent over 16 million levels. Inadequate sample resolution can distort sound in two different ways: *quantization* and *clipping*.

Quantization Just as low color resolution can produce distortions in a bitmapped representation of a photograph, so can low sample resolution distort a sound recording. Each amplitude sample must be assigned one of the numbers available in the code being

used. If the number of distinct values is too few, perceptually different amplitudes will be assigned the same number. Rounding a sample to the closest available value is known as **quantization**. In the case of sound, excessive quantization may produce a background hissing or a grainy sound. The solution is to record with a higher sample resolution (for instance, by using 16 rather than 8 bits).

Clipping A different form of distortion related to wave amplitude is **clipping**. Sound-sampling equipment is designed for a selected decibel range. If the source sound exceeds this range (as, for instance, when someone yells into a microphone held close to their lips), higher amplitudes cannot be encoded, because no values are available to represent them. The waveform of a clipped sound shows square tops and bottoms marking the point at which the highest amplitudes could not be captured (Figure 7.5). Clipping can produce a harsh, distorted sound.

The solution to clipping is to lower the amplitude of the source sound to record within the limits of the ADC circuitry. Recording equipment usually includes some form of meter such as a swinging needle, colored bars, or lights to show input levels and alert users when the amplitude range has been exceeded. The familiar, “Testing—one, two, three,” is often used to establish the proper distance and speech level when recording with a microphone.

Clipping can also occur during the mixing of different audio tracks. **Mixing** is the process of combining two or more sound selections, or *tracks*, into a single track. For example, a background music track might be mixed with a voice track of a poetry reading. This combination of two or more tracks may produce an amplitude that exceeds the available range. Adjustments to the volume of each track can eliminate the problem. Another solution is to use higher sample resolutions (for instance, 24-bit) to provide a wider range of amplitude values.




Figure 7.5 Clipping.

Sample Rate **Sample rate** is the number of samples taken in a fixed interval of time. As noted previously, a rate of one sample per second is designated as a Hertz. Because sound samples are always taken thousands of times each second, sample rates are usually stated in kilohertz.

Sample rate affects sound quality by determining the range of frequencies that can be represented in a digital recording. At least two measurements are required to capture each cycle of a sound wave—one for each high value, or peak, and one for each low value, or trough. The highest frequency that can be captured is thus one-half of the sample rate. CD-quality sound captures 44,100 samples per second (44.1 kHz sample




Figure 7.6 Aliasing—A higher frequency is falsely reproduced as a lower frequency. Original wave is shown in black. Reproduced wave is shown in blue.

rate) and can represent frequencies as high as 22,050 Hz or 22.05 kHz. DVD-Audio uses a sampling frequency of 96 kHz to capture frequencies as high as 48 kHz.

Sounds that do not contain high frequencies can be more efficiently represented using lower sample rates because this will produce a smaller overall file size. One potential problem with lower sample rates, however, is aliasing.

Aliasing **Aliasing**, as it applies to sampled sound, is the false representation of high frequencies as low frequencies. Aliasing occurs when the frequency being sampled is greater than one-half the sample rate being used. For instance, if a 150-Hz sound is sampled at a rate of 100 Hz, the resulting sound will be 50 Hz (Figure 7.6).

Aliasing can be eliminated by applying electronic filters to the source sound to eliminate frequencies above one-half of the sample rate. Such filtering is often applied automatically by recording equipment.

Another approach to the problem of aliasing is to *oversample*. **Oversampling** uses a higher sample rate to accurately capture the frequencies above the desired range. For instance, the human voice has a limited range of frequencies. These can generally be captured with a sample rate of 11.025 kHz. But any background sounds with frequencies above approximately 5.5 kHz would be falsely included as lower frequencies. Using a higher rate such as 44.1 kHz will accurately capture these frequencies. The higher frequencies can then be eliminated with less-expensive and more-efficient digital filters. Once these frequencies are removed, the file is *downsampled*. **Downsampling** is the process of reducing the sample rate in an audio file. This reduces the size of the file to that required to capture the frequency range of the desired sound. In this case, the sample rate would be reduced from 44.1 kHz to 11.025 kHz.

Balancing File Size and Sound Quality The most significant challenge in the use of sampled sound is large file size. One minute of a single channel of CD-quality sound (16-bit sample resolution and 44.1-kHz sample rate) produces a file of 42,336,000 bits ($16 \times 44,100 \times 60$) or approximately 5 megabytes (MB). Stereo requires a second channel and doubles the size for a total of 10 MB per minute of sound. DVD-Audio creates even larger files by using higher sample rates (96 kHz), a larger sample size (24 bits), and more channels to produce “surround sound.”

Fortunately, it is not always necessary to use CD- or DVD-quality sound. Some sounds, such as normal speech, contain relatively low frequencies and a limited range of amplitudes. In these cases, higher sample rates and sample resolutions do not improve sound quality—they just create needlessly large files. Using a rate of 11.025 kHz for voice recording results in a file only one-quarter the size of a CD-quality sound file. In addition, 8-bit sample resolution and monaural sound are usually adequate for speech. This further reduces file size by a factor of four—1 minute of monaural, 8-bit, 11.025-kHz sampled sound requires only 650 KB, one-sixteenth the size of a stereo CD recording.

These dramatic differences in file sizes make it important for multimedia developers to match sample resolutions and rates to the type of sound being recorded. This often requires testing a given sound at different resolutions and rates to determine a quality level appropriate to the application. One reason for including audio specialists on a multimedia development team is that they can draw on their experience to greatly expedite this process.

Determining the Size of Sampled Sound Files Sound file sizes for monaural sound can be readily calculated by simply multiplying the time of the recording, the sample rate, and the size of each sample. The formula is:

$$\text{Monaural Sound File Size} = \text{Sample Rate (in kilohertz)} \times \text{Sample Size (in bytes)} \times \text{Sample Time (in seconds)}$$

For example, a sound sampled at 44.1 kHz, using a 16-bit (2-byte) sample size for 10 seconds produces a file size of 882,000 bytes (approximately 860 KB). To calculate stereo requirements, double the size of the monaural sound file. Comparisons of file sizes for 1-minute of sound at different qualities are given in Table 7.1.

Sound Compression Lowering the sample rate and reducing sample resolution are two ways to reduce the size of a sampled sound file. These methods work well for sounds

Table 7.1 Size and Quality Comparisons for Sampled Sound

Resolution	Rate	Stereo/Mono	Size (1 Minute)	Quality
16	44.1 kHz	Stereo	10 MB	CD
16	22.05 kHz	Stereo	5 MB	FM radio
8	11.025 kHz	Mono	650 KB	AM radio
8	5.5 kHz	Mono	325 KB	Bad telephone

at relatively low frequencies and narrow amplitude ranges. They are not effective for sounds that contain wider ranges of both frequency and amplitude, such as musical performances. In these cases another strategy can be used: *file compression*.

File compression can be either *lossless* or *lossy*. Lossless compression uses more efficient coding to reduce the size of a file while preserving all the information of the original. Lossy compression discards some of the original information.

Lossless compression is essential for files containing computer programs and alpha-numeric data, because any change in this information could easily disable the program or distort the data. Images and sounds, however, often remain recognizable and usable when relatively large amounts of information are sacrificed. Because lossy strategies produce much smaller files, they are the preferred technique for sound compression.

Lossy sound compression **codecs** (coder/decoders) use various techniques to reduce file sizes. Some of these take advantage of **psychoacoustics**, the interplay between the psychological conditions of human perception and the properties of sound. For instance, while humans with optimal hearing can perceive frequencies as high as about 20 kHz, most people cannot distinguish frequencies above approximately 16 kHz. This means that higher-frequency information can be eliminated and most listeners will not miss it. Higher amplitude sounds in one stereo channel will also typically “drown out” softer sounds in the other channel. Again, this is information that usually will not be missed.

Lossy compression also uses other techniques such as variable bit rate encoding (**VBR**). In VBR, sounds are encoded using a different number of bits per second depending on the complexity of the sound. For simple passages of sound with limited frequencies, a smaller number of bits per second is used than for more complex passages, such as those with many different instruments and higher frequencies.

Lossy codecs such as the widely supported MP3 can reduce file sizes by as much as 80% while remaining virtually indistinguishable from the original CD-quality sound. Sound compression is a constantly evolving area of research and development. There are several competing formats and many different opinions about the relative merits of each.

Sampled Sound File Formats

A variety of file formats have been developed for sampled sound. Some are specific to particular computer platforms while others are intended for specialized audio capture and editing programs or for specific uses, such as web broadcasting.

AIFF, or audio interchange file format, is an Apple format widely used on Macintosh computers. AIFF can support a wide range of sample resolutions, sample rates, and audio channels. Because AIFF files are not compressed, they tend to be relatively large. AIFF files use the extensions .aiff or .aif and can be played on Windows computers as well as Macs.

WAV was developed by Microsoft and IBM and is the standard sampled sound format for the PC. Nearly all sound-capable Windows applications support WAV. WAV files can be monaural or stereo, and either 8- or 16-bit sample size. This format also supports a variety of sample rates. Like AIFF, WAV files are uncompressed, high-quality sound files that can be played on both Macintosh and Windows platforms. WAV files use the extension .wav.

AU was developed by Sun Microsystems. This format is widely used on the Internet for transmission of relatively low-quality sound files. AU files use the extension `.au`.

RealAudio, developed by RealMedia, the RealAudio format supports streaming audio at low bandwidths. *Streaming audio*, discussed at the end of this chapter, is sound that can be played as audio files are being received by the computer. This allows users to begin playing sounds without the waiting required to download a complete file. It also supports real-time broadcasts of events such as concerts and the live reception of radio over the Internet. RealAudio files use the extension `.rm`.

MP3 (MPEG1, audio layer 3) is a popular audio format that supports significant compression while preserving excellent quality. It is widely supported across different computer platforms and is frequently used on the Internet. MP3s are often “ripped” from CDs. Ripping transfers the CD file to a user’s computer and converts it to MP3 format. This creates small, high-quality versions of the original sounds for use on the Web or in portable MP3 players. MP3 files use the extensions `.mp3` or `.mpga`.

WMA (Windows Media Audio) is a format developed by Microsoft as an alternative to MP3. WMA can deliver lossy compressed audio comparable to MP3 at lower bit rates. An advanced version of the codec, WMA Pro, significantly improves performance over the MP3 standard. WMA uses a `.wma` file extension.

AAC (advanced audio coding) is the successor to MP3 specified in the MPEG4 standard. AAC produces better sound quality than MP3 at comparable bit rates. It can also significantly reduce file sizes for comparable-quality audio. Many commercial users (including Apple iPod, Apple iPad, Apple iPhone, Blackberry, YouTube, and Sony PlayStation) have adopted the AAC standard for their digital audio. AAC files use a variety of extensions including `.mp4` and `.aac`.

Synthesized Sound

In sound synthesis, the computer sends commands to a specialized electronic device called a **synthesizer**, which then generates the corresponding sounds. The most common format for these commands is **MIDI**, or Musical Instrument Digital Interface. As its name suggests, MIDI was developed to provide a standard method of connecting musical instruments, synthesizers, and other digital devices.

MIDI is an audio format for representing the elements of a musical composition in a digital code. Codes are provided for:

- Specific instruments
- Notes
- The force and duration of musical actions (pressing a key, striking a drum)
- Routing commands to different synthesizer channels to produce music with multiple simultaneous parts (such as a guitar and a bass drum)
- A variety of specialized control functions (enabling multichannel play, etc.)

Prior to the development of MIDI in 1983, there was no guarantee that synthesized music played on two different systems would sound the same. One system might designate a guitar sound with a binary code that another system used for a flute. Developers




Figure 7.8 MIDI system with sequencer.

supported input devices. A keyboard or other instrument can be connected to the computer through standard MIDI jacks on the soundcard. The computer can then be used to directly play any MIDI instrument.

The computer can also be used to create a composition without playing an instrument. Using sequencer software, an original composition is created by simply placing notes on a musical scale (Figure 7.9). Other compositions, including those produced by performers, are imported. Any part of the composition can then be edited in a wide variety of ways. Pitch, tempo, the duration and volume of notes, and the arrangement and timing of instruments are all readily altered with the sequencer.

MIDI dramatically changed music composition by placing control over a virtually unlimited range of instruments and musical scores in the hands of a single individual.

MIDI dramatically changed music composition by placing control over a virtually unlimited range of instruments and musical scores in the hands of a single individual.



Figure 7.9 A sequencer. (GarageBand)

7.4 Sampled and Synthesized Sound Compared

Sampling and synthesis are very different techniques for incorporating sound in multimedia applications. Their relative strengths and weaknesses can be summarized as follows.

Advantages of Sampled Sound

Sampled sound can be played on virtually any modern computer at a consistently high quality. It is also easily created and edited.

- **High Quality:** The evolution of digital technology made it possible to capture many thousands of samples per second and to record these at bit depths that minimize the effects of quantization. In addition, the creation in the 1980s of CD-Audio, a nearly universal standard for high-fidelity music, promoted widespread acceptance and support of sampled sound. Other standards, such as DVD-Audio, have expanded the

note. One significant advantage of this approach over sampled sound is that the duration of a MIDI sound can be readily altered without producing distortions. Another editing advantage of MIDI is that it allows a single skilled musician to create and play an original composition that otherwise would require the efforts of many skilled professional performers and technicians. This has provided multimedia developers with a source of significantly less-expensive original music.

- *Small Files:* MIDI sounds on computers also have another striking advantage: small file size. A MIDI file is a listing of alphanumeric messages. These take up far less space than the many thousands of samples per second recorded for sampled sound. In fact, MIDI files may be up to 1000 times smaller than comparable sampled sound files.

Challenges of Synthesized Sound

The challenges for the use of MIDI in multimedia productions concern expertise, playback consistency, and reproduction of natural sounds.

- *Expertise:* Unlike the process of capturing an existing sound, the creation and editing of MIDI sound does require knowledge of musical theory. Sampled sound can be captured by virtually anyone, and nonspecialists can easily master many editing changes. MIDI sound, on the other hand, demands at least basic understanding of notes, scales, and other elements of music.
- *Playback Consistency:* The playback quality of synthesized sound is less consistent than it is for sampled sound. Every computer processes sampled sound in essentially the same way. Given comparable amplifiers and speakers, sampled audio will sound the same no matter where it is played. MIDI sound must be synthesized, that is, artificially created by the computer's soundcard. The synthesizers built into soundcards differ significantly in quality and may produce very different results. There are several reasons for the differences in sound synthesizer quality.
 - Some synthesizers use a process known as **frequency modulation** (FM). FM synthesis produces the variety of sounds by using one signal to modulate the frequency of another signal. This can be very effective if the desired output is a novel electronic sound. If the goal is the natural sound of traditional instruments, however, a second approach is usually more effective.
 - The second major approach to synthesizing sound is called **wavetable synthesis**. This uses very short samples of naturally produced sounds to generate new, synthesized sound. Wavetable synthesizers differ in the number and quality of their sound samples as well as in the means they use to generate new sounds from their samples. The result is significant variation in output quality.
- *Natural Sound:* The third major challenge in the use of MIDI is that synthesized sound is generally not effective for the representation of nonmusical natural sounds such as the human voice. If a multimedia project requires speech and other natural sounds, sampled sound is usually the better choice.

7.5 Combining Sampled and Synthesized Sound

The challenges in digital audio can sometimes be met by combining synthesized and sampled approaches.

QuickTime, Windows Media Player, and RealAudio simplified user access to all forms of audio. Improvements in bandwidth provided through DSL, cable, and satellite services also improved access to large digital sound files, as did advances in audio compression. Particularly significant was the MP3 format, which dramatically reduced the size of CD-quality audio and led to a revolution in the distribution of music.

There are two major strategies for delivering sound on the Internet: *downloading* and *streaming audio*. **Downloaded audio** transfers a complete audio file from one computer (the server) to another (the client) according to a set of file transfer protocols. Users await the complete delivery of the file and then use player software to open the file and listen to the audio. The file remains on the user's computer and can be edited and replayed at will. These are significant advantages, but downloading also has serious shortcomings. Downloads take time, they consume hard-disk space, they are not easily updated, and they cannot be used to broadcast live events. One approach to shortening the delay between starting a download and hearing the audio is *progressive downloading*. As in normal downloading, progressive downloads save a file to the client computer's hard disk, but they also buffer content in main memory and begin to play the sound as it is being downloaded. Progressive downloads are relatively easy to deliver using common protocols such as HTTP and TCP/IP and they can deliver high-quality audio files over a wide range of connection speeds. Their main disadvantages are that playback during the download process may be interrupted on computers using slower network connections and users will not be able to access later portions of a recording until the download is complete.

Streaming audio provides a solution to these limitations. **Streaming audio** is "real-time" sound that is heard as it is being delivered and is not saved to the client computer. Streaming audio uses special protocols such as RTSP (Real Time Streaming Protocol), special servers, and special media formats and players. RealAudio, QuickTime, and WMA are popular formats with streaming capability. The protocols used to deliver streaming media are optimized for efficient, real-time delivery over networks rather than delivery of error-free downloads. The special requirements for preparing and delivering streaming audio make it more difficult to implement than downloads. In particular, developers must choose between competing streaming formats as they prepare files and arrange for their distribution. On the other hand, streaming is the only way to provide audio of live events over networks. It provides more reliable playback than progressive downloads, does not consume hard-disk space on the client machine, and can be readily updated.

7.8 Guidelines for the Use of Sound

Multimedia development typically demands careful planning and frequent revision. The challenges of digital audio can be more readily met by following a few basic guidelines.

1. **Identify the purpose of the sound.** Sound can be memory and processor intensive—use it for good reasons:
 - To attract attention (chimes, bells).
 - To inform (oral histories, speeches).
 - To illustrate (word pronunciations, musical selections, animal sounds).
 - To establish a mood or setting.

- To provide feedback (audible mouse clicks, spoken alert messages).
 - As an alternative to text for the visually impaired.
2. **Use high-quality sound.** Poor audio gives an immediate negative impression.
 3. **Conserve file space.** Calculate sound file sizes. Choose the most efficient sound format:
 - Lower sample rates and sizes for speech.
 - Consider MIDI sources.
 - Consider compression options such as MP3.
 4. **Consider the playback environment.**
 - Public vs. private use.
 - Quality of synthesizers for MIDI sound.
 - Compatibility of sound formats with playback hardware and software.
 - Give users control:
 - Over volume.
 - To stop or start play.
 5. **Avoid excessive use of sound.** Sound can be more tiring for users than images or text.
 6. **Organize sound files.** Preserve original sources.

7.9 Summary

There are two basic approaches to creating digital sound. The first is sampled sound, a recording made up of many thousands of samples of existing sounds. Sampled sound has several strengths including effective representation of natural sounds, ease of creation and editing, high quality, and reliable playback. The disadvantages of sampled sound include large file size and limited editing control.

The second form of digital audio is synthesized sound, sound created by the computer itself. MIDI is the most widely used form of synthesized sound. A MIDI file contains commands that the computer follows to artificially generate sound. These files are much smaller than sampled sound files. They also permit knowledgeable developers to edit music at the level of the individual note for any of the various instruments used in a composition. The length of synthesized sound tracks can be altered without affecting pitch. The disadvantages of synthesized sound include limitations in the production of natural sounds such as human voices, the need for knowledge of musical theory, and less consistent playback quality.

Sampled and synthesized sounds have a number of advantages over traditional analog formats. These include high-quality copies, durability, random access, and ease of editing and distribution.


Sound has become an essential element in many multimedia applications and is widely distributed over the Internet either as downloads or streaming audio. The challenges of digital sound make it particularly important for developers to carefully consider the purposes sound serves in their applications and the techniques they use to optimize the quality and efficiency of multimedia sound.

Discussion Questions

1. Identify three expressive possibilities for using sound in multimedia applications. Locate one example of a multimedia animation on the Web and describe the uses and importance of sound in this application.
2. Determine the sound file size for a stereo music recording of 2.5 minutes, 8 bit, 11.05 kHz.
3. Explain why MP3 file compression became such a popular format for digital music.
4. If you are the audio specialist for a development team, should you save the original sound files as .aiff format or MP3 format? Explain your selection.
5. If you are the audio specialist for a web development team, should you create the background music for an animated cartoon in MIDI or sampled format? Explain your choice.
6. Describe a situation where an audio specialist may combine sampled and MIDI sound for an animated cartoon.
7. Describe how a computer application can create MIDI sounds.
8. What are the benefits of converting an audio tape library to CD format?
9. Identify and explain three relevant guidelines to incorporate the sound of cathedral bells in a public kiosk on the history of Chartres Cathedral.
10. Consider the distinction between bitmapped and vector graphics and explain how that distinction is similar to the difference between sampled and synthesized sound.

■ ■ ■ Chapter 8

Video



Topics you will explore include:

- Digital Video
 - Video Quality
 - Codecs
 - File Formats
 - Shooting
 - Editing
 - Rendering
- Guidelines for Video

For most of the 20th century, the creation of “motion pictures,” whether film or video, was a restricted specialty demanding teams of skilled professionals and expensive equipment. Home movie cameras and camcorders gave amateurs little more than a tempting entrée to the world of video. To be sure, they could capture moving images; but raw video is exactly that—it is only with the revision and refinement of editing that a video draft becomes a memorable message. And analog editing was expensive and complex. Few nonprofessionals had the skills or the resources to create effective analog video.

As in all media, the computer transformed video and film, adding expressive possibilities that were impossible to produce using analog techniques. The result has been new forms of expression ranging from special effects to convincing digital simulations of human actors. Cutting-edge digital film and video still require expertise and computing resources beyond the budgets of most multimedia producers. But there has also been a revolution in desktop digital video. Improvements in microcomputers, digital cameras, and video-editing software have made it possible for individuals and small production teams to effectively add video to a wide range of multimedia applications.

After completing this chapter, you should understand:

- Key elements of digital video: resolution, frame rate, compression strategies, codecs, file formats
- Main development considerations for each of the three stages of creating digital video: shooting, editing, and rendering
- Basic guidelines for the use of video in multimedia applications

8.1 Moving Pictures

To understand both the power and the continuing challenges of digital video, we must turn first to the elements of video and to its origins in the analog technologies of the last century.

Film and video are composed of a series of rapidly displayed still images. We perceive these stills as continuous motion for two reasons. First, each image captures an instant of motion, recording the changes in the positions of moving objects. One image shows the feet of a running horse in one position and the next captures their new position an instant later. The second factor is persistence of vision: images formed on the retina remain for a short time after an object is gone. If the still images are changed rapidly enough, persistence of vision fills the time between them, resulting in the perception of a continuous flow of motion.

Traditional film and video are analog media. Film records individual images as continuous areas of color on a transparent medium that is then projected to a screen. Analog video records images as continuously varying electrical voltages. These voltages are then used to produce images on cathode ray tubes (CRTs) or projection screens. Sound tracks for both traditional film and video also use analog techniques.

Digital formats have effectively replaced analog video, but some multimedia applications either make use of analog source material or use analog TVs for display of their products. For these reasons, a basic understanding of the older video standards may be relevant to some multimedia developers. See Appendix D for a discussion of this topic.

8.2 Digital Video

Nowhere is the triumph of digital media more evident than in film and video. But digital video poses very significant challenges for multimedia developers. The most important challenge is large file size. Like its analog cousin, digital video is composed of a series of rapidly displayed individual images. Each image is made up of very small picture elements, or *pixels*. Each pixel is assigned a color. Reproducing a photo-realistic range of colors requires a 24-bit code for each pixel. The lowest-resolution computer monitors display a grid 640 pixels wide and 480 pixels high. This translates to 307,200 pixels and nearly a megabyte (MB) of digital data for each screen. Full motion video requires a display of 30 of these screens each second. A computer must store and process almost 30 MB of data for every *second* of uncompressed digital video. This was well beyond the processing and storage capabilities of earlier microcomputers. Dramatic improvements in hardware and compression techniques have overcome earlier limitations for desktop display of full-screen video. DVD players are common additions to personal computers and small, portable devices, such as tablet computers and smartphones, also effectively display digital video. Large video files are still a major challenge, however, particularly when an application is intended for distribution over the Web. Multimedia developers must often make compromises as they try to incorporate high-quality digital video in their applications.

Sound also adds to the size of video files. CD-quality stereo sound requires approximately 10 MB per minute.

Digital Video Quality

The quality of digital video depends on three main factors: *screen resolution*, *frame rate*, and *compression method*. **Screen resolution** is the number of horizontal and vertical pixels used to present the video image. Screen resolution determines how large the video will appear to the user, for instance, as a window 720 pixels wide and 480 pixels high. **Frame rate** is the number of individual video frames displayed per second. The compression method, or **codec**, is the particular algorithm or set of algorithms used to compress and then decompress the digital video. Large display sizes and higher frame rates require more processing and greater bandwidth. This in turn often demands greater compression.

Screen Resolution The smaller the screen resolution of a digital video, the less processing, storage, and transmission it requires. Developers often reduce screen resolution to match the capabilities of the output medium. This is called the **output resolution** of the video. The output resolution of the relatively high-quality DV (digital video) format is 720×480 pixels. This requires the computer to process and transmit information for nearly 350,000 pixels at rates of up to 30 times per second. Slower delivery options such as mobile phones and Internet video streaming cannot transfer data at this rate. Reducing display size to 176×144 for mobile phones yields a pixel count of approximately 25,000. A display size of 240×180 for Internet video reduces pixels to just over 43,000.

Frame Rate A common frame rate for broadcast video is 30 frames per second (fps). Video intended for streaming over the Internet is often delivered at a rate of just 15 fps, effectively cutting the required data rate in half.

D1 is the original high-resolution format used in expensive cameras and editing systems for the production of broadcast-quality TV using 19mm tape. More recent formats for broadcast TV include D5 and D10-MPEG IMX.

DV is a smaller tape format (6mm) widely used in both consumer and professional production and editing. DV uses M-JPEG intraframe compression.

DVD-Video uses MPEG2 compression and provides a screen resolution of 720×480 pixels. This is the format used for the distribution of video on DVD optical discs. An extension of the DVD standard, Blu-ray, supports resolutions up to 1920×1080 .

Interlaced and Progressive Display

Interlacing is a technique to lower bandwidth demands by presenting only half of the horizontal lines of an image at a time. On one pass the odd-numbered lines are displayed; the next pass completes the image by displaying the even-numbered lines. Each half-image is called a *field*. Because the fields are displayed very rapidly, the viewer sees a completed frame. Interlacing has been widely used in television transmission but computers have used progressive display. In progressive display the complete frame is presented at once. The merger of television and video technologies has produced a general trend toward progressive, rather than interlaced, display.

Flash Video is a popular Internet video standard developed by Macromedia and playable through the widely installed Flash Player. Popular social media sites such as YouTube and Yahoo Video have used the .flv format. Flash Video produces highly compressed files suitable for network distribution.

QuickTime is a cross-platform format for the distribution of video, animation, and sound files. QuickTime supports a variety of codecs and screen resolutions. QuickTime files use the .mov file extension.

Windows Media Video is a highly compressed streaming video format from Microsoft. Windows Media Video uses a .wmv extension.

RealVideo is a streaming format for delivery of video over the Web. Developed by RealNetworks, RealVideo uses a .rm extension.

SDTV (standard definition) is a digital format that uses roughly the same resolution as analog television. Available resolutions include 720×480 and 640×480 . SDTV can use either 4:3 or 16:9 aspect ratios. **Aspect ratio** is the relationship between width and height on a display device. (For instance, a 12-inch-wide monitor using a 4:3 aspect ratio will have a height of 9 inches.)

HDTV (high definition) uses a 16:9 aspect ratio and has resolutions of either 1280×720 or 1920×1080 . Lower-resolution HDTV uses progressive scanning and is designated as 720p. Higher-resolution HDTV was originally interlaced but now also includes the progressive scanning that is more appropriate for newer high-definition TVs and computers (1080p).

HDV uses the same small tape format as DV but supports high-definition video resolutions (1080i, 1080p, or 720p). HDV uses MPEG2 compression and uses the extension .m2t.

AVCHD (advanced video coding high definition) uses a variant of MPEG4 compression and can record in 1080i, 1080p, and 720p resolutions. Developed by Sony and Panasonic, AVCHD can record to DVDs, hard drives, or solid-state media. The extensions .mts and .m2ts are used for AVCHD files.

Motion JPEG 2000 is a variant of JPEG 2000, the successor to the ubiquitous JPEG standard. Motion JPEG 2000 uses a new form of compression (wavelet) to produce smaller files at higher quality than the original JPEG standard. Like M-JPEG, this format uses intraframe compression, a significant advantage for digital editing.

Motion JPEG 2000 can deliver mathematically lossless compression as well as compression that is either visually lossless (the human eye cannot detect the losses) or lossy. The format is also optimized for network applications: it can deliver higher-quality images by sending only the additional information needed rather than resending another complete, higher-resolution image. The U.S. Library of Congress has adopted Motion JPEG 2000 as its video archiving format. Motion JPEG 2000 files use either the .mj2 or .mjp2 extensions.

8.3 Sources of Digital Video

Multimedia developers have two ways to acquire digital video: they can convert existing analog video to a digital format (see Appendix D) or they can purchase or create original digital footage.

Creating Original Digital Video

There are three main steps in creating an original digital video: *shooting*, *editing*, and *rendering*.

Step 1: Shooting Effective shooting of digital video requires planning. Developers review the intended uses of the video. They list the shots that will be required. They consider weather, lighting conditions, and the availability of personnel. They also consider the ways in which video will be integrated with other media in the completed project.

Stand-alone videos are sometimes shot with the intent of doing little more than recording a particular event and immediately sharing the result with others. **Shooting to record** attempts to capture the ultimate form of the video as the shooting is done. Lighting decisions may involve little more than keeping the sun to the shooter's back and the identification of essential shots may be a short list committed to memory. But video destined for a multimedia application is seldom shot in this way.

In a multimedia product, video works with text, graphics, and other elements to inform, entertain, or persuade a user. The effective integration of video with other media almost always demands careful editing of the original footage. **Shooting to edit** captures source footage with editing in mind. The videographer carefully plans the shoot, concentrating on acquiring a variety of individual video sequences, or clips, that will later be trimmed, reordered, and blended to effectively communicate a message.

Recording the Shots: The Digital Video Camera The highest-quality digital video requires expensive equipment and trained professionals. Such shoots are carefully budgeted and painstakingly planned. In recent years, the development of higher-quality, affordable cameras and increasingly powerful desktop editing systems has put digital video within the reach of a wide range of multimedia developers. Like the video professional, these developers will generally shoot to edit, trying to record a variety of video images as source material for the editing process.

Shooting to edit requires a camera designed to record high-quality source footage. The most important considerations include the number and quality of CCDs, lens quality,

microphone location and quality, storage media, file format, and light sensitivity (Figure 8.1).

- **CCDs:** A **CCD**, or *charge-coupled device*, generates different levels of electrical voltage based on variations in the intensity of light striking its surface. These voltages are then converted to digital values to store data about each pixel of a digital image. The size of CCDs varies from approximately $\frac{1}{16}$ to $\frac{1}{2}$ inch or more. Larger CCDs are used in more expensive cameras. The number of CCDs is also important. To digitally record color, each sample must include information about the proportions of red, green, and blue (RGB) light. Two approaches are taken to defining these **RGB** levels. In the first, a single CCD is used. The incoming light is passed through filters and the CCD records the level of each filtered color. In the second approach, the light is split into the three color components by a prism and three separate CCDs are used to record red, green, and blue levels. Three-CCD cameras produce clearer, more accurate color. While these cameras remain more expensive than single-CCD models, prices have fallen and good three-CCD options are increasingly available in the “prosumer” category.



Figure 8.1 Digital video camera considerations include quality of CCDs, lenses, and microphone; storage type and capacity; and light sensitivity.

The resolution of the CCD is also important. Higher-resolution CCDs sample smaller elements of the image and produce more accurate digital images. This is reflected in larger horizontal and vertical dimensions. Higher resolutions are particularly important when the camcorder will be used to capture still images. For motion capture, resolutions that are higher than the format used to store the video (for instance, 720×480 for DV or 1920×1080 for HD) are not necessary.

Whether the camera is used for still or for video capture, the resolution of the CCD itself is the most important measure of camera resolution. Camera resolutions are sometimes stated based on digital enlargement rather than CCD resolution. *Digital enlargement* uses software to interpolate new pixels to increase image size. The results never match the accuracy of a higher-resolution CCD. Camera selection should always be based on the resolution of the CCD itself.

- **Lenses:** As in still cameras, the quality of an image is greatly affected by the quality of the lens. Higher-quality cameras use lenses from better vendors and they also support higher zoom ratios through the use of camera optics rather than software. In fact, digital video producers often suggest that software zoom capabilities be ignored in selecting a camera, because they produce inferior results to optical zoom. In addition, software zoom, if desired, can always be applied during the editing process on a computer.
- **Microphones:** Microphone placement, type, and quality are important for accurately capturing sound in a digital video. Microphones are designed differently to capture different types of sound. *Omnidirectional* microphones are optimized to capture a broad range of background sound. *Unidirectional* microphones are intended to record sound from a narrowly defined location. *Zoom* microphones match their pickup patterns to the camera’s zoom lens. At wide zoom, they act as omnidirectional

- **Light Sensitivity:** Cameras vary in their ability to effectively capture images in low-light conditions. This is measured in units of lux. Lower lux ratings indicate that a camera can operate in lower light conditions. DV camcorders vary in their low-light capabilities from approximately 2 to 8 or more lux. A variety of auto exposure presets are also often available for different lighting conditions—for instance, sunlight, moonlight, spotlight, or dusk. Supplemental lighting can also often be attached directly to cameras or provided through stand-alone lights.

A *lux* is the light given off by 1 candle over a 1-square-meter surface.

Shooting Basics Like still photography, effective videography requires an understanding of the capabilities of the camera and an awareness of basic “best practices.” Developers prepare for shoots with extra batteries and storage media (tapes, DVDs, memory cards), external mikes, and headphones. They know the automated focusing and light modes the camera supports and also how to shift to manual control when necessary. They also note the advice of professionals for *framing shots*, *camera motion*, the use of *pans* and *zooms*, and taking care of *time code*.

- **Framing a Shot—The Rule of Thirds:** The **rule of thirds** is perhaps the most widely embraced guideline for framing a video shot. To use the rule, mentally divide the camera image into thirds both vertically and horizontally by inserting two equally spaced lines in both directions. Subjects are then aligned on the intersection of these lines (Figure 8.3). The choice of left or right vertical line or upper or lower horizontal line is based on the direction of the motion. In general, the subject should be moving toward the open area of the frame. A shot of a runner on a track moving to the left of the camera, for example, frames her body on the right vertical line, with her eyes on the



Figure 8.3 The rule of thirds.

intersection of that line and the uppermost horizontal line. Using the rule of thirds for an image, rather than simply centering it, preserves its interest and meaningfully relates it to the action that is taking place. It also helps to ensure adequate side and headroom, thus avoiding an unintentionally cramped or cropped image.

- **Minimizing Camera Motion—Shakes, Pans, and Zooms:** Excessive camera motion is a distraction. This is particularly true of the jumpy images produced by unsteady hands, but many professionals also caution against the intentional motions introduced by pans and zooms.

Digital video cameras often include image stabilization technology to minimize shakes and jitters. While these may be helpful, they are no substitute for the use of tripods or basic techniques, such as using flat surfaces to support the shooter's hands and arms or holding the camera close to the body when no other source of support is available.

Pans (moving side to side) and zooms (enlarging camera images by lens changes) can serve useful functions. The slow pan of the vast, empty sea from the perspective of the life raft helps to tell a story. Zooms can readily vary the amount of detail conveyed in a scene and are also often useful. But both techniques are difficult to use effectively without specialized equipment to stabilize the camera. Professionals generally restrict their use by panning slowly in just one direction, rather than also panning back. Similarly, they zoom slowly to a fixed point rather than repeatedly zooming in and out. For most video shots, the best rule is to capture moving images with a *still* video camera.

- **Taking Care of Time Code:** Digital video cameras write a **time code** as they are recording images and sound. The code is in the form hours: minutes: seconds: frames. A time code of 01:21:36:05 indicates a location at 1 hour, 21 minutes, 36 seconds, frame 5. This code can be viewed on each frame of the video and it serves as the frame's address. Time code makes it possible to easily locate specific video segments. Editing software uses time code to carry out splits, trims, transitions, and other effects.

Users of tape-based cameras need to take precautions to preserve an accurate time code. These cameras will record a single, continuous time code for the full length of a tape provided that they begin a new recording session at a previously recorded point. If the tape is advanced beyond an earlier recording point, however, the time code will be broken and a new code sequence will begin when the camera resumes recording. This may happen when the camera is shifted to VCR mode to view a previously recorded segment and then advanced beyond the last recorded frame before recording is resumed. Because there is no time code on the tape, the camera treats it as it would a new tape and starts the code over again. The result is that different frames will share the same time code or "address." In order to avoid this conflicting information and the complications it creates for cataloging and editing video, it is important not to break the time code. Cameras often provide an "End Search" control to automatically locate the end point of recording.

White Balancing

White balancing is the process of adjusting a camera to correctly record white in different lighting conditions. Different types of light—the sun, incandescent bulbs, fluorescent tubes, and so on—produce different hues of white. A camera that is not white balanced may produce video with an inaccurate color tint. Most cameras can be automatically white balanced by briefly recording a white object. Videographers often carry a piece of white cloth for this purpose: they aim the camera at the cloth and record for a few seconds. White balancing is particularly important when changing from one artificial light source to another or between indoor and outdoor recording.

- *Getting the Right Shots:* Video planning also includes the identification of particular types of shots needed. Video is used to convey a message. Just as a traditional author chooses words carefully, so too the videographer carefully selects images. One consideration is *coverage*—the source video needs to cover all the important elements of the subject being recorded. A documentary of a figure skating competitor might require source footage of her arrival at the arena, practice sessions, discussions with her coach, and the nervous anticipation of her parents, as well as the competition itself.

In addition to covering all aspects of the subject, videographers are careful to include a variety of different types of shots. Some shot variations reflect changes in the camera's *field of vision*.

- *Close-up shots* (CUs) fill the screen with the subject, focusing the viewer's attention on its details. Close-ups are often used for dramatic effect—the tension in the face of the coach as the skater approaches a difficult jump. These are often among the most powerful video images.
- A *medium shot* (MS) frames the whole subject. Medium shots are used to present the main action or tell the story. The camera frames the skater's whole body as she begins her routine. The greater part of most videos consists of medium shots.
- A *wide shot* (WS) presents the subject as relatively far away and is often used to orient a viewer to the scene of the action. The camera moves out from the skater, showing the stands and the cheering spectators.

There are variations on these basic shot categories—a BCU (big close-up), for example, is an extremely close shot of a subject, while an MCU is a medium close-up. Other important basic shots include establishing shots, cutaways, point-of-view shots, reverse angles, and over-the-shoulder shots.

- An *establishing shot* orients viewers by providing an image identifying the subject. This may be a wide shot, such as the skating arena framed against the city skyline. It could also be a medium shot of a banner presenting the name of the event or a close-up of a ticket stub.
- A *cutaway*, as its name implies, momentarily takes the viewer away from the main subject to a related image. As the skater completes the most difficult part of her routine, a cutaway displays the crowd reaction.
- A *point-of-view* shot shows what the subject would see—a camera behind the skater captures the bouquets of flowers being thrown from the stands at the end of the performance.
- A *reverse angle* shot is sometimes called a *shot/reverse shot*. A shot of the subject is taken from one angle and another shot is taken from a different angle. This may be accomplished either by using two cameras or by moving the camera and restaging the scene. This technique is often used in interviews. One image shows the skater as she responds to a reporter's animated questions after her victory. The reverse shot is taken behind the skater and includes the face of the reporter. This heightens the sense of interaction between the two individuals.
- *Over-the-shoulder* shots include the subject as well as others observing the subject. With the competition over, the skater tells her story to a gathering of friends. The video is shot from behind the crowd of friends, showing portions of them, while

focusing on the skater. Over-the-shoulder shots can efficiently present the interaction of a main subject with other elements of the scene.

With source footage in hand, the digital videographer is ready to begin the editing process and transform a scattered collection of images into a coherent video presentation.

Step 2: Editing Video-editing software ranges from basic consumer packages (e.g., iMovie, Movie Maker) to increasingly powerful prosumer applications (e.g., Final Cut Pro, Premiere, Avid Studio), to specialized, expensive software for professional video and film production. The prosumer category provides desktop multimedia producers, and even some professional videographers, with a powerful complement of video-editing tools.

Digital video editing involves four major tasks:

- Capturing video from an external source
- Arranging separate video sequences, or clips
- Splitting and trimming clips
- Adding transitions and special effects

Editing software provides the tools to perform these tasks. Editors include windows in which each activity takes place. The names and specific features of these windows vary from product to product, but virtually all include variants of preview, library, and construction windows (Figure 8.4).

A *preview window* displays the source video prior to capture and also is used to preview the current project at any time during the editing process. VCR-like controls are provided to rewind, fast-forward, pause, and play. Clips that have been transferred to the computer are located in a *library window*. The library window may also display titles, transitions, and effects that can be applied to the video. Clips are edited and combined in a *construction window*. The construction window presents the assembled video clips either as a **storyboard** or as a **timeline**. The storyboard is a more general overview in



Figure 8.4 Windows, timeline, and tracks in Final Cut Express, a basic video editor.

in the use of a lower resolution, such as 240×180 , for streaming video and video email attachments. Still lower resolutions such as 176×144 may be required for cell phones.

The frame rate is another important factor in the size of video files. Reducing frame rates can dramatically reduce the amount of video information a device must process in a given time. Computer hardware and network bandwidths continue to improve, but frame rates for videos streamed via the Web often must be reduced to ensure that a wide range of users can effectively view them.

Having selected an appropriate codec, resolution, and frame rate, developers then specify the *video data rate*. Codecs typically can compress at different quality settings. Setting a relatively low data rate will require more compression and will usually produce lower-quality video. This is often essential, however, to ensure effective delivery. Rates vary from as low as 20 to 30 kilobits per second (Kbps) for low-quality streaming video to approximately 9 megabits per second (Mbps) for DVDs and up to 48 Mbps for Blu-ray discs. In addition to selecting a data rate, developers often also have the option to select either *constant* or *variable bit rate* encoding. VBR is sometimes done using two passes, one to analyze the video data to determine which scenes to record at a higher or lower rate, and a second to do the actual encoding. This slows the rendering process but usually results in higher quality than CBR.

Finally, most video also includes sound. Sound is recorded on tracks separate from video and can also be encoded using different codecs and data rates. When file size and data rates are not as critical, sound is often recorded in the uncompressed, widely supported PCM (pulse code modulation) format. Common compression options include MP3 and the Dolby Digital AC-3 formats.

8.4 Guidelines for Video

The production of high-quality video has traditionally required expensive equipment, highly trained professionals, and generous budgets. Today, the availability of affordable, powerful digital tools—cameras, editing software, and computers—has made video a practical addition to many multimedia projects. Video is also complex and demanding, however. The successful use of video requires attention to basic guidelines for shooting, editing, and rendering.

Shooting

1. **Choose a camera carefully.** Consider the following:
 - CCDs.
 - Optics.
 - Microphones.
 - Storage media.
 - File formats.
 - Lux rating.
2. **Steady the camera.** Use a tripod or lean against a solid surface.
3. **White balance prior to shooting.** This is especially important when changing between different lighting conditions.
4. **Avoid shooting into light and backlit scenes.**
5. **Limit pans and zooms.**

6. **Frame the subject.** Use the rule of thirds.
7. **Make an inventory of required shots.**
 - Different angles.
 - Wide shots, medium shots, and close-ups.
 - Establishing shots, reverse angles, over-the-shoulder, and point-of-view shots.
8. **Use the highest resolution available.**
9. **Add external microphones if required.**
10. **Use headphones to monitor sound quality.**
11. **Record background sounds for use in editing.**
12. **Don't break the time code.**

Editing

1. **Protect source video.**
 - Keep copies of original sources at the highest resolution and lowest compression.
2. **Save a copy of the master video prior to rendering.**

Rendering

1. **Match codec, resolution, frame rate, and data rate to intended use and delivery medium.**
2. **Use variable bit rate encoding when available.**

8.5 Summary

Powerful microcomputers and sophisticated editing software have made it possible for all multimedia developers to add high-quality video to their productions.

Digital video is characterized by very large file sizes that place significant burdens on processors, storage devices, and, especially, computer networks. Multimedia video is tailored to specific uses by adjusting screen resolutions and frame rates and choosing appropriate compression options.

Digital video is acquired using digital cameras or downloads of previously created digital video files. Relatively inexpensive digital camcorders can produce high-quality video that can be effectively edited by multimedia developers. Most multimedia development will require a shoot-to-edit approach, in which careful planning identifies the range of necessary video clips. Editing software can then be used to capture video, arrange clips, carry out splitting and trimming, add transitions and effects, and finally render the master video as a new video file suitable for distribution.

Key Terms

Aspect ratio	Codec
AVCHD	D1
CBR	DV
CCD	DVD-Video

Flash Video	Rule of thirds
Frame rate	Scalable compression
HDTV	Screen resolution
HDV	SDTV
Interframe compression	Shooting to edit
Intraframe compression	Shooting to record
Master video	Source video
M-JPEG	Splitting
Motion JPEG 2000	Storyboard
MPEG	Time code
Output resolution	Timeline
QuickTime	Transitions
RealVideo	Trimming
Rendering	VBR
RGB	Windows Media Video

Review Questions

1. What is the distinction between film and video?
2. What is screen resolution and what does it mean for digital video?
3. Why do developers often need to adjust the output resolution of digital video?
4. What is a codec?
5. Identify and define the three main strategies for compressing digital video.
6. Identify one advantage and one disadvantage of interframe compression.
7. What is the distinction between MPEG2 and MPEG4 video compression?
8. What is one advantage of the DV format for archiving standard definition video?
9. What are the three steps in creating original digital video?
10. Identify and explain the two main approaches to shooting video.
11. Describe the rule of thirds and explain its importance in shooting video.
12. What is time code and why is it important in shooting video?


Discussion Questions

1. Identify and explain the three factors that influence the quality of digital video output.
2. Why does digital video produce large data files?
3. How do developers control these large data files?
4. You are sent to shoot the source footage for a video promoting your college. Identify and explain three important considerations for shooting this digital video.
5. Your college plans to have one version of the video promotion on the college website and a second version on a DVD to accompany the Admissions catalog. Identify and explain the important considerations when you render the video project for each of these uses.

6. Describe the features of a digital camera that are important to consider if your multimedia project requires professional-quality digital video.
7. Locate a 45- to 90-second video clip on YouTube. Discuss the quality of the video, including shot selection, camera control, and editing. How could the clip be improved?
8. Research developments in 3-D digital video recording. Report how this 3-D space is achieved and the features of cameras that support 3-D recording.
9. Research the AVCHD format. Report the benefits of this digital video format and details regarding the variety of video resolutions supported by the standard.
10. Research the Motion JPEG 2000 format. Report the benefits of this digital video format and details regarding its current uses.

Chapter 9

Animation



Topics you will explore include:

- Animation Basics
- Traditional Animation Techniques
- Cel Animation
- 2-D Digital Animation
 - Key frame
 - Tween
 - Programmed
- 3-D Digital Animation
 - Motion Capture
 - Forward Kinematics
 - Inverse Kinematics
 - Animating with Physics
 - Prerendering
 - Real-Time Rendering
- Guidelines for Animation

9.1 The Brave New World of Digital Animation

Animation is the pinnacle of modern multimedia. It incorporates and draws inspiration from each of the other media. And more than any other medium, animation exploits the creative and transforming potential of the computer as a “universal machine.”

Computers have dramatically lowered the costs and increased the ease of creating many different types of animation. *Motion graphics*, for example, is the art of making titles, credits, and other graphic objects move across movie and television screens. For many years, only large studios could afford these services. Now individuals and small groups readily create a wide array of flashing text, spinning logos, and image morphs to complement websites and other multimedia productions. Virtually every form of traditional animation from the simplest flipbook to the extraordinary creations of the great Disney Studios has been transformed by digital technology.

The revolution in animation is not just about economy and efficiency. The computer also provides developers with entirely new capabilities that have resulted in animations that were inconceivable a generation ago. These new creative powers draw on three principal capabilities of computers.

First, the computer supports *interactivity*. Traditional animation is a passive medium, intended simply for viewing. By contrast, the computer supports user participation. We do not *watch* video games or flight simulators. We *play* and *fly* them.

Second, computers can convincingly *simulate three-dimensional sensory experience*. Traditional animations were largely two-dimensional fantasy worlds that playfully presented improbable behaviors such as singing mice and flying men. The computer now supports an entirely different form of fantasy by creating realistic 3-D characters and scenes that are often indistinguishable from those of video or film.

Third, computers can *embody and implement rules of behavior*. A traditionally animated character does what it is *drawn* to do. Computer-animated characters do what they are *told* to do. There are many different types of “rules of behavior.” Some determine how the object is to appear. Computers create realistic 3-D images through algorithms that, in effect, tell the object how to respond to simulated light. The rules may also determine motion. *Inverse kinematics* provides rules of behavior for the various limbs of animated characters so that the hipbone really is connected to the thighbone—and both move as they should. The airplane in a flight simulator flies realistically because the computer is implementing a set of rules to reproduce the responses of simulated airfoils to different flight conditions. The behaviors may also be psychological, as with game characters that react to certain situations, such as the presence of weapons or food, in specific ways whenever they happen to encounter them.

The computer transformed the work of animators by providing powerful tools of creative expression and new ways to engage their audiences. The potential of these new forms of animation is already clear in video games that addictively immerse their players in alternate realities and in films that convincingly substitute fully digital actors for human performers. As the film producer Jeffrey Katzenberg once remarked, thanks to computer-generated animation, “If we can imagine it, we can make it.” These new powers follow directly from the programmability of the computer, from the fact that it is a universal machine with, in a practical sense at least, unlimited potential. Digital animation is indeed a “brave new world,” one that will almost certainly continue to generate

The familiar **flipbook** can present dozens of images on a series of pages, each showing a different stage of a motion. As the pages are rapidly flipped beneath the thumb, the motion, such as a person walking, is displayed. The flipbook illustrates several additional elements of animation. First, the *quality* of the motion will depend on the rate of display—very slow flipping produces jerky, unnatural motion. Second, assuming an adequate rate of flipping, the *speed* of the motion will depend on the differences between the images—larger variations in the positions of arms and legs from one drawing to the next will produce the illusion of a faster walk. Third, each drawing must be a variation on its predecessor, usually with slight changes between the two. To produce a new image, it is important to be able to use the preceding one as a reference. This is accomplished by laying a new page over the drawing. If the paper is thin enough, the previous image will show through. Thicker papers will require a light table to illuminate the underlying image. This process of drawing while referencing preceding images is traditionally known as **onionskinning**. Finally, the flipbook also illustrates *registration*, another basic requirement of animation. Registration is a way of physically aligning the images with one another. The binding of a simple notepad accomplishes this. Drawing on a set of loose sheets requires prepunched holes and peg systems or some other form of registration.




Figure 9.2 Zoetrope.

The 19th century saw the development of mechanical animation display devices. One, the *zoetrope*, was a rotating drum with slits on its side (Figure 9.2). A light illuminated a strip of drawings fastened inside the drum. As the drum turned, the viewer caught a glimpse of each successive image through the passing slits. When the drum was rotated at an appropriate speed, persistence of vision blended the individual images and produced the perception of motion. Another device, called the *praxinoscope*, was used by Charles-Émile Reynaud to project short animations to audiences at his Théâtre Optique in Paris during the 1890s. This early experiment gave little more than a hint, however, of the enormous influence of fully developed animation.

9.3 Traditional Animation

Traditional animation is film-based. Individual images of the animation sequence are photographed and recorded as separate frames on a long strip of transparent film. The film is passed in front of the light of a projector and the animation appears on-screen. Later, video was used to encode the images and sounds of film on magnetic tape for television display. Movie theaters and televisions provided animators with the mass communication possibilities that drove the commercial development of traditional animation.

Film dramatically enhanced the expressive possibilities of animation. Multiple reels could hold any desired number of individual film images. This made it possible for animators to create longer animations with more subtle motions. Projectors reliably displayed

The different components of objects often move independently of one another. If the snowball strikes a tree at the bottom of the hill, the motion of the branches will, at first, lag behind the motion of the trunk. As the trunk comes to temporary rest at the extreme point of its motion, the branches will continue to move. Paying attention to such *overlapping motions* helps animators produce convincing, lively motions.

Close observation of the natural world is important for successful animation. But most animators are not trying to simply duplicate natural motion. Instead, animation usually derives its power from the skillful exaggeration of motion for dramatic effect. Often the

exaggeration is simply in the rate of motion—the snowball eases into its downhill motion, but it gains speed with an unnatural rapidity and quickly grows to enormous proportions, scattering the terrified people in its path. Other forms of exaggeration focus on distortion. **Stretch** and **squash** are staples of the traditional animator's art (Figure 9.4). The speeding snowball hits a bump and flies into the air. As it rises, it stretches to form a vertically elongated ellipse. It hits the ground and is squashed into a horizontal ellipse; it snaps back to a round shape and races on. Stretch and squash wildly exaggerate the effects of gravity to enliven the




Figure 9.4 Stretch and squash.

snowball's journey.

These strategies have been applied to a wide range of animation subjects. In fact, anything that can be photographed is a candidate for animation. Paper cutouts, clay figurines, puppets, and all sorts of natural objects have been posed, photographed, reposed, and photographed again to create the individual photo frames of filmed animation. But the technique that most directly influenced the development of digital animation was cel animation.

9.4 Cel Animation

Cel animation was perfected and popularized by the Disney Studios of the early and mid-20th century. **Cel** originally referred to the drawings of individual animation frames made on sheets of celluloid, the same flexible, transparent material used for early films. These drawings were then photographed to produce the animated film. Today, acetate has replaced celluloid, but the technique is still known by its traditional name.

The main advantage of cels is that they save enormous amounts of drawing time by allowing animators to break scenes into those parts that stay the same and those that must be changed from frame to frame. A single drawing can then be used over and over for the unchanging elements of the scene. For instance, if a character skips down a village path, the path, the village buildings, sky, clouds, trees, and so on are unchanging background items. These can be placed on one cel. Objects that change can be placed on another layer of cels. The skipping child will require a series of drawings, each depicting different positions of her arms, legs, head, and torso. Only the child will be drawn on this layer of cels. To create the individual frames of the animation, the two layers are stacked over a light source and the composite image—background village scene and one stage of the skipping child—is photographed. For the next frame, the top cel is

2-D Animation

Developers can produce simple 2-D digital animations by mimicking basic traditional techniques such as the flipbook. *Animated GIFs* consist of a series of individual GIF images that are rapidly displayed in sequence. Simple software lets animators insert or delete images, vary the rate of display, stop or loop the animation, and so on.

Other forms of traditional animation also have digital counterparts. *Cutout animation* uses figures cut from paper or other flat material. These are often made up of separate parts, such as arms or legs that can be positioned differently to produce the various states of motion needed for the animation. Producing the figures, manipulating their parts, and photographing each setup are time-consuming tasks. Digital paint and draw programs can be used to create and modify cutouts much more rapidly and with greater control of detail. Animation programs can then be used to quickly import these images, arrange them on a timeline, set timing and transitions, and produce the final animation as a digital movie.

Rotoscoping was also transformed by digital techniques. **Rotoscoping** is the process of producing an animated sequence by tracing the individual frames of a film or video. This can be especially effective for animating complex motions, such as the twisting and turning of people dancing. Traditionally, the filmed dance would be projected one frame at a time to a surface on which an artist could trace the outlines of the dancers. The sequence of tracings captured the pattern of motion and the tracings themselves could then be developed by the artist to fit the subject and mood of the animation. Rotoscoping was labor-intensive and required specialized equipment usually available only at larger production studios. The computer makes rotoscoping a practical tool, available to virtually any animator. Film or video is simply converted to digital form or shot with digital cameras. Individual frames are then imported to image-editing programs such as Photoshop that allow the artist to add a transparent layer and trace the desired parts of the scene. The original image layer is deleted, leaving behind the traced layer. This can be further developed and saved as an animation frame. The individual frames are then imported to an animation or video program such as After Effects or Premiere where they are sequenced and edited.

More complex productions can be created using 2-D animation software that mirrors many of the elements of traditional cel animation. Animations are composed of a series of individual frames like the film frames used to present a cel animation, the frames are synchronized to one or more sound tracks, graphic elements can be placed on different layers corresponding to traditional cels, major changes in scenes are designated as key frames, and the illusion of motion is created by producing a series of tweens based on key frames.

Digital animation programs such as Flash or Director present frames as a horizontal row of small rectangles in a window called a **timeline**. Developers can easily move to different frames by clicking on a frame or by using simple controls similar to those on VCR or DVD players. The contents of the frame are displayed in another window where they can be edited. The timeline makes it possible to precisely control each frame of the animation.

A frame in a digital animation may be composed of multiple *layers*, just as a frame in a cel animation may be composed of several transparent sheets of “celluloid.” As in cel animation, layers have a stacking order. The lowest layer is used for background elements, those images that remain the same as others are changed to produce the appearance of motion. Animators can easily change the order of layers. And unlike traditional animation, there is no need for precise registration devices to maintain alignment or different paints for different cel layers to compensate for the effects of opacity.

The key frames and tweens of traditional cel animation are also important components of digital animation. The creation of frames is facilitated by another digital variant of a traditional technique, onionskinning. Here the computer imitates the process of using one drawing as a reference for a new image by creating a faint image of the original on one layer and allowing the animator to draw on a second, higher layer. Animators can produce each successive frame manually. This is known as **frame-by-frame animation**, a technique that provides complete control over frame content, but is also very time consuming.

Tween Animation A powerful alternative to the frame-by-frame approach is tween animation. In **tween animation**, the animator creates the key frames and the computer




Figure 9.5 Motion tween defined in the timeline using Flash MX.




Figure 9.6 Motion guides in Flash determine the location of each animated object.

automatically produces the tweens. There are several different types of tweens. A simple **motion tween** can be used to move an object from one position to another. The first key frame places the object in one position and the second places it in another. The program then fills in the intervening frames (Figure 9.5). Tweening is also used to produce **path-based animation**: the animator draws a path from one key frame to another and the computer fills in the intervening images, spaced out along the path, to produce the desired motion (Figure 9.6).

Tweening is also used to animate other properties of objects. One common example is *morphing*, also known as *shape tweening*. In **morphing**, the shape of one image is gradually modified until it changes into another shape. The image of a child might be morphed to that of an adult or a drawing of a pen might be morphed to a rocket ship. The key frames in this case are the two images and, again, the animation program creates the tweens, the sequence of frames over which the program gradually alters the shape of the object, little by little, to complete a transition from one to the other (Figure 9.7). Animators can control the way in which objects change by specifying the points of the

Programmed, or procedural, animation is a different approach. In **programmed animation**, animators write commands and the computer generates the animation. This requires knowledge of programming languages and the mathematical techniques required to specify patterns of movement as well as the other changes (size, shape, color, etc.) that occur in the animation.

Programmed Animation in Flash

The following script is a simple example of rotating an object through programming, rather than tweening:

```
OnClipEvent (enterFrame) {_rotation += 9}
```

Programmed animation has several advantages. Files sizes are smaller because much of the animation consists of commands, rather than a series of images. This reduces storage, bandwidth, and processor requirements. As a result, programmed animations load and play more quickly, allowing them to be used on a wider range of computers and networks.

Another advantage is the relative ease with which different versions of an animation can be created. For instance, if an animation requires a large flock of birds, a single bird can be animated procedurally. The animator can then create different birds by simply altering the parameters governing direction, speed, wing motion, and so on.

Programmed animation also supports more complex forms of interactivity. In computer games, developers often provide users with a wide range of choices. Programmed animation allows the developer to specify the content of the animation that the computer will create based on the user's actions. The animation is then generated "on the fly."

Animation software may support both tweening and programmed animation. The scripting languages (ActionScript, Lingo) in Flash and Director, for instance, can be used to produce programmed animations. Once a programmed animation is created, it can be used alone or in combination with tweened animations.

The computer provides flexible, novel animation possibilities through programming and it transformed traditional 2-D animation techniques such as cel animation, cutouts, and rotoscoping. It had an even greater impact on 3-D animation.

3-D Animation

Traditional 3-D animations are created with sequences of photographs of three-dimensional objects such as clay figures, puppets, toys, models, and people. The animator sets up one scene, photographs it, makes changes to the figures to be animated, takes another photograph, and so on until the animated sequence has been completed. This is a time-consuming process requiring painstaking attention to the positions of the animated objects as well as careful control of camera angles and lighting.

The earliest applications of the computer to 3-D animation simply facilitated traditional approaches. For example, specially designed and programmed computers were used to precisely control the motion of cameras across a stage area. The computer allowed operators to shoot each frame, reposition objects, and shoot the next frame from a new position. When the frames were projected, the motion of the camera would appear perfectly smooth because of the precise positional control provided by the computer.

As the graphics rendering capabilities of computers improved, their role in 3-D animation changed. Now computers could be used to create convincing representations of three-dimensional objects themselves and then set them in motion. This eliminated

the need for elaborately built stages and models and soon led to the creation of novel animations that could not be produced using traditional techniques. This new form of 3-D animation involves three major, interrelated tasks: *creating objects and scenes*, *defining motions*, and *rendering*.

Creating Objects and Scenes Animators create their objects and scenes in much the same ways as 3-D graphics artists do—through *modeling*, *surface definition*, and *scene composition*. Modeling defines the shapes of objects using techniques such as polygons, splines, and metaballs (see Chapter 6). Surfaces are defined by specifying materials (glass, metal, wood, etc.), applying image and bump maps, and establishing properties such as opacity and reflectivity. Animators compose scenes by placing objects and defining camera angles, lighting, and environmental effects.

Defining Motions The second major task in 3-D animation is to define motions. The elements of a 3-D animation include the objects and sounds viewers will experience as well as the cameras and lights used by the animator to define the finished product. Virtually all of these elements can be set in motion. Cameras can move in and out of a scene as if they were on tracks or booms, lights can follow characters and, of course, the characters themselves can be transformed in all the ways established by the animation tradition. Stretch and squash, ease-in and ease-out, exaggeration and anticipation—all these traditional manipulations and more remain directly relevant to 3-D animation.

As in 2-D animation, 3-D developers use key frames to designate major changes in an animation with intervening frames produced by the computer. The movements captured in key frames can be created in several different ways. Models can be placed at different points in a scene to define a path that is then completed through computer tweening. Similarly, shapes, colors, transparency, and texture can be changed using key frames and tweens. The most complex motions typically involve models of humans and animals. Here it is necessary to manipulate individual body parts to achieve realistic motion. *Motion capture*, *forward kinematics*, and *inverse kinematics* are three of the major techniques used to animate animals and humans.

Motion capture, also known as *performance animation*, is the technique of recording the motions of actual objects, such as human or animal bodies, and mapping these motions to a computer-generated animated character. The “performers” are equipped with sensors to track the motion of various body parts as they create the actions to be animated. This information is transmitted to the computer and processed to produce the corresponding motion in the animated character on screen. In this way animation producers and performers can see the results of the performance and immediately make any necessary adjustments. Performance animation is often used to capture complex natural motions that would be difficult to create using other techniques. The technique has been used to reproduce the movements of highly realistic “virtual actors” and “virtual models” that are intended to be indistinguishable from real humans. In other cases, the results of performance animation are deliberately modified to be less realistic to fit the style of a specific production.

Kinematics is the study of the motion of bodies or systems of bodies. Animals are systems of body parts. The motion of one part, such as a knee, produces related motions in others—thigh, shin, and foot. In **forward kinematics**, objects are modeled as

as IK, free animators from some of the more laborious aspects of 3-D animation, allowing them to concentrate on creating engaging characters and stories.

Rendering As in static 3-D graphics, rendering is the final step used to produce the frames of a 3-D animation. **Rendering** creates the final animation frames by applying the modeling, surface definition, scene composition, and motion specifications created by the animator. An animation may be either *prerendered* or rendered *in real time*, “on the fly.” The former approach is appropriate for applications with little or no interactivity, such as animated films. The latter is essential for highly interactive animations such as video games because the final form of the animation depends on the user’s choices.

Prerendering of an animated feature film such as *Toy Story* or *The Polar Express* requires enormous processing resources. Each of the film’s many thousands of individual frames is a high-resolution bitmapped image. The individual pixels that make up these images are defined by complex calculations carried out by the computer to implement the object properties, lighting, camera angles, and motions specified by animators. To render *Toy Story*, the first fully digital feature-length animated film, Pixar Animation used a “rendering farm,” a network of 117 workstations, each with at least two processors. The task required 800,000 computer hours (a single computer would have taken 43 years to complete this task).

The luxuries of rendering farms and weeks of rendering time are not available for video games and other highly interactive 3-D animations. In these cases the computer must produce the animation immediately. More-powerful computers and specialized *play stations* with powerful graphics-processing capabilities are part of the solution to this challenge. Simplifying the animations themselves by creating objects with low polygon counts and minimizing the use of complex textures and shading is also important. The animated objects of a video game are usually created through programming languages such as C++ and then rendered in real time by rendering routines provided through Direct3D or OpenGL.

OpenGL and Direct3D

OpenGL and Direct3D are APIs, *Application Programming Interfaces*. OpenGL is a widely implemented cross-platform API, whereas Direct3D is a Microsoft standard for Windows PCs.

APIs specify standard definitions and functions that can be implemented by a range of software and hardware. For instance, OpenGL provides functions to draw 3-D objects from primitives, apply textures, set camera angles and lighting, and render scenes in real time. Programmers can use these functions with all OpenGL compliant hardware and software. This simplifies application development and also encourages rapid adoption of new devices such as improved video cards.

9.6 Animation Tips and Guidelines

Animation covers an extremely wide range of productions from the very simple, such as spinning logos that can be produced quickly by individuals, to complex feature-length films that require years of coordinated effort by hundreds of artists and technicians. Nonetheless, many of the guidelines appropriate to larger productions are also useful for individuals and small teams. Animation typically requires greater computational resources than static media such as text, drawings, or photos, and the process can easily become expensive and unwieldy without careful planning.

1. **Don’t forget the learning curve!** Animation programs are typically more difficult to master than other media-specific software.

2. **Design for delivery.** Complex animations rapidly consume bandwidth and processing. Be sure your animation can reach its intended audience. To minimize animation file size:
 - Use simple backgrounds.
 - Simplify and limit the number of objects.
 - Limit the number of lights and the use of reflections and transparencies.
 - Experiment with different rendering options to pick the best combination of file size and quality.
 - Be sure to preserve an original uncompressed file.
3. **Consider clip animation.** An appropriate animation may be available at little or no cost.
4. **Consult the tradition.** The staples of the animator's art will often ease the development process and enliven a digital production. Consider:
 - Cycles.
 - Holds.
 - Shooting on twos.
 - Tweening—motion, size, color, shape.
 - Stretch & squash.
 - Ease in & ease out.
 - Overshoot & overlapping motion.

9.7 Summary

The dramatic accomplishments of digital animation are based on a rich animation tradition, a powerful new set of digital tools, and, above all, the creativity of a new generation of writers, producers, animators, and programmers. The “universal machine” plays a two-fold role in their work.

On the one hand, computers serve as very efficient assistants in the animation process. In the hands of skilled developers, digital versions of traditional tools for creating, editing, and combining media save time and money. On the other, the computer has extended its role, becoming not simply a tool but also a virtual partner in the creative process. The key to this transformation lies in the computer's universality—its ability to embody any form of knowledge and intelligence that we can either define ourselves or find a means of empowering the machine to define for itself.

The practical effects of machine intelligence are already evident in 3-D animation techniques. We have seen them in advanced forms of rendering and in the variety of algorithms used to produce natural motions and behaviors. Here the computer creates scenes that animators simply could not know how to create on their own. New animation software will incorporate increasing amounts of knowledge and intelligence, allowing animators to express an unprecedented range of experience from the hyperrealistic world of virtual humans to otherworldly forms limited only by their imaginations. Together, advanced computers and talented animators will ensure that digital animation remains the cutting-edge frontier of modern multimedia for some time to come.

Key Terms

Alpha tweening	Onionskinning
Animating with physics	Path-based animation
Cel	Pencil test
Cycle	Persistence of vision
Ease-in/Ease-out	Programmed animation
Flipbook	Rendering
Forward kinematics	Rotoscoping
Frame-by-frame animation	Scratch track
Holds	Shooting on twos
Inverse kinematics	Size tweening
Key frame	Storyboard
Kinematics	Stretch/Squash
Leica reel	Timeline
Morphing	Tween animation
Motion capture	Tweens
Motion tween	

Review Questions

1. What is persistence of vision? How is it related to animation?
2. What basic elements of animation are illustrated in a simple flipbook of images?
3. What were the advantages of film for traditional animation?
4. What is a key frame? How did it improve the efficiency of developing traditional animation?
5. Why was celluloid significant in the development of traditional animations?
6. What is onionskinning?
7. What is a storyboard?
8. What is a pencil test?
9. What is a scratch track?
10. What are animated GIFs? In what way are they similar to a flipbook animation?
11. Describe the process of rotoscoping. How is it used in 2-D animation?
12. What are the features of 2-D animation software that mimic traditional animation?
13. What is the difference between frame-by-frame animation and tween animation sequences?
14. What is morphing?
15. How do program commands generate animation?
16. What are the advantages of programmed animations?
17. Describe the process of motion capture for creating 3-D animation.
18. When is performance animation frequently used for 3-D animation?
19. What is kinematics? What is the difference between forward and inverse kinematics?


20. Identify and explain which form of kinematics requires more computer-processing power.
21. What are the advantages of animating with physics?
22. What is prerendering and when is it used?
23. Why is real-time rendering often found in computer video games?
24. Identify and explain two guidelines that will be important to follow if you need to create an animated web logo for a client's website.
25. Identify and explain two guidelines that will be important to follow if you need to develop a computer-animated children's fable.

Discussion Questions

1. Identify the major challenge of traditional animation and explain three methods to overcome that challenge.
2. Identify the role of the storyboard, pencil test, and scratch track in developing a traditional animation.
3. Why is cel animation described as a "complex, demanding, and expensive form of animation"?
4. What specific efficiencies did animation software introduce to the 2-D traditional animation process?
5. Identify and explain four types of tweening found in typical 2-D animation software applications.
6. In what ways do the power of new computers alter the development of 3-D animation?
7. Research and explain how claymation animation is produced. Is this an example of computerized animation or not? Explain.
8. If you train as a 3-D digital artist, would you have the necessary skills to become a 3-D digital animator? Explain your response.
9. List the steps for creating 3-D animation and identify the main purpose of each.
10. Would a 3-D animator prefer to use forward or inverse kinematics to develop an animated sequence of a school of dolphins? Explain your answer.
11. Identify a current animation sequence from a movie, TV, or website and analyze how you think the developer may have created it. Refer to specific techniques for computer animation.
12. Video games are a major product in the entertainment market. Based on your knowledge of animation, what techniques might an animator use to make sure the gaming animations remain current, flexible, and responsive to the player?
13. Why do the authors suggest that computer animation is the "pinnacle of modern multimedia"? Do you agree with this assessment or not? Explain.

Chapter 10

Authoring



Topics you will explore include:

- Approaches to Authoring
- Authoring Metaphors
 - Card
 - Icon
 - Timeline
- Authoring Process
 - Application Design
 - Importing and Creating Media
 - Editing Content
 - Integrating and Synchronizing Media
 - Establishing Navigation Structure
 - Adding Programming Components
 - Database Support
 - Previewing, Testing, and Debugging Applications
 - Project Delivery
- Choosing an Authoring Application

Timeline Metaphor The **timeline metaphor** organizes media content and interactivity as sequences of **frames** much like the frames of traditional films and animations. Media elements are first imported into a *library* or *cast window*. They can then be used repeatedly in many different frames without significantly increasing file size. Each frame can have multiple layers. Layers define the stacking order of the media. A graphic that is shared by several frames is placed on the bottom layer to create a background. Other media intended to appear in front of the background are placed in higher layers. Sounds play in a separate layer and extend over multiple frames. Transitions can be applied to a sequence of frames to fade items in or out of the viewing area. The timeline controls the presentation of events and interactivity. As the *playhead* moves across the timeline, individual frames appear on the screen. The rate of playback, in frames per second (fps), can be regulated, and navigation menus or buttons can be placed in a frame to alter the flow of the playhead on the timeline (Figure 10.4).

The timeline metaphor is especially appropriate for dynamic media, such as video and sound, which change over time. Timeline applications, such as Director and Flash, are powerful authoring tools that allow developers to precisely synchronize the elements of animation sequences based on fractions of seconds. They are also more difficult to learn and are usually chosen only when animation or video is the dominant element in a multimedia project.




Figure 10.4 This timeline from Flash shows media organized in frames. Frame 1 is one instance of the display sequence. Each frame has 14 layers. Two layers have a special purpose: one layer contains program code to control the playback sequence and the top layer contains sound tracks synchronized to each frame. The playhead, the rectangle at the top, is currently on frame 21. See Color Plate 27.

10.2 The Authoring Process

Multimedia authoring involves a series of interrelated tasks. Developers *design* the application. They *import* or *create*, and *edit* various media elements. They *integrate* and *synchronize* media. They *establish navigation structure* and they may *program* more-sophisticated user interactions. They may also add *database support*. They *preview*, *test*, and *debug* their applications. Finally, they prepare (or *publish*) their products for delivery. Just as authoring applications differ in terms of their basic metaphors, they also vary in their capabilities to perform these essential tasks.

Application Design

Authoring software may include a number of features to support the design process. Presentation programs, such as PowerPoint, usually provide an outline view in which authors can organize the basic structure of a presentation. More complex multimedia projects often make use of storyboards. A **storyboard** is a series of sketches of screens used to guide the development process. Storyboards include layouts of screen elements such as media and navigation controls as well as directions to guide the work of animators, programmers, and other members of the development team.

Authoring applications with good support for design can speed the development process because it is usually easier to build an application from a design created in the same program.

Importing Content

Multimedia content is frequently created in media-specific applications such as paint or draw programs that use their own (“proprietary”) file formats. Media content can also be purchased in a variety of formats from clip library sources. To make use of these different forms of media, authoring applications can usually import several different file formats. Not all formats are supported by all authoring applications, however. For example, images in .psd (Photoshop) format or sounds saved as MIDI files may not be directly supported by the authoring application. Such files can usually be converted to supported formats such as TIFF for .psd files or QuickTime for MIDI, but this adds another step to the development process.

Creating and Editing Content

Media-specific applications have powerful tools optimized for the tasks each performs. The development process would be very inefficient, however, if every element of a multimedia application had to be created and edited in different, specialized applications. For this reason, all authoring applications include some media creation and editing capability. For example, all applications have tools to enter text either as a graphic or in editable text form. Text content is often easier to create and edit within the authoring application when the supporting media are visible on screen. Adjustments to font size, color, and style are also easier to make within the authoring environment.

Many authoring programs also include basic image- and sound-editing capabilities. This makes it possible to quickly create graphics for buttons, make simple adjustments to imported images, or shorten sounds. The power and flexibility of these tools varies widely from product to product. PowerPoint includes a basic draw program while the capability of Flash draw tools is more advanced. Similarly, the paint capabilities of Authorware or SuperCard are less powerful than those of Director.

Media Integration, Synchronization, and Playback

Once the content is developed, authoring software is used to integrate and synchronize various media elements and determine the order in which they are played for a user. Techniques for media integration vary with authoring metaphor. Media may be placed on a card surface, represented as an icon and dragged to a flowline, or selected from a library or cast window and placed on a timeline. The position and order of objects may be determined by placement in layers.

Synchronization is critical for dynamic media. Sounds, animations, and transitions must be timed to present a coordinated and unified flow of information. Authoring tools approach synchronization in various ways. Objects can be held on screen for specific times (20 seconds) or paused on screen until another event occurs such as the end of a sound segment. In these cases, timing properties are assigned to the objects themselves. More complex synchronization is done on timelines. Media objects are placed on the timeline to

play for a specified number of frames. In similar fashion, an animation can be synchronized to a sound track by placing each on a different layer of a common sequence of frames.

Variations in computer processor speeds, access times for storage devices such as hard drives or optical discs, and network transmission rates make synchronization particularly important for multimedia developers. Dynamic data such as video places high demands on computer systems. Less powerful, slower systems often cannot process the information rapidly enough to maintain smooth motion and consistent sound. An animation with a high frame rate created on a fast processor may slow to a crawl on less capable systems or not play at all. To ensure adequate performance on different systems, authoring applications optimized for dynamic media often have options to synchronize media automatically. Timing controls can be applied to various media components or the final project may be defined with parameters to drop out images to keep up with sound playback.

Establishing Navigation Structure

Authoring tools are also used to determine the order in which content is presented to the user, which is known as playback. Playback is determined by navigation structure. There are four basic navigation structures: *linear*, *hierarchical*, *networked*, and *conditional*.

The simplest form of navigation is **linear** or *sequential*. Screens are viewed one after the other, much like the pages of a book. Linear navigation is appropriate whenever information is best presented as an unvarying sequence, such as a recipe for baking a cake. Some authoring applications, such as PowerPoint, are particularly well suited to linear navigation. While other navigational structures can be created in PowerPoint, the normal flow of information is from one slide to the next as a user clicks a mouse.

A second navigation structure is **hierarchical**. Navigation starts at the top with the most general topic and filters down to more specific options. Authoring software is used to structure menu options or create other forms of hierarchical navigation such as *image maps*. An **image map** is a graphic with "hot spots" where a user can click to navigate to a particular topic. For example, a state tourist map might include the counties as hotspots. Clicking on a particular county leads to a description of tourist attractions in that region.

Networked is the third common navigational structure. A networked structure allows users to explore more freely by replacing sequences or hierarchies with a variety of user options. One common form of a networked structure is the hyperlink. **Hyperlinks** are connections between two data items, for instance, between the title of a painting and a photo of the painting. A single website may be organized in a hierarchical structure of web pages by the author, but the hyperlinks within each page can send the user on a "web" of exploration with no prescribed path (Figure 10.5).

Finally, navigation structures may be **conditional**. Access to information is contingent on the user's responses or progress in the application. A specific project may require that certain conditions be met before the user proceeds to the next step. A multimedia tutorial on video editing, for example, may prevent users from jumping to the last chapter if they haven't completed the previous sections. In these cases, programming code specifies conditional navigation.




Figure 10.5 Navigation structures.

Navigation control is an important consideration for developers. It governs how the content is structured and controls the playback sequence. Multimedia developers plan navigation structures as part of the design process and they choose authoring applications based in part on how well they support navigation.

Programming

All authoring applications can create basic navigation structures as well as other simple interactions, such as playing a sound or video. Applications such as PowerPoint use a series of dialogue boxes to specify the actions of screen buttons, add hyperlinked terms, and create simple forms of animation.

These simple interactions are adequate for basic multimedia presentations but more complex projects require more flexibility and control. Projects with extensive interactivity, such as tutorials and games, or customized routines, such as a calculator or a stopwatch, require authoring applications with programming capability.

Programming in authoring applications is either script or icon based. A **script** is a series of commands specifying the properties or behavior of a specific element in a mul-

The second approach to playing the application embeds or bundles a player directly in the multimedia project. In this case, the player is no longer separate; it becomes part of the application file. This increases application file size, but it has the advantage of producing a stand-alone file for easy distribution. PowerPoint includes a “Package for CD” feature that embeds the PowerPoint Viewer into the presentation. Users do not have to own PowerPoint to view the file nor do they need a separate player, the application stands alone. Similarly, a project created in Flash may be published as a stand-alone projector file. This embeds the Flash Player, producing an application that will play without the use of a browser.

10.3 Choosing an Authoring Application

No single authoring tool is suitable for all multimedia projects. Multimedia developers select authoring applications by matching the requirements of specific projects to the features available in a given authoring product. The following guidelines identify some of the major considerations in this process.

1. **Consider the subject.** Is the content mainly static (not changing over time, such as photos or text) or dynamic (sound, animation, video)? Card-based applications will be easier to use and very effective for most static content. Dynamic media may require timeline-based applications.
Will the content require specialized features? If so, these should be directly matched to capabilities of the authoring application. For instance:
 - Capturing, storing, and retrieving user responses.
 - Extensive hyperlinks.
 - External database support.
2. **Consider the media.** Are the file formats of the graphics, audio, animations, and video for the project directly supported in the authoring application? If not, can they be readily converted?
3. **Consider delivery.** Where will the application be used?
 - Desktop applications are often delivered on CD-ROMs or DVD-ROMs with high storage capacities. This permits ready delivery of large, media-rich projects developed in applications such as Director.
 - Network delivery often requires applications optimized for small file sizes, such as Flash.
4. **Consider maintenance.**
 - Is the application widely used and supported? If so, expertise is more likely to be available for future revision.
 - Will the project require frequent updates? If so, choose an application that simplifies this process.
 - Some applications store individual media once, referencing each with an alias for repeated use. Changing an element such as a logo may mean simply replacing one graphic with a new one—all the references to that one image are automatically updated.

- Some applications can import external files at the time of playback. Updating the application may be as easy as replacing one of the files. This is particularly useful in projects that rely on timely data such as catalogs or advertisements.

10.4 Summary

Authoring applications are used to assemble and synchronize media elements, develop the user interface, and provide interactivity. Authoring applications are based on different development metaphors. One readily grasped metaphor organizes the content on a sequence of cards, pages, or slides. An icon metaphor organizes media on a flowline, and the timeline metaphor presents the content in a sequence of frames with multiple layers of media elements. Authoring applications have a range of tools for importing, creating, and editing media elements. In addition, many applications support some form of programming to control navigation, playback, and interaction with the media. Because these applications vary in their features and uses, multimedia developers may employ different authoring products for different projects. They make their choices by matching project requirements to the metaphor and features of the authoring application.

Key Terms


Authoring	Icon
Authoring application	Icon metaphor
Background layer	Icon programming
Card metaphor	Image map
Conditional	Linear
Database	Metaphor
Debugger	Networked
Flowline	Player
Foreground layer	Programming
Frame	Script
Hierarchical	Storyboard
Hyperlink	Timeline metaphor

Review Questions

1. What is an authoring application?
2. What is the benefit of an authoring application over programming languages to develop a project?
3. What is a metaphor?
4. What is the purpose of authoring metaphors?
5. What are the three common authoring metaphors for project development?
6. What are the two layers on a card?
7. What are the benefits of using a background layer in the card metaphor?
8. How does the icon metaphor organize media content?
9. What type of media content is most appropriate for a timeline metaphor?

Chapter 11

Multimedia Development



Topics you will explore include:

- Development Team
 - Project Manager
 - Project Designer
 - Content Experts
 - Writers
 - Media Specialists
 - Programmers
 - Acquisitions Specialists
- Development Plan
 - Definition
 - Preliminary Proposal
 - Storyboard
 - Functional Specification
 - Design
 - Prototype
 - Production

Multimedia permeates all areas of modern communication and entertainment. From advertising and marketing to games, training, and education, multimedia is producing new products and transforming the creation of old ones. Print publications increasingly use the Web to distribute words and images, to add late-breaking developments, and to more fully engage their readers with audio and video. Television uses the tools of digital multimedia to produce traditional commercials and programming and to add new forms of interactivity using a wide variety of websites. Few educational publishers—and virtually no marketing campaigns—ignore the potential contributions of multimedia to their products.

This wide range of products gives rise to a variety of approaches to multimedia development. Print publishers, filmmakers, game producers, corporate trainers, and educators all approach their work differently. But all share common challenges and opportunities dictated by the nature of multimedia technology. As a result, multimedia developers share a common set of essential tasks and procedures. In this chapter, we explore the elements of multimedia development common to the production of the majority of advanced applications.

After completing this chapter you should understand:

- The skills and functions of the members of a typical multimedia development team: project manager, project designer, content experts, writers, media specialists, programmers, acquisitions specialists
- The three stages of a multimedia development plan: definition, design, and production
- The objectives and products of each stage: preliminary proposal, storyboard, functional specification; media creation, interface design, prototype; alpha version, beta version, gold master

11.1 The Development Team

Effective multimedia is developed by small groups and even by individuals, but successful commercial products are the result of teams of professionals following a carefully planned development process. A team is important for two reasons. First, different specialists are needed to produce high-quality media. A person skilled in graphics, for example, is seldom equally skilled in sound. Second, a multimedia project is usually shaped, and reshaped, by the interactions of team members. Multimedia development is both *interactive* and *iterative*. It is **interactive** in the sense that team members often contribute to the development of components outside their immediate area of expertise. It is **iterative** in that further product development and testing often leads to changes to earlier work. The best products are the result of a creative team dynamic that fosters the sharing of ideas and a willingness to revise.

Multimedia development also requires leadership and planning. The same qualities that can lead to exceptional results can also spell disaster without effective coordination and direction. Enthusiastic team members can easily expand content and features well beyond the practical limits of budgets and delivery schedules. To keep the efforts of the team on track, a systematic development plan, with clearly articulated steps and outcomes, is also essential.

No one team and no particular set of steps is used for all multimedia development. Teams, and the organization of the work they do, vary by industry and even by project. The teams that create multimedia products relating to film often include producers and directors. Projects originating in the computer industry may include project managers and software engineers. One project may employ several video specialists while another makes no use of that medium at all. But nearly all development projects must tap certain types of expertise and complete a common set of major tasks. Understanding these tasks, and the contributions of different specialists, is essential for all members of the multimedia team, even for the ambitious “team” of one.

11.2 Team Members

Among the essential members of a multimedia team are the *project manager*, the *project designer*, *content experts*, *writers*, *media specialists*, *programmers*, and *acquisitions specialists*.

Project Manager

Commercial multimedia productions are complex and expensive. Projects often take many months to complete and companies take significant economic risks funding their development. The **project manager** is the person with ultimate responsibility for ensuring that the product is delivered with the promised features, on time, and on budget. The project manager oversees the business aspects of multimedia development.

The work of the project manager includes:

- Contract negotiations with the client
- Hiring and evaluation of team members
- Creating and monitoring a production schedule
- Budgeting
- Monitoring client review and approval
- Coordinating testing and revision
- Ensuring product delivery
- Overseeing product documentation and the archiving of project materials

Successful project managers have an understanding of the multimedia market and current technologies. They are well organized, focused, and task oriented.

Project Designer

The **project designer** is responsible for the overall structure of the product’s content and for the look, feel, and functionality of the user interface. The designer must understand the ways in which each of the media can most effectively convey project content. Above all, the designer must understand what is new in “new media.” This includes a thorough understanding of the strengths and weaknesses of text, graphics, sound, animation, and video in a computer environment. The heart of new media, however, is interactivity. The designer must be aware of the potential to engage users in novel ways by shifting the focus from the project’s contents to the user’s interactions with that content. Depending on the project, interactions might include: navigation options; contextual help screens

and audio; customizing options such as setting difficulty levels; queries, challenges, or reinforcements tied to user performance; and immersive, virtual reality experiences.

One person may carry out project design but it may also be a shared responsibility. In some educational and training products, for instance, instructional designers are responsible for content structure while a graphics designer shapes the appearance of the interface. Instructional designers are trained to identify specific educational outcomes and strategies. They also have expertise in evaluating the results of educational products. Graphics designers are skilled in the principles governing the creation and effective use of graphic elements such as color, line, shape, and spatial organization.

The work of the project designer includes:

- Organizing information by topic and structuring content
- Establishing the look and feel of the product (formal, playful, etc.)
- Determining the metaphor for the user interface
- Creating the navigational structure
- Supervising the work of media specialists and writers

Content Experts

Content experts have a detailed understanding of the topic presented in the multimedia application. The need for content experts varies significantly with different applications. An application designed to assist diabetes patients with management of their disease requires very specific, current, and accurate information from a specialist. A basic business website may not require a content expert as a team member, though it will, of course, demand careful consultation with the business owner and/or employees.

The work of the content expert includes:

- Identifying facts, theories, procedures, processes, or other information to be presented
- Ensuring the accuracy of all product content
- Assisting in product testing and revision
- Identifying other specialized content experts as required

The content expert should have a thorough working knowledge of his or her specialty. This includes basic subject content as well as the latest research and sources of additional expertise. It is helpful if the expert also has an understanding of the essentials of multimedia technology and the ways in which it may be effectively applied to the presentation of the topic.

Writers

The development of a multimedia product requires a variety of written documents. **Writers** are the individuals responsible for producing these documents. In some cases, the product itself is focused on writing. Multimedia children's books, for instance, have specific stories as their focus. Here, the writer is at the very heart of the project and his or her creativity is central to its success. In applications that are not centered on a written text, such as retail marketing sites or action games, writing still plays an essential role.

In these and other projects, writers may be called on to produce various documents:

- A product proposal for a potential client
- A detailed product specification
- Scripts for dialogue and action to guide animators, actors, or programmers
- Bug and testing reports
- Release notes and manuals
- Help screens

Writing is often the responsibility of more than one person, particularly when the project calls for creative as well as technical writing. Multimedia writers benefit from a knowledge of the development process. They also need an understanding of the specific limitations and possibilities of the written word in multimedia applications.

Media Specialists: Graphics, Sound, Animation, and Video

Media specialists are responsible for the preparation of the individual elements in a multimedia application. As members of the team, they also interact with others, sharing ideas for product features both within and beyond their specialties.

Graphics Graphics are an important component of nearly every multimedia product. Graphics capture the eye and the attention of the user, they establish a product's mood, they convey information, and they are critical guides for effective navigation and user interactions. Multimedia graphics specialists are artists skilled in design principles and in the most current digital technology. They understand the principles of color, line, and image composition as well as the workings of draw, paint, and illustration software.

The graphics specialist is a required member of most multimedia production teams. He or she may be called on to perform a variety of tasks:

- Choose the graphics software used to create the product
- Design screen layouts
- Select stock graphics from clip art, photo houses, and other sources
- Edit existing graphics
- Perform conversions between different graphics file formats
- Produce original artwork such as logos, drawings, and buttons
- Ensure consistent graphics display across different computer platforms

Sound Producing high-quality sound requires both expertise and specialized equipment. The sound specialist for a multimedia project is trained in traditional sound production and has a thorough working knowledge of the sound studio. He or she is also familiar with the latest digital tools for creating and editing sounds of all types from narrations, to music, to sound effects. As part of the multimedia team, this person must also understand both the limits and potential of sound delivered via computer. The sound professional will be the best judge of the most effective strategies for ensuring high-quality sound within the limitations of the delivery options available. As an important contributor to the development process, he or she also often affects design decisions by suggesting ways in

The acquisitions specialist typically will manage all aspects of permissions for a project:

- Research availability and costs of copyright permissions for projected content
- Complete copyright agreements for selected content
- Maintain documentation of copyright permissions
- Write copyright agreements between team members and the developer
- Write copyright agreements between the client and the developer

11.3 The Development Plan

Like most creative undertakings, multimedia development is a balancing act. The flow of ideas between team members determines the form and even “personality” of the product but it often leads to a “blue-sky” profusion of features that must be balanced against the need to produce a marketable product on time and on budget. The development plan is both tightrope and safety net—it must stimulate the creative energies of the team while also clearly defining the product and the steps that will lead to its successful completion.

Development plans take many different forms but each must address three essential tasks: *definition*, *design*, and *production*. Progress markers, sometimes referred to as *rewards*, are identified for each stage. Often the rewards are *deliverables*, documents or elements of the application that are delivered to the client as the product takes shape. Payment schedules are often tied to deliverables. Each stage depends on its predecessors but the results of previous stages are often modified as a result of later work. Obstacles to preparing or licensing a particular video segment, for example, may result in a redefinition of the product. As noted previously, multimedia development is usually *iterative*—earlier stages are reshaped or reformulated as development progresses.

Stage 1: Definition

Something must justify the time, energy, and other resources demanded by multimedia development. The most important question in the development process is: “What is the purpose of the product?” The second most important is: “Why should we use multimedia to achieve it?”

The product’s purpose is defined through its goal or goals. A product goal is not simply a description of its features. “Produce a web-based music store with recording samples, critics’ reviews, and videos of the latest concerts” is not a goal. “Increase sales of *Rolling Stones* CDs to female purchasers aged 20 to 32 by at least 20%” is a goal. The product goal clearly states what the application should accomplish.

Identifying the goal also involves identifying the audience. Who are the intended users? What are their ages, genders, classes, and nationalities? What types of computing devices and networks do they use? Both content and the way in which it is presented need to be tailored to the user.

With goal and audience in mind, another set of questions is posed about the application itself. What are the advantages of multimedia for accomplishing the goal? What media elements will it require? What forms of interactivity will be provided? How will it be delivered? Will it need to be regularly updated? What are the rough costs of development?

Product definition then proceeds in stages based on the results of increasingly specific formulations. There are often three key documents in this process: *preliminary proposal*, *storyboard*, and *functional specification*.

Preliminary Proposal The **preliminary proposal** is a short one- to three-page description of the proposed application. It is used to begin the process of developer–client negotiations. The proposal lays out the plan for the project:

- Identifies the goal
- Specifies the need and the audience
- Outlines projected outcomes and benefits
- Briefly describes projected media content
- Describes types and uses of interactivity
- Provides a preliminary cost estimate

The preliminary proposal often includes a flowchart. A **flowchart** is a simple box diagram with brief descriptions of product contents. Lines or arrows are often used to connect these boxes to identify navigational paths. The flowchart is a broad overview, sketch, or outline of the product. Figure 11.1 shows a sample flowchart for an application created by the authors.

Storyboard The product is further defined through the storyboard. A **storyboard** is a series of sketches of major screens. Rough drawings of media elements such as photos, animations, or videos are sketched in. Buttons and other navigational objects such as pull-down menus are also sketched and their functions are briefly described (Figure 11.2). Storyboards may be produced with pencil and pen, on paper or white boards, or with a computer. General-purpose presentation programs such as PowerPoint are often used for storyboarding. More powerful authoring applications are often appropriate for




Figure 11.1 A flowchart—main application elements identified (Exploring “Fra Lippo Lippi”).




Figure 11.2 A storyboard—screen content and basic functions sketched (Exploring “Fra Lippo Lippi”).

storyboarding as well. These have the advantage of allowing developers to readily add more advanced features to the storyboard as they further define the product.

Storyboards are very helpful in communications with clients during product definition. They make it possible to easily visualize ideas for content and features. This allows developers to test their proposed creations with clients before committing time and other resources. Storyboards also continue to be important during later stages because they make it easier to communicate project goals and requirements to all members of the development team.

Functional Specification The **functional specification** is a detailed description of the elements and the performance of the multimedia product. What media components—drawings, photos, sound segments, animation or video sequences—will be created? What types of user interactions—navigation options, queries, suggestions, reinforcements, on-line ordering—will be supported?

The functional specification is often the basis of a detailed business contract. Such contracts are critical to the success of the development process. The novelty and potential complexity of multimedia products provide fertile ground for misunderstanding and disappointment. Costs and delivery schedules can easily get out of hand as additions and changes are made to the project. Both the developer and the client must understand exactly what has been promised and the procedures to be followed if either party wishes to change the specifications.

Stage 2: Design

The definition stage specifies what the product is to be. The objective of the *design phase* is the creation of an incomplete working model of the product called a **prototype**.

During product design, the first media elements are created, the interface is designed, and these elements are combined to create the prototype.

Media Creation Media creation involves several tasks. The first is identifying required media. A detailed listing, called a **content inventory list**, is developed. This document lists each media element or “asset,” the party responsible for its creation, and whether or not it has been completed.

The content inventory list is important because it serves as an early reality check. Can the required media be produced in a timely and cost-effective manner? This list will be further refined as the design process continues and media elements are modified, eliminated, or added to the product. It will also guide the work of team members during the production phase of the project.

Other tasks in media creation include *preproduction*, *production*, and *postproduction*. **Preproduction** is the process of preparing media for editing—scanning photos or other graphics, digitizing an analog sound or video source, or performing file conversions. In the **production** phase, the asset is edited using the software that has been selected for that medium (Photoshop, Sound Forge, Final Cut, etc.). In **postproduction**, media is edited using other software to achieve desired effects. Adobe After Effects, for example, is often used to add animated text and special effects, such as sparkles, smoke, or fire, to video.

Interface Design The **user interface** is the content of the application as the user experiences it on screen. This includes the presentation of media elements and the resources—buttons, menus, hints, specialized controls—that allow the user to interact with the application. In the design stage this interface is carefully specified.

The goal of interface design is to engage the user. In linear, noninteractive products, such as a simple information kiosk, this may simply mean holding the user’s interest and attention. In fully developed interactive applications such as games or tutorials, the interface may need to anticipate choices, provide hints or reinforcements, or present new interactions based on previous user responses. Whatever the application, the user interface must present media elements and user interactions in a way that supports the product’s goals and matches the expectations and abilities of its audience. Figure 11.3 presents one element of an interface design.

The user interface should establish an appropriate tone. The tone of the application is determined by the style of its media elements and controls. Virtually any tone may be created—playful, humorous, casual, formal, dignified, serious, businesslike, and so on. Cartoon-like images, bright primary colors, and large animated buttons help to set a playful and welcoming tone for a children’s animated story. Sounds, fonts, and video clips would similarly be chosen to appeal to children and support the entertainment or educational goals of the product.



Figure 11.3 Interface design. Exploring “Fra Lippo Lippi” uses an interactive progress indicator to locate the reader’s position in the poem. Grayed sections indicate progress through the poem. Clicking on a line number jumps the user to that section.

Discovering problems or limitations in this stage can avoid client dissatisfaction and save many hours of development time.

Once the prototype is reviewed and tested, it also serves as an important resource in the next phase of the multimedia project. Team members use the prototype to guide their individual work on the production of the media and software routines needed to complete the product.

Stage 3: Production

In the production stage, all remaining elements of the product are created and integrated into the application (Figure 11.5). Content, media, and acquisitions specialists continue the work of identifying, securing, creating, and editing media elements. Programmers complete needed software routines and integrate media with the user interface. In many projects, designers continue to refine the interface itself. This is particularly true in highly interactive and imaginative applications such as games, which are often significantly redesigned, or “tweaked,” during the production stage.

Production also includes regular quality assurance testing, complete with bug reports and documentation of corrective measures. Prerelease versions of the product are often created to facilitate both in-house and external testing. An **alpha** version includes most of the media elements but many bugs. As bugs are identified and corrected and the remaining media elements added, a **beta** version is created. The beta version includes all media but is not yet free of all bugs. Successive revisions of beta eventually produce the complete, bug-free application, ready for distribution. This is sometimes called the “gold master.” Production also includes the completion of several other tasks essential




Figure 11.5 A production screen—all media and functions complete (Exploring “Fra Lippo Lippi”). See Color Plate 28.

to product delivery and distribution such as the preparation of release notes, manuals, and packaging.

Finally, many multimedia developers stress the importance of *systematic archiving* of project materials as the development process is completed. Archiving is important for several reasons: disputes may arise among the various parties in the development process, the project may need to be revised or updated in the future, or materials for which the developer has retained copyright may be needed for future products.

11.4 Summary

Advanced multimedia development is a team effort that is guided by a development plan. The composition of development teams and the steps they follow vary according to industry and project. Most multimedia development teams include a project manager, a project designer, content experts, writers, media specialists, programmers, and acquisitions specialists.

The development plan is centered on three major stages: product definition, design, and production. The preliminary proposal, flowchart, and storyboard lead to a functional specification defining the product. This stage often concludes with the writing of a business contract specifying the legally binding agreements between client and developer. In the design phase, an incomplete working model of the product called a prototype is built. The prototype includes some completed media elements and most of the functionality of the proposed product. The prototype is used to test and refine the design. Testing of the prototype may lead to revisions to the proposed product and to adjustments in projected development schedules and costs.

The prototype is also used to guide the further development of the product in the production phase. Production completes media development and the programming of all product functions. This phase is often marked by preliminary releases of the product called alpha and beta versions. Frequent testing is done, bugs are identified and corrected, and the final product is created. The production phase concludes with the creation of supporting documentation such as manuals and release notes, the preparation of packaging for product distribution, and the systematic archiving of project materials.

Key Terms

Acquisitions specialist

Alpha

Beta

Content experts

Content inventory list

Development plan

Flowchart

Functional specification

Interactive

Intuitive interface

Iterative

Media specialists

Metaphor

Postproduction

Preliminary proposal

Preproduction

Production

Programmer

Project designer

Project manager

Prototype


Storyboard

User interface

Writer

■ ■ ■ Chapter 12

Professional Issues in Multimedia Development



Topics you will explore include:

- The Definition of a Profession
- Codes of Professional Ethics
- Copyright
 - Traditional Rights
 - Digital Challenges
- Digital Rights Management

Professional Responsibility and Codes of Ethics

A professional code of ethics is a statement of obligations. These obligations are directed to individuals, to laws, to society, and to the profession itself. A **code of ethics** is a statement of the standards and obligations that define a practitioner's professional responsibilities.

As an emerging profession, multimedia development is not yet guided by a common set of professional standards. To get a sense of the shape of a possible code of ethics for multimedia developers, consider the Software Engineering Code of Ethics and Professional Practice jointly developed by the Association for Computing Machinery (ACM) and the Institute for Electrical and Electronics Engineers (IEEE). This code relates quite directly to the work of a multimedia programmer and offers guidance to other members of a development team as well.

The Software Engineering Code of Ethics The code is organized as eight principles with a set of specific obligations for each. The principles are major obligations: general courses of action that software professionals should undertake. The specific obligations for each principle identify the ways in which they are fulfilled in the course of a professional's daily work. Although the principles sometimes overlap, in general they suggest that professionals have obligations in several different areas—to society at large, to the laws that govern their practice, to clients and employers, to colleagues and subordinates, and to the profession itself. The following summary identifies the principles and highlights a number of obligations in the ACM/IEEE code that are relevant to the work of multimedia developers. For the complete code, see Appendix C.

1. **The "Public" Principle:** *"Software engineers shall act consistently with the public interest."*

Professionals are obligated to consider the broader, public consequences of their work. The code specifically notes the need to develop and approve software that is "safe, meets specifications, passes appropriate tests, and does not diminish quality of life, diminish privacy or harm the environment." They are also expected to consider the ways in which physical disabilities, economic disadvantage, and other factors might limit access to the software they develop. Finally, the code contends that professionals should also serve the public interest by volunteering their professional skills to public causes.

Each of these injunctions has a more or less obvious application to the work of multimedia developers. They, too, need to consider the ways in which their products impact society as a whole, whether they function properly, are safe, and are accessible to disadvantaged segments of the population.

2. **The "Client and Employer" Principle:** *"Software engineers shall act in a manner that is in the best interests of their client and employer, consistent with the public interest."*

In addition to their public responsibilities, professionals have specific obligations to their clients and employers. For instance, the code requires them to

- work within their areas of competence and honestly acknowledge limitations of experience or education,
- use the property of clients or employers only as authorized and appropriate,

- design, test, develop, and maintain high-quality, reliable software;
- provide accurate, clear documentation; and
- understand the environment in which their products are used.

The importance of this principle to multimedia development would be difficult to overstate. Multimedia is directly affected by the continual evolution of digital technology and by the rapid development of new products and services. Maintaining currency with recent developments in their respective fields is critical to the work of all multimedia professionals.

The ACM/IEEE code effectively suggests a wide range of guidelines for the professional practice of software engineering. Many of these also apply to professional multimedia development. The need for ethical guidance is often felt most strongly in areas in which the profession encounters novel challenges to well-established understandings and practices. In medicine, for instance, the development of advanced technologies to sustain life led to a range of challenging questions about the rights of patients and the responsibilities of physicians. New practices, procedures, and legal instruments, such as living wills, were developed in the context of a broad public discussion with economic, political, religious, and ethical components. Multimedia developers similarly must respond to significant changes and challenges. Today, the creation and protection of intellectual property, especially the many forms of creative expression covered by copyright, produce important challenges for multimedia developers.

Copyright is embodied in laws. Those laws create both important protections and equally important restrictions for multimedia development. No multimedia professional can function effectively without a basic understanding of copyright. Knowledge of copyright thus clearly falls under the professional injunction that developers know and follow the laws governing their work; but a multimedia professional's relationship to copyright goes beyond this simple injunction. Copyright is currently a focal point in a major contest between different cultural interests and values, and multimedia developers are in the middle of the fray. The practices that they develop and follow, as well as the technologies and products they help to create, will affect, and be affected by, a continuing copyright debate. To understand the professional issues raised by copyright, multimedia developers must first consider its traditional formulation and the specific protections it affords to content creators.

12.2 The Copyright Tradition: Rights, Remedies, and Exceptions

One reason that understanding copyright is important to multimedia developers is to guard against intentional or unintentional violations of the rights of others. The relative ease of digital editing, copying, storage, and transmission greatly increases the potential for copyright infringement by any member of a development team. In addition, the wide range of media that may be included in multimedia products often requires copyright permission from many different individuals or organizations. Another reason to become familiar with copyright is that developers need to protect their own work by retaining rights to elements such as interface designs that may be useful on other projects. This in turn requires that developers understand how to organize and define the work of their

teams and consultants. Developers may also need to frame agreements with their clients to specify copyright ownership for specific elements in a multimedia product. Each of these activities requires an understanding of what copyright is, the protections it affords, and how it is enforced.

Copyright Defined

Copyright is a form of legal protection given to creators of “original works of authorship.” The primary purpose of copyright protection is cultural advancement—people are more likely to undertake creative work if they can enjoy the economic benefits of their efforts.

Copyright differs from another common protection of creative effort, *patents*. Copyright applies to original or creative *expression*, but not to the facts, processes, theories, or ideas that are expressed. The “Better Mousetrap” is not protected by copyright, but the words used to describe it in trade publications and advertisements are. Patents, on the other hand, do protect mousetraps and other inventions. A **patent** is a grant of rights to the creator of an original, useful invention. The holder of a patent is given an exclusive right to make, use, and sell their invention for a certain period of time.

U.S. copyright law protects virtually any form of original expression—literature, music, drama, pantomimes, choreography, pictures, graphics, sculptures, motion pictures, sound recordings, architecture, and so on. The only requirement is that the expression be in a **fixed form**, a form in which it can be preserved and from which it can subsequently be “perceived, reproduced or otherwise communicated” (U.S. Copyright Office 2007, 2). A dance routine performed on a street corner is not protected unless it is also in a fixed form, perhaps as a set of notations on a page, or as a video recording. But once it is fixed, original expression is automatically protected. The work does not need to be registered and, since 1989, no notice of copyright needs to be given. Computer programs are treated as literary works and are also covered by copyright, although there is much discussion of the advisability of treating them instead as inventions subject to the protections of patents. For the multimedia developer, this broad understanding of “works of original authorship” combined with the automatic coverage of works in fixed form means that virtually any content created by another party is potentially covered by copyright.

Copyright Protections The owner of a copyright has five major rights:

- To reproduce the copyrighted work
- To produce derivative works (for instance, a film version of a novel)
- To distribute copies to the public (by sale, rental, lease, or lending)
- To perform the work publicly
- To display the work publicly

The creator retains these rights unless they are specifically transferred to another party. For instance, the purchaser of a painting does not own the right to reproduce it as a postcard unless the right to produce derivative works has been transferred to the new owner. Agreements with content providers should specify the rights being transferred. Similarly, client contracts should specify the rights to any multimedia content, such as screen designs, that the developer wishes to retain.

resources are likely to be regarded as **works for hire**. In these cases, an employer may own the copyright for works created by an employee. As in determining fair use, however, there are many ambiguities and uncertainties involved in identifying works for hire. Developers and their employees will be well served by explicit, written agreements detailing copyright ownership for the content workers produce.

Copyright laws seek to define and balance interests, rights, and obligations among individuals and between individuals and society at large. Fair use, for instance, seeks a balance between the property rights of individual creators and the interests of society in an open press and unfettered education. This balancing process has always been fluid and, at its borders, marked by uncertainty. Rather than being a set of specific directives etched in stone, copyright law is, instead, a set of general principles whose application to specific cases ranges from clear and definite to highly debatable and uncertain. For instance, how much of a work can a journalist quote in a book review?

A few properly cited sentences clearly seem to be allowed under fair use; the whole book clearly would not be. What about approximately 300 words from an unpublished manuscript of some 200,000 words? The answer depends on the application of the criteria for fair use, and here even the courts themselves may disagree. In 1979, Harper & Row Publishers entered into an agreement with *Time* magazine that allowed *Time* to publish portions of President Gerald Ford's memoirs. The memoirs were soon to be released in book form by Harper & Row. Prior to *Time*'s publication, another magazine, *The Nation*, surreptitiously acquired a copy of Ford's manuscript and published an article that used approximately 300 words directly from that source. Following this "scoop" by *The Nation*, *Time* refused to make its final payment to Harper & Row, which then brought suit against *The Nation* for copyright infringement. A lower court originally found in favor of Harper & Row, but on appeal this decision was reversed: the appeals court ruled that *The Nation*'s publication of quotations from Ford's manuscript was a fair use. In 1985, the Supreme Court reversed the appeals court ruling, finding that *The Nation* had in fact infringed Harper & Row's copyright. In part, the court argued that the small portion of Ford's manuscript taken by *The Nation*, which dealt with his pardon of former President Nixon, was "essentially the heart of the book" and was therefore "qualitatively substantial" even though it was a tiny fraction of the original source (O'Connor 1985, IV).

As this case illustrates, uncertainties in the application of copyright law have long been a fact of life for publishers, journalists, and others. The development of digital media has complicated matters even more.

12.3 Copyright in the Age of Digital Media

The relative ease of copying, editing, and transmitting digital media poses serious challenges to traditional copyright protections. Copyright law developed in the age of analog media and the rights that it established were defensible largely because of the nature of the media itself. Paintings, books, photographs, music, and films, for instance, are much more difficult to copy and distribute in analog form. Few individuals had the resources to do so, and those organizations that chose to ignore copyright could be readily identified and prosecuted. Digital versions of these media, on the other hand,

certain ways specified in a contract. Such agreements, called **end user license agreements (EULAs)** are very common for software programs and they are becoming more common for digital content such as electronic books. Users who casually click through the “Agree” buttons on first use of an eBook may have, quite unknowingly, surrendered their traditional fair use privileges. DRM can be used to protect contract rights just as it can protect copyright.

Many applications of DRM have focused on defending the rights of content owners. In effect, this involves using digital technology to try to solve problems created by the digital revolution itself. If a computer can be programmed to readily copy a file, it can also be programmed to copy-protect that file or otherwise limit a user’s access. If copyrighted digital media is readily edited and transmitted, so, too, can digital techniques be used to permanently mark its original identity and track its subsequent uses.

The use of DRM to limit media piracy by controlling user copying and access is perhaps the most visible and controversial area of the technology. In fact, many popular accounts identify DRM exclusively with these controls, and some critics have quipped that DRM really stands for Digital *Restrictions* Management (Sullivan 2006). Copy and access restrictions to media have taken many forms and have often generated both consumer dissatisfaction and persistent efforts to defeat the DRM safeguards. For example:

- Adobe, the developer of the popular PDF format for text documents, also markets electronic books called *eBooks*; eBooks use a DRM-enabled form of PDF. Various controls can be set through Adobe DRM to limit copying, sharing, and reading of purchased or loaned texts. Libraries, for instance, can loan eBooks for a specified period of time. After the loan period expires, the eBooks become unreadable. Adobe’s rationale for including DRM was the need to protect the copyright interests of creators by forestalling mass duplication of digital copies. Critics have noted, however, that Adobe has published eBooks that are actually in the public domain. In these instances, DRM effectively blocks perfectly legal copying of the public domain content in the work (at least from a copyright point of view; a license agreement may legally prohibit this use) (Lessig 2004, 151). A Russian company, ElcomSoft, developed software they called the Advanced eBook Processor that allowed a user to convert eBooks into a DRM-free PDF format, thereby removing copy and access limitations. In 2001, one of ElcomSoft’s programmers, Russian citizen Dmitry Sklyarov, was arrested by the FBI in Las Vegas, Nevada, where he was attending a professional conference. Sklyarov was charged with distributing a product intended to circumvent electronic copyright protection measures. Though charges against him were ultimately dropped, Sklyarov spent several weeks in U.S. jails and was required to remain in the United States for several months as legal proceedings against ElcomSoft continued.
- A form of encryption, **Content Scrambling System (CSS)**, is used by the motion picture industry to protect DVDs from digital piracy. CSS scrambles the contents of a DVD, which can then be viewed only through a player licensed to use corresponding descrambling algorithms. This frustrated both legal (for instance, copying selected portions of a movie for discussion in film classes) and illegal uses of the medium. In addition, it was initially not possible to view DVDs on computers running the Linux operating system because licensed DVD players were not available for Linux. In 1999,

Jon Lech Johansen and unidentified associates developed a program commonly known as DeCSS that defeated CSS encryption, allowing direct access to the disc's digital video. Johansen was charged with violation of Norwegian economic crime laws. He was eventually acquitted and went on to develop and post software to circumvent Apple's DRM, FairPlay, for online music, becoming a controversial symbol of resistance to DRM control technology.

- Audio CDs initially had no copy protection. As technology for "ripping" CDs and transferring music to computers became commonplace, some music publishers turned to DRM to prevent widespread copying and redistribution. One such company was Sony BMG. In 2005, Sony began adding DRM to its music CDs to control playback on Windows PCs. Sony's CDs installed software to the PC, sometimes without a user's consent or knowledge. When Sony's DRM was found to interfere with the operation of some other programs and to open users' computers to potential security breaches, a series of legal challenges arose that included class action lawsuits and actions by individual states alleging violations of laws banning the deployment of "spyware." Sony's attempts to remove the software from affected machines exacerbated the problem when it was reported that their initial uninstall program did not remove the offending software and may have further compromised computer security. Sony ultimately recalled all CDs on which the DRM software (XCP/MediaMax) had been installed and offered refunds to consumers. Sony has since abandoned efforts to protect its CDs with DRM and, as of this writing, no other major distributor is using DRM on its audio CDs.
- DRM was applied to the sale of music on the Internet. Microsoft, for instance, embedded DRM in the Windows Media Audio (WMA) format used for playback of downloaded music on its Zune players and Windows PCs. Sony developed a proprietary format for its music, as did Apple for the music provided through its popular iTunes store. Apple's DRM format, known as FairPlay, limited users' ability to copy purchased music to five computers, though it could be copied to an unlimited number of iPods. In contrast to open standards such as advanced audio coding (AAC) or MP3, the proprietary formats of Microsoft, Sony, Apple, and others are not interoperable: music files that play on one device generally do not play on others. This generated consumer dissatisfaction, spawned attempts to crack the DRM, and encouraged other vendors, such as eMusic, to provide music in an open format. In response, several Internet music providers, including Apple, eventually discontinued the use of DRM.

The application of DRM copy/access controls to digital media, as these examples suggest, has often produced unhappy consumers. Such restrictions sometimes interfere with legitimate uses of media and, worse, may degrade the performance of the user's playback device. It has been estimated that the presence of DRM controls creates processing overhead that "can cut the battery life of MP3 players by 25 percent" (Center for Democracy and Technology 2006, 20). Even in the absence of these effects, such restrictions frustrate the expectation of flexibility in copying, editing, and remixing media that have become hallmarks of the digital revolution. People realize that such flexibility in all forms of digital media is possible and they resent and resist restrictions on these freedoms.

On the other hand, digital "freedoms" clearly do not imply a right to freely appropriate copyrighted media. As copyright owners continue to press for effective ways to protect

their property, they face a fundamental challenge: it is extremely difficult to develop and maintain a system of DRM that is free from attack by determined “crackers.” As Apple’s former CEO, Steve Jobs, commented in an open letter on the subject, “there are many smart people in the world, some with a lot of time on their hands, who love to discover [DRM] secrets and publish a way for everyone to get free (and stolen) music” (Jobs 2007). These challenges spurred another attempt to defend traditional copyright protections, the Digital Millennium Copyright Act.

The Digital Millennium Copyright Act

The **Digital Millennium Copyright Act (DMCA)** is an extension to U.S. copyright law enacted in 1998. The act responded to rights holders’ concerns about media piracy and also implemented provisions of the 1996 World Intellectual Property Organization (WIPO) treaty that required revisions in the copyright laws of signatory nations, including the United States. The DMCA contains a number of provisions that directly affect the work of digital media professionals: it clarified the permitted copying of digital media by libraries, archives, and educational institutions; it limited the liability of Internet service providers (ISPs) for copyright infringement by those who use their services; it criminalized the circumvention of DRM control measures even if no other violation of copyright protections occurred; and it outlawed the creation and distribution of any “technology, service or device” intended to circumvent a “technological measure that effectively controls access to a work protected by [copyright]” even if such devices were not actually used to violate copyright (U.S. Copyright Office 2007, 237).

The DMCA is controversial. In fact, the act is a virtual case study in the clash of traditional interests, rights, and legislation with the challenges posed by a revolutionary technology. Stakeholders in media, such as the software, entertainment, and publishing industries, have welcomed the law, while many librarians, researchers, and public advocacy groups have opposed it (UCLA Online Institute for Cyberspace Law and Policy 2001). The various provisions of the DMCA raise practical issues of direct concern to multimedia developers in their daily work as well as professionally significant social and legal issues. Among these are the following:

- *Potential Abuse of Copyright Claims:* ISPs have a strong incentive to immediately remove media from websites they host as soon as a copyright holder notifies them of an alleged violation. This is because their exemption from liability for copyright infringement under the provisions of the DMCA depends on acting “expeditiously to remove, or disable access to” the offending material as soon as they are notified of a copyright infraction (U.S. Copyright Office 2007, 155). The notification process is usually simple and no independent determination of the legitimacy of the claim is required for the ISP to take action. This provides media creators and other owners of copyright with a straightforward, practical way to respond to violations of their rights. On the other hand, a website may be disabled simply because an infraction of copyright has been alleged, whether the allegation is true or not. Although the act also provides for a counter-notification denying that the media is being displayed in violation of copyright, many ISPs will follow the safer course of removing disputed material.

This opens the door to frivolous or malicious attacks on websites and other multimedia applications where no copyright violation has actually occurred.

- *Fair Use:* The framers of the DMCA were concerned with balancing copyright protections with the exemptions embodied in fair use. They explicitly indicated that nothing in the act was to affect “limitations, or defenses to copyright infringement, including fair use” (U.S. Copyright Office 2007, 238). However, many critics have alleged that the law undermines legitimate fair uses of media by essentially allowing copyright holders to place an unbreakable lock on their content. Under the DMCA, it is illegal to circumvent an electronic protection. Thus, media that otherwise could be copied for such fair use purposes as research, criticism, or news reporting, could be rendered inaccessible through DRM. In anticipation of this problem, the act also defined a process for granting exemptions from the circumvention prohibition. An exemption made in 2006, for instance, permitted educational libraries and media studies departments to circumvent DRM protections of audiovisual works for educational purposes. Critics note, however, that such specific exemptions fail to address other potentially fair uses of content that has been protected by DRM. Fair use has always been an ambiguous area of the law and its practical meaning has been determined by court decisions. DRM, enforced through the DMCA, may effectively curtail this process of testing and revising understandings of acceptable uses because it precludes the presumptive fair use in the first place. For instance, a music critic could not make a potential fair use of a small portion of a DRM-protected song without violating the DMCA. Thus, legitimate challenges to fair use restrictions may never make it to court. In *Free Culture*, Lawrence Lessig argued that this amounts to substituting computer code and the “judgment” of a machine for law and the reasoned analysis of a judge (Lessig 2004, 148, 152). Further, he pointed out that DRM software, created under the direction of media companies, may regulate users, and limit their creativity, in ways that have nothing to do with copyright at all. He notes, for instance, limitations on the use of eBooks by Adobe, including denying permission to copy, lend, or give away works that are actually in the public domain (Lessig 2004, 148–153).
- *Research:* The DMCA prohibits circumventions of the electronic protection measures designed to prevent violations of copyright. Thus it is illegal to disable such protections even if no illegal use is actually made of the media they protect. While the law does provide exemptions to this prohibition for research purposes, critics have argued that those exemptions are so narrowly defined that they hamper both research and freedom of expression. The arrest of Dmitry Sklyarov and the prosecution of ElcomSoft, discussed previously, are often cited as instances of the chilling effects of the DMCA on research. In a number of other cases, faculty and students have been threatened with prosecution under DMCA for publicizing the results of their research on DRM. At least one textbook suffered a delay in publication because of fear of prosecution under the DMCA (Electronic Frontier Foundation 2006).
- *Creative Expression:* As we have seen throughout our study of modern multimedia, the digital computer has transformed the conditions of creating and using media. Easily learned media-specific software enables individuals to readily express themselves through text, sound, images, videos, and animations. Authoring software makes it possible for nearly anyone to combine media and add various forms of interactivity.

receives it is also free to sell it, effectively eliminating any monopoly control. Second, OSI products provide access to the program code (or *source code*) thus making it possible for others to modify the application. Finally, an OSI license must allow others to create derivative works, that is, other software based on the original code. These new products, in turn, must also be subject to free redistribution. OSI licenses differ radically from common commercial practice, which typically provides a license for individual use only, with no rights to modify or redistribute the software. By contrast, open source multimedia applications such as Gimp, Audacity, and Blender are free to download and use. Upgrades to the software are generated through fellow programmers and redistributed for free. The OSI community of programmers is dedicated to developing robust software and sharing it with a wide community of users. See <http://opensource.org> for additional information.

These two programs, one to support reuse of digital media, the other to foster community development and use of freely redistributed applications, address some of the challenges of digital ownership in a networked society where bits travel fast and free. In the spirit of second-generation DRM, Creative Commons Licensing and Open Source Initiative programs offer new models to publish, share, and promote digital content while at the same time respecting creative authorship.

Given the character of digital media and the capabilities of computers, the expansion of digital rights management is nearly inevitable. Keeping up with the transformations in the definition, uses, and protection of copyrighted media will remain an important professional concern for multimedia developers for some time to come. The various ways in which developers interact with the issues of copyright also illustrate key elements of professional responsibility. For instance, the “self principle” of the ACM/IEEE code implies the need for professionals to stay informed of changes in copyright law and practice. The “colleagues principle,” to be “fair to and supportive of,” colleagues suggests the importance of clearly defining copyright ownership for work produced in the course of a project. The “Product” and “Management” principles both suggest the need to seek and properly document copyright permissions. Finally, developers’ obligations to the profession and to the public imply a professional responsibility to increase awareness of copyright issues affecting not only the practice of multimedia development but also society at large.

12.5 Conclusion

This chapter examined the meaning of professional responsibility and explored a specific issue, copyright, that is central to the work of virtually all multimedia developers. But the range of potential professional issues extends far beyond copyright. One clear indication of the importance of considering these issues is the attention given to multimedia development by *other* professionals, individuals who, in the course of exercising their own professional responsibilities, have directed their attention to multimedia products.

As noted at the beginning of the chapter, one way of highlighting the need to consider professional issues in multimedia development is the public controversy surrounding video games. In the United States, both the American Psychological Association and

the American Medical Association have issued reports on the behavioral and health implications of video games. Psychologists and physicians have raised concerns about a variety of health effects. These include specific physical symptoms such as epileptic seizures and “musculoskeletal disorders of the upper extremities and increased metabolic rate” (Kahn 2007, 3). More frequently, however, the concerns focus on possible psychosocial and behavioral effects including video game overuse or addiction, social isolation, and increased violence and aggression. Parents, religious leaders, and legislators have raised similar issues. The development of a rating system for video games was one effect of these widespread public concerns.

On the other hand, professionals and others have often noted the potential benefits of video games. In addition to their role in providing entertainment and diversion, games have been lauded for a range of other benefits. They have been used for military training, health education, and the treatment of phobias. One study found a positive effect of game playing on the development of surgeon’s skills (Dobnik 2004); other studies have noted the social engagement and bonding provided by multiplayer online games (Taylor 2006). Some have argued that playing violent games actually has the positive effect of releasing tension and aggressive emotions. And many educators are convinced that the immersive, interactive characteristics of video games hold great promise for learning (Gee 2007; Glazer 2006).

The video game controversy, like the issues surrounding copyright, will be with us for some time; advocates and detractors alike insist on the need for further long-term experience and study. Whatever the outcome of debates such as these, one thing is clear: the revolutionary technologies of modern multimedia will continue to generate significant social effects and widespread public interest. It is important that the voices of those who are creating multimedia products be a part of the discussion. As participants in an emerging profession, developers must define the codes of professional responsibility that lend authority to their voices. Professional values begin with individual competence and integrity; widen to supportive, respectful relationships with colleagues; then widen further to include obligations to the profession itself and to the well-being of society as a whole. The early pioneers of multimedia envisioned a world made better through a remarkable technology. Modern multimedia developers now wield creative tools that their predecessors could only imagine.

What kind of a world will they build?

Key Terms

Analog hole	Fair use
Code of ethics	Fixed form
Content Scrambling System (CSS)	Open Source Initiative
Copyright	Patent
Creative Commons	Profession
Digital Millennium Copyright Act (DMCA)	Public domain
Digital rights management (DRM)	Remedies
Digital watermark	Works for hire
End user license agreement (EULA)	

10. Research and report the purpose of Creative Commons (<http://creativecommons.org/>). Do you think the Creative Commons licensing program is a solution to any of the problems that critics identify with DRM?
11. Adobe Photoshop provides a means to digitally watermark your image creations. Research and report other software applications that offer the same watermarking capability.
12. If you digitally watermark the home video you created in question 6 to showcase your snowboarding skills, what benefits might you receive once the video is posted on YouTube?
13. Some would argue that the age of copy protection for intellectual property is over. Copyright in the digital age can't be enforced, lacks strength, isn't respected internationally, and restricts creativity. As a multimedia developer and creative artist, take a position on the status of copyright law in the digital age.
14. Research and develop a position on a social issue that you think multimedia developers will need to address to secure the future of their work. Relate your position to the code of ethics presented in this chapter and Appendix C and to current developments in multimedia applications.

The Scanning Process



Scanning typically involves six major steps: selecting the part of the image to be scanned, setting color mode, setting spatial resolution, specifying output dimensions, making adjustments to image quality, and executing the scan.

Step 1: Selecting the Image Area

Scanning software includes a preview mode in which the scanner makes a rapid pass over the image and creates a low-resolution preview. Once the preview is on screen, the user outlines the area to be scanned by dragging a rectangle around it. This is the only part of the image that will be captured when the scan command is given.

Step 2: Select Color Mode

Color mode is the type of image to be produced. Typical options are line art or black and white bitmap, grayscale, and color. Selecting a color mode sets the color resolution of the image (the number of bits assigned to each pixel). Line art images use 1 bit; grayscale images use 8 bits. The bit depth available in color mode varies with the capability of the scanner (24, 30, 42, or 48 bit, for instance).

The flatbed scanner is the type most often used in multimedia production. These are similar to copy machines. Images or objects are placed on a glass surface. A light and scan head move beneath the glass and the reflected light produces the different voltages used to encode the image as a digital file. Flatbed scanners often include adapters to capture transparent media such as 35mm slides. Additional scanner software settings include:

- Exposure adjustments to reduce shadows or introduce highlights.
- Halftone patterns to apply to line art images. As in traditional printing, computers create line art images through different combinations of black and white

dots. Different image effects can be achieved with different patterns (fine dots, vertical lines, horizontal lines, diffused patterns, etc.).

- Descreening is an image adjustment that compensates for scans that pick up the linescreen pattern of a printed image. The interaction of the scanner and the original linescreen may produce a wavy or rippled effect sometimes called a *moiré pattern*.

Step 3: Set Spatial Resolution

Spatial resolution is the number of pixels that will be created for each square inch of the image (ppi). This is usually called *resolution* in scanning software.

In general, resolution should be set to match the intended output device. Images to be displayed on monitors might be set to 72 ppi, whereas a resolution of 300 ppi or more would be used for printing.

Step 4: Set Output Dimensions (Scaling)

Scanning software allows users to scale the output dimensions of images to produce either larger or smaller versions of the original. Scaling is important because an enlargement made at the time an image is scanned is usually better than one made after scanning. In effect, the scanner can do better enlargements because it has the original image at hand. Trying to enlarge the image after a scan will either spread the existing pixels or require *resampling*, a process in which the editing software interpolates values for new pixels. Either approach can significantly distort the image.

Step 5: Make Image Adjustments

A variety of image adjustments are usually available. These include position changes (rotate right, rotate left, mirror), sharpening, changing color ranges, adjusting exposure, setting different halftone patterns, and descreening. Sharpening accentuates divisions between different colors and helps to reduce the blurriness of scanned images. Use sharpening with care; too much sharpening distorts images. Changing color ranges allows users to shift the amounts of particular colors in the image. These shifts are sometimes used to correct defects in the original (for instance, a yellowed photo) or for artistic effect.

Step 6: The Scan

Once the selection, color mode, resolution, output dimensions, and adjustments have been determined, the image is ready to be scanned. Giving the scan command causes the scanner to make a much slower pass or, in some models, a series of passes over the selected area to create the higher-resolution final image.

This step often includes options for the destination of the final scan—scan to an open application, to a particular location on the hard drive, or to CD, for instance.

Scanning Tips

The following suggestions can improve the efficiency and effectiveness of scanning.

- Clean the glass. Dust produces speckles on scanned images.
- Use high-quality originals. Store originals carefully.
- Scan at the highest spatial resolution you will need (for instance, 300 ppi for printing). Bitmapped images can be reduced in size (*downsampled*) without loss of quality, but adding pixels (*upsampling*) will degrade the image.
- To produce a larger image than the original, scale during scanning. The scanner will do a better job enlarging an image than an image-editing program can do later.
- Avoid grayscale scanning of line art and printed grayscale images. The crisp edges of line art are often blurred by grayscale scanning. Printed grayscales, unlike black and white photos, are not contone images. They are actually halftones, made up of pure black and white dots. They, too, can be blurred in grayscale mode.
- Avoid enlargements of line art and printed grayscale images. Unlike a contone image, line art and printed grayscales do not have continuous areas of color to sample—enlarging increases the distances between individual lines and dots, degrading the image.
- Save and organize files of original image scans. These will contain the greatest amount of information for later editing.

■ ■ ■ Appendix C

Software Engineering Code of Ethics and Professional Practice



“This code may be republished without permission as long as it is not changed in any way and it carries the copyright notice.”

Software Engineering Code of Ethics and Professional Practice, copyright © 1999 by the Institute of Electrical and Electronics Engineers, Inc., and the Association for Computing Machinery, Inc.

<http://www.acm.org/about/se-code>

Short Version: Preamble

The short version of the code summarizes aspirations at a high level of abstraction. The clauses that are included in the full version give examples and details of how these aspirations change the way we act as software engineering professionals. Without the aspirations, the details can become legalistic and tedious; without the details, the aspirations can become high-sounding but empty; together, the aspirations and the details form a cohesive code.

Software engineers shall commit themselves to making the analysis, specification, design, development, testing, and maintenance of software a beneficial and respected profession. In accordance with their commitment to the health, safety, and welfare of the public, software engineers shall adhere to the following eight Principles:

1. Public. Software engineers shall act consistently with the public interest.
2. Client and employer. Software engineers shall act in a manner that is in the best interests of their client and employer, consistent with the public interest.
3. Product. Software engineers shall ensure that their products and related modifications meet the highest professional standards possible.

4. Judgment. Software engineers shall maintain integrity and independence in their professional judgment.
5. Management. Software engineering managers and leaders shall subscribe to and promote an ethical approach to the management of software development and maintenance.
6. Profession. Software engineers shall advance the integrity and reputation of the profession consistent with the public interest.
7. Colleagues. Software engineers shall be fair to and supportive of their colleagues.
8. Self. Software engineers shall participate in lifelong learning regarding the practice of their profession and shall promote an ethical approach to the practice of the profession.

Full Version: Preamble

Computers have a central and growing role in commerce, industry, government, medicine, education, entertainment, and society at large. Software engineers are those who contribute, by direct participation or by teaching, to the analysis, specification, design, development, certification, maintenance, and testing of software systems. Because of their roles in developing software systems, software engineers have significant opportunities to do good or cause harm, to enable others to do good or cause harm, or to influence others to do good or cause harm. To ensure, as much as possible, that their efforts will be used for good, software engineers must commit themselves to making software engineering a beneficial and respected profession. In accordance with that commitment, software engineers shall adhere to the following Code of Ethics and Professional Practice.

The Code contains eight Principles related to the behavior of and decisions made by professional software engineers, including practitioners, educators, managers, supervisors, and policy makers, as well as trainees and students of the profession. The Principles identify the ethically responsible relationships in which individuals, groups, and organizations participate and the primary obligations within these relationships. The Clauses of each Principle are illustrations of some of the obligations included in these relationships. These obligations are founded in the software engineer's humanity, in special care owed to people affected by the work of software engineers, and in the unique elements of the practice of software engineering. The Code prescribes these as obligations of anyone claiming to be or aspiring to be a software engineer.

It is not intended that the individual parts of the Code be used in isolation to justify errors of omission or commission. The list of Principles and Clauses is not exhaustive. The Clauses should not be read as separating the acceptable from the unacceptable in professional conduct in all practical situations. The Code is not a simple ethical algorithm that generates ethical decisions. In some situations, standards may be in tension with each other or with standards from other sources. These situations require the software engineer to use ethical judgment to act in a manner that is most consistent with the spirit of the Code of Ethics and Professional Practice, given the circumstances.

Ethical tensions can best be addressed by thoughtful consideration of fundamental principles, rather than blind reliance on detailed regulations. These Principles should

influence software engineers to consider broadly who is affected by their work; to examine if they and their colleagues are treating other human beings with due respect; to consider how the public, if reasonably well informed, would view their decisions; to analyze how the least empowered will be affected by their decisions; and to consider whether their acts would be judged worthy of the ideal professional working as a software engineer. In all these judgments concern for the health, safety and welfare of the public is primary; that is, the “Public Interest” is central to this Code.

The dynamic and demanding context of software engineering requires a code that is adaptable and relevant to new situations as they occur. However, even in this generality, the Code provides support for software engineers and managers of software engineers who need to take positive action in a specific case by documenting the ethical stance of the profession. The Code provides an ethical foundation to which individuals within teams and the team as a whole can appeal. The Code helps to define those actions that are ethically improper to request of a software engineer or teams of software engineers.

The Code is not simply for adjudicating the nature of questionable acts; it also has an important educational function. As this Code expresses the consensus of the profession on ethical issues, it is a means to educate both the public and aspiring professionals about the ethical obligations of all software engineers.

Principles

Principle 1: Public

Software engineers shall act consistently with the public interest. In particular, software engineers shall, as appropriate:

- 1.01. Accept full responsibility for their own work.
- 1.02. Moderate the interests of the software engineer, the employer, the client, and the users with the public good.
- 1.03. Approve software only if they have a well-founded belief that it is safe, meets specifications, passes appropriate tests, and does not diminish quality of life, diminish privacy, or harm the environment. The ultimate effect of the work should be to the public good.
- 1.04. Disclose to appropriate persons or authorities any actual or potential danger to the user, the public, or the environment, that they reasonably believe to be associated with software or related documents.
- 1.05. Cooperate in efforts to address matters of grave public concern caused by software, its installation, maintenance, support, or documentation.
- 1.06. Be fair and avoid deception in all statements, particularly public ones, concerning software or related documents, methods, and tools.
- 1.07. Consider issues of physical disabilities, allocation of resources, economic disadvantage, and other factors that can diminish access to the benefits of software.
- 1.08. Be encouraged to volunteer professional skills to good causes and to contribute to public education concerning the discipline.

Principle 2: Client and Employer

Software engineers shall act in a manner that is in the best interests of their client and employer, consistent with the public interest. In particular, software engineers shall, as appropriate:

- 2.01. Provide service in their areas of competence, being honest and forthright about any limitations of their experience and education.
- 2.02. Not knowingly use software that is obtained or retained either illegally or unethically.
- 2.03. Use the property of a client or employer only in ways properly authorized, and with the client's or employer's knowledge and consent.
- 2.04. Ensure that any document upon which they rely has been approved, when required, by someone authorized to approve it.
- 2.05. Keep private any confidential information gained in their professional work, where such confidentiality is consistent with the public interest and consistent with the law.
- 2.06. Identify, document, collect evidence, and report to the client or the employer promptly if, in their opinion, a project is likely to fail, to prove too expensive, to violate intellectual property law, or otherwise to be problematic.
- 2.07. Identify, document, and report significant issues of social concern, of which they are aware, in software or related documents, to the employer or the client.
- 2.08. Accept no outside work detrimental to the work they perform for their primary employer.
- 2.09. Promote no interest adverse to their employer or client, unless a higher ethical concern is being compromised; in that case, inform the employer or another appropriate authority of the ethical concern.

Principle 3: Product

Software engineers shall ensure that their products and related modifications meet the highest professional standards possible. In particular, software engineers shall, as appropriate:

- 3.01. Strive for high quality, acceptable cost, and a reasonable schedule, ensuring significant tradeoffs are clear to and accepted by the employer and the client, and are available for consideration by the user and the public.
- 3.02. Ensure proper and achievable goals and objectives for any project on which they work or propose.
- 3.03. Identify, define, and address ethical, economic, cultural, legal, and environmental issues related to work projects.
- 3.04. Ensure that they are qualified for any project on which they work or propose to work, by an appropriate combination of education, training, and experience.

Principle 5: Management

Software engineering managers and leaders shall subscribe to and promote an ethical approach to the management of software development and maintenance. In particular, those managing or leading software engineers shall, as appropriate:

- 5.01. Ensure good management for any project on which they work, including effective procedures for promotion of quality and reduction of risk.
- 5.02. Ensure that software engineers are informed of standards before being held to them.
- 5.03. Ensure that software engineers know the employer's policies and procedures for protecting passwords, files, and information that is confidential to the employer or confidential to others.
- 5.04. Assign work only after taking into account appropriate contributions of education and experience tempered with a desire to further that education and experience.
- 5.05. Ensure realistic quantitative estimates of cost, scheduling, personnel, quality, and outcomes on any project on which they work or propose to work, and provide an uncertainty assessment of these estimates.
- 5.06. Attract potential software engineers only by full and accurate description of the conditions of employment.
- 5.07. Offer fair and just remuneration.
- 5.08. Not unjustly prevent someone from taking a position for which that person is suitably qualified.
- 5.09. Ensure that there is a fair agreement concerning ownership of any software, processes, research, writing, or other intellectual property to which a software engineer has contributed.
- 5.10. Provide for due process in hearing charges of violation of an employer's policy or of this Code.
- 5.11. Not ask a software engineer to do anything inconsistent with this Code.
- 5.12. Not punish anyone for expressing ethical concerns about a project.

Principle 6: Profession

Software engineers shall advance the integrity and reputation of the profession consistent with the public interest. In particular, software engineers shall, as appropriate:

- 6.01. Help develop an organizational environment favorable to acting ethically.
- 6.02. Promote public knowledge of software engineering.
- 6.03. Extend software engineering knowledge by appropriate participation in professional organizations, meetings, and publications.
- 6.04. Support, as members of a profession, other software engineers striving to follow this Code.

- 6.05. Not promote their own interest at the expense of the profession, client, or employer.
- 6.06. Obey all laws governing their work, unless, in exceptional circumstances, such compliance is inconsistent with the public interest.
- 6.07. Be accurate in stating the characteristics of software on which they work, avoiding not only false claims but also claims that might reasonably be supposed to be speculative, vacuous, deceptive, misleading, or doubtful.
- 6.08. Take responsibility for detecting, correcting, and reporting errors in software and associated documents on which they work.
- 6.09. Ensure that clients, employers, and supervisors know of the software engineer's commitment to this Code of Ethics, and the subsequent ramifications of such commitment.
- 6.10. Avoid associations with businesses and organizations which are in conflict with this Code.
- 6.11. Recognize that violations of this Code are inconsistent with being a professional software engineer.
- 6.12. Express concerns to the people involved when significant violations of this Code are detected unless this is impossible, counterproductive, or dangerous.
- 6.13. Report significant violations of this Code to appropriate authorities when it is clear that consultation with people involved in these significant violations is impossible, counterproductive, or dangerous.

Principle 7: Colleagues

Software engineers shall be fair to and supportive of their colleagues. In particular, software engineers shall, as appropriate:

- 7.01. Encourage colleagues to adhere to this Code.
- 7.02. Assist colleagues in professional development.
- 7.03. Credit fully the work of others and refrain from taking undue credit.
- 7.04. Review the work of others in an objective, candid, and properly documented way.
- 7.05. Give a fair hearing to the opinions, concerns, or complaints of a colleague.
- 7.06. Assist colleagues in being fully aware of current standard work practices including policies and procedures for protecting passwords, files, and other confidential information, and security measures in general.
- 7.07. Not unfairly intervene in the career of any colleague; however, concern for the employer, the client, or public interest may compel software engineers, in good faith, to question the competence of a colleague.
- 7.08. In situations outside of their own areas of competence, call upon the opinions of other professionals who have competence in those areas.

Principle 8: Self

Software engineers shall participate in lifelong learning regarding the practice of their profession and shall promote an ethical approach to the practice of the profession. In particular, software engineers shall continually endeavor to:

- 8.01. Further their knowledge of developments in the analysis, specification, design, development, maintenance, and testing of software and related documents, together with the management of the development process.
- 8.02. Improve their ability to create safe, reliable, and useful quality software at reasonable cost and within a reasonable time.
- 8.03. Improve their ability to produce accurate, informative, and well-written documentation.
- 8.04. Improve their understanding of the software and related documents on which they work and of the environment in which they will be used.
- 8.05. Improve their knowledge of relevant standards and the law governing the software and related documents on which they work.
- 8.06. Improve their knowledge of this Code, its interpretation, and its application to their work.
- 8.07. Not give unfair treatment to anyone because of any irrelevant prejudices.
- 8.08. Not influence others to undertake any action that involves a breach of this Code.
- 8.09. Recognize that personal violations of this Code are inconsistent with being a professional software engineer.

frame. The CRTs (*cathode ray tubes*) used in most analog television sets create images by using an electron gun to sweep lines of differently colored phosphorus dots, causing them to glow in a particular pattern. The NTSC established the rate at which the screen is scanned at 60 Hz, or 60 times per second. This took advantage of the cycle rate (60 cycles per second) of the alternating current used in the United States.

The scanning method used in NTSC video is known as *interlacing*. An *interlaced scan* is one in which alternating lines of the image are produced in each scanning pass. The electron gun first sweeps across the odd-numbered lines and then returns to sweep the even-numbered lines in a second pass. Each pass produces a partial image called a *field*. The two fields are produced very rapidly and blend together to present the completed image, called a *frame*. Scanning each of the two fields in one-sixtieth of a second produces a *frame rate* of 30 frames per second (fps).

The NTSC standard also provided for overscanning. *Overscanning* is the process of transmitting a larger image than will appear on the screen of the TV. This ensures that the transmitted image will completely fill the television screen. As a result, the maximum visible resolution of an NTSC TV screen is reduced from 525 to 484 lines.

The current frame rate for NTSC video is actually 29.97 fps. This slight departure from 30 fps was made when color information was added to the original black and white signal.

To broadcast color television images, NTSC uses a composite signal. A *composite color* signal is a mixture of two other signals, one of which represents *luminance* and the other *chrominance*.

Luminance is the amount of brightness, or white, in an image. *Chrominance* is color hue. Composite color is inexpensive to create and transmit. This technique also made it possible to continue using black and white TVs after color television was introduced. Older sets continued to use the luminance information while ignoring chrominance. (The addition of color to the NTSC also led to the slight change in frame rate to 29.97 fps.)

Although NTSC color TV is broadcast as a composite signal, it is displayed on a TV screen using a different color model. TV displays, like computer monitors, use the *RGB* (Red, Green, Blue) color model. Each pixel of the image is colored by blending different proportions of red, green, or blue light. RGB is *component color*: each color component is represented separately. RGB can produce a virtually unlimited range of very pure colors. In order to produce RGB color on a screen, a television must first translate the composite color information of the broadcast signal to component RGB mode. The composite signal cannot record color as precisely as component color, however. As a result, NTSC color displayed on TVs lacks the range and purity of full RGB color as displayed on a computer monitor.

The limited range and purity of NTSC color has led critics to quip that the acronym actually stands for Never The Same Color.

All analog video broadcasts in the United States used NTSC composite color. The original production of video, however, was done in other formats and most of these made use of component color. This allowed producers to create and edit images with the superior color range and fidelity of the RGB format.

Other Analog Video Broadcast Standards

While NTSC was used in most of North America, other incompatible analog TV standards have been used elsewhere in the world. The two major competitors are *PAL* (phase alternate line) and *SECAM* (*séquential couleur avec mémoire*). PAL was used in England and much of Europe. SECAM was found in a number of countries including France and Russia.

These standards are also interlaced but they use different scan rates (50 Hz), frame rates (25 fps), and screen resolutions (625 lines). Video produced for one format cannot be played on devices intended for another format. This means that NTSC videotapes cannot be played in Europe, and European video productions cannot be played in the United States, without specialized VCRs.

VCRs, Camcorders, and Videotape Standards

The development of VCRs and video camcorders in the 1980s provided another mode of creating and distributing analog video. VCRs use a variety of tape formats, the most important of which are VHS, S-VHS, 8mm, and Hi8. There is limited compatibility between these formats: S-VHS decks can also play VHS tapes, and Hi8 decks can play 8mm tapes, but no other combinations are possible.

- *VHS*: The first widely adopted format was VHS. The VHS format has a relatively low resolution of 240 lines. It can support Hi-Fi audio but it uses composite color. As a result, the overall quality of VHS video is slightly lower than analog TV broadcasts.
- *S-VHS*: Introduced in 1987 by JVC, S-VHS was an improvement on VHS. S-VHS increased resolution to 400 lines. It also improved color quality by maintaining separate luminance and chrominance signals, rather than mixing the two types of information as in composite color. This is a variant of component color known as *Y/C* (for luminance/chrominance). *Y/C* color is also called *pseudocomponent* because it is not as precise as RGB color. It does represent a significant improvement over composite color, however. S-VHS is an improvement over NTSC broadcast video.
- *8mm*: The 8mm format was a smaller tape that made possible more compact, light-weight video cameras. It supported a screen resolution of 230 lines and provided near-CD-quality sound.
- *Hi8*: Hi8 improved the resolution and color of 8mm in ways similar to the improvements of S-VHS over VHS. Resolution increased to 400 lines and *Y/C* component color was added.

S-VHS and Hi8 offer significant advantages as source media for digital conversion because of their superior resolution and color quality. None of these formats compares very favorably, however, with the expensive broadcast quality video used for TV production. These provide full RGB component color and resolutions of approximately 1000 lines.

Delivery of Digital Multimedia on Analog Displays

Developers who need to deliver applications on analog devices face a number of challenges. To understand these, we need to turn first to the differences between the display devices used by computers and analog TVs.

First, one important difference is that analog TVs use interlaced scanning to produce a single frame from two separate fields. Computer monitors use progressive scanning. *Progressive scanning* reproduces each line of the image in a single pass. Second, analog TVs overscan and computer monitors underscan. Overscanning transmits a larger image to the screen than it can display. This clips off portions of the original image and

Analog video is converted to a digital format by the sampling techniques familiar from graphics and sound. The output from a VCR or laserdisc player is connected to a digitizing board that samples the signals and records the value of each sample. Digitizing boards are often installed in computers as add-on cards. They may also be connected as an external device.

Digitizing boards contain ADCs, *analog-to-digital converters*. These devices sample the electrical currents produced by playing the analog source and store the resulting voltage levels as digital values. In much the same manner, ADCs are also used to capture the audio content of analog video. Measurements of the voltages that produce sound are taken and stored as digital values. Many digital video cameras can also digitize analog video. A VCR or laserdisc player is connected to the camera's analog input port and played while the camera is in *record* mode. This samples the analog video and stores the resulting digital file on the camera's tape, disc, hard drive, or memory card.

The quality of digitized video depends on several factors. First and foremost is the quality of the analog source video. Analog media is subject to generation decay: when a copy is made from a previous copy, quality declines. Original analog recordings are always preferable to copies. The state of physical preservation of analog media is also a factor. Analog laserdiscs may delaminate or become scratched. Tape is subject both to loss of the iron oxide layer that encodes data magnetically and to developing a sticky surface that interferes with playback. The format of the analog source video and the method used to connect the analog playback device to the digitizing device are also important. S-VHS and Hi8 support higher resolutions and Y/C color and can produce better digital video than their lower-resolution composite counterparts. These advantages can be easily lost, however, if proper cabling is not used. S-VHS and Hi8 devices typically provide output options for both composite and Y/C color. Common composite connectors include coaxial cable and RCA jacks. The output from either of these mixes the Y/C signal into a composite signal, just as in NTSC broadcast or the lower-quality VHS or 8mm formats. To maintain the advantage of Y/C color, a special *S-Video* cable that transmits luminance and chrominance information through separate wires must be used. S-Video connectors are provided on S-VHS and Hi8 devices and on most digitizing devices. Finally, the quality of the digitizing devices used and the choices made for digitizing formats also affect quality. For instance, earlier digital formats such as 8-bit D1 provide less color definition than later 10-bit formats such as D5. Consideration must also be given to whether a format is supported by the developer's editing software.

The rich store of analog video, from news reports and documentaries, to TV dramas, sitcoms, concerts, sporting events, and more, makes it likely that conversion of analog to digital video will continue to play a role in multimedia development for some time to come. Understanding the differences among various analog formats and the range of choices in the digitization process will help to ensure higher-quality digital conversions.



Glossary



3-D imaging program: Software used to model 3-D objects, define surfaces, compose scenes, and render a completed image.

8mm: An analog tape format used in lightweight video cameras that supports a screen resolution of 230 lines.

AAC (advanced audio coding): The successor to MP3 specified in the MPEG4 standard. AAC produces better sound quality than MP3 at comparable bit rates.

Access point: A central transmitter and receiver of radio signals on a wireless LAN.

Access time: The time to locate and load data from a disk surface. Measured in milliseconds (ms), access time includes the seek time (moving the arm over the appropriate track) and rotational delay (the time to spin the disk under the read/write head to the correct sector location).

Acquisitions specialist: A member of a multimedia team who secures appropriate permissions to use copyright-protected content in a project.

Active matrix: A type of LCD display in which a single transistor controls each liquid crystal cell to produce a faster display rate on the screen. Also called *TFTs* (thin film transistors).

Adaptive indexing: The process of selecting colors in an indexed color palette based on an analysis of the dominant colors in an image.

Adaptive multimedia: A form of multimedia that embodies aspects of intelligence and decision making.

ADC (analog-to-digital converter): An electronic device that converts an analog data stream into digital data.

Additive color: Color produced by combining varying amounts of differently colored light. The color on computer monitors and television displays is additive color produced by combining red, green, and blue light. See also *subtractive color*.

Address bus: Electronic pathway that carries information about memory locations of data. Bus size, measured in bits, determines how much memory the processor can address.

AIFF (audio interchange file format): A digital audio file format from Apple used by Macintosh computers.

Aliasing: An inaccurate or false representation of data. As used in text, aliasing is the appearance of ragged letter edges, especially on diagonal lines. As used in sound, aliasing is the false representation of a high frequency as a low frequency as the result of an inadequate sample rate.

Alignment: In text display, the position of lines of text relative to the margins. Common alignments include left, right, justified, and centered.

Alpha: In multimedia development, an initial test version of an application that typically contains most media elements but may have many bugs.

Alpha tweening: Animation technique that creates the illusion of motion by altering the color or opacity of an object from one frame to another.

ALU (arithmetic logic unit): A component of the CPU that performs mathematical and logical calculations on data.

Amplitude: A measure of sound pressure; the amount of energy associated with the sound. Different amplitudes are perceived as variations in loudness. See also *volume*.

Analog data: Data that varies continuously such as temperature, voltage, or pressure.

Analog hole: A loophole to avoid compliance with the protections on digital media. Playing a digital file and capturing the analog signal to a recording device will circumvent the digital protective measures.

Animated GIF: A file of .gif images that repeat in sequential order to produce a simple animation. A waving flag could be produced in an animated gif file format.

Animating with physics: A method of animation that specifies motions based on the properties of objects and the laws of physics.

Animation: The technique of rapidly displaying a series of still images to produce the appearance of motion. This illusion of motion is possible due to a phenomenon known as *persistence of vision*.

Anti-aliasing: In text display, a method used to produce characters with smooth edges by blending the color of the text with the background color of the screen or page.

Application: Software that performs a specific task, such as word processing or image editing.

Artificial intelligence (AI): The branch of computer science that explores methods to embody intelligence in computer software and hardware. The term was first used by John McCarthy in 1956 at MIT. Examples of applications that use AI are computer games, expert systems, and robotics applications.

Ascender: The portion of a letter written above the normal text body. Letters such as *h*, *k*, and *t* have ascenders.

ASCII (American Standard Code for Information Interchange): A code to represent letters, symbols, and numbers in binary format. It was originally developed in 1965 as a 7-bit code for 128 characters that were compatible with all data processors. In 1981, IBM introduced an 8-bit code with 256 unique characters for its personal computers. Today's standard is 8-bit, known as "extended ASCII or ASCII-8."

Aspect ratio: The relationship between width and height on a computer monitor, television display, or movie screen. The aspect ratio of NTSC video is 4:3, whereas HDTV is 16:9.

Assembler: Software to convert abbreviated commands in assembly programming languages to machine code. Like the language itself, assemblers are dependent on the specific machine instruction set used by the computer.

Assembly language: A low-level programming language that uses symbolic instruction codes to define instructions for the computer to execute. The codes are machine dependent, developed for one specific type of processor. Assembly language requires an assembler, a program to convert the abbreviated codes to machine language for program execution.

AU: Audio file format developed by Sun that is used on the Internet for transmission of relatively low-quality sound files.

Authoring: The process of integrating media and creating the user interface for a multimedia application.

Authoring application: Programs especially designed to facilitate the development of multimedia products. This software supports integration of various digital media and ability to create interactivity.

Autotracing: The process of converting a bitmapped image to a vector image by identifying image areas that can be treated as shapes. These shapes are then defined by mathematical formulas to complete the conversion to vector format.

AVCHD (Advanced Video Coding High Definition): Digital video compression format that can record in 1080i, 1080p, and 720p resolutions. Uses .mts and .m2ts file extensions.

Background layer: In multimedia authoring, an area that holds media elements shared across multiple screens. See also *foreground layer*.

Backward compatibility: The ability of more recent hardware or software to use data from an earlier product (for example, CD discs are readable in CD-RW drives).

Bandwidth: The rate at which digital data can be transmitted over a communication medium, or band.

Basic interactivity: User control of multimedia information through common navigation techniques like buttons, menus, navigation bars, or VCR-like controls.

Berners-Lee, Tim: The inventor of the World Wide Web.

Beta: In multimedia development, an advanced test version of an application that usually contains all media components and few bugs.

Binary code: The coding system consisting of two digits, 0 and 1. Binary code is the universal language of computers.

Bit: A binary digit used to encode digital data (0 or 1).

Bit depth: The number of bits used to represent a data sample.

Bitmap: A computer graphic with 1-bit color depth resulting in the possibility of two colors, generally black and white. See also *line art*.

Bitmapped font: A technique for displaying text through a monitor or printer. Each pixel of a letter is described by a binary code of one or more bits creating a bitmap of the letter.

Bitmapped image: A graphic represented as a grid of rows and columns of dots in memory. The value of each dot (or picture element) is stored as one or more bits of data. The density of dots (spatial resolution) determines the sharpness of the displayed image. The number of bits for each dot determines the color resolution for each dot.

Bitmapping: The process of defining an image as an array of individual pixels.

Block: The smallest addressable unit of CD-Audio data storage. A block consists of 58 frame units of data.

Blu-ray: An optical disc format developed for recording and playing back high-definition (HD) video and storing large amounts of data. Dual-layer Blu-ray discs can store up to 50 GB data. The name is derived from the blue-violet laser used to record data.

Bluetooth: Standardized as 802.15, Bluetooth provides wireless networking of data and/or voice devices in a small area (up to 30 ft). Bluetooth supports a basic data rate of 1 Mbps and is intended for wireless data exchange between a computer and local peripherals such as a printer, keyboard, or PDA.

BMP: A Windows bitmapped image file format.

Browser (web): A software application that resides on a client computer to process and display documents transmitted by the HTTP protocols. Web browsers became popular in 1993 when Marc Andreessen developed Mosaic as the first graphical browser. Mosaic became the “killer application” of the Internet because its graphical interface provided easy navigation to pages that could display text and images on the client computer.

Bump map: An image of a textured surface produced by creating a pattern of lighter and darker shades of color. Lighter shades appear higher and darker shades appear lower.

Bus: An electronic channel or path that carries bits within the circuitry of a computer system.

Bus width: The number of bits a bus can transfer at one time. Wider bus size means more data can be transferred faster. A 32-bit bus can move twice as much data as a 16-bit bus.

Bush, Vannevar: (1890—1974) A scientist and professor at MIT, Bush constructed the Differential Analyzer. He was also a visionary of modern multimedia. In “As We May

Think" (*Atlantic Monthly*, 1945), he introduced the concept of "Memex," an interactive hypertext system for organizing information.

Byte: A group of 8 bits.

Cache: High-speed electronic storage that holds recently accessed data. Cache is designed to increase the speed of processing by keeping a copy of frequently read data closer to the processor, thus saving the time that would be required to fetch it from main memory.

Card metaphor: A common metaphor for authoring applications that organizes media content in sequential order where each point of information is placed on a card or displayed on a screen.

Cartridge disk: A portable magnetic storage medium where the disk is a rigid platter contained in a sealed plastic case. The most popular form of cartridge disk is the zip disk.

Case: A typographical characteristic of letters. Capital letters are called *uppercase*; small letters are designated as *lowercase*. The term is derived from the manual typesetting industry. As early as 1588, blocks of letters were organized in wooden cases. The capital letters were in drawers above (upper case) and the small letters were below (lower case).

CAV (constant angular velocity): In optical storage, a method to locate and access data where the disc is rotated at a constant speed, similar to hard drives.

CBR (constant bit rate encoding): A method of encoding digital video or sound that assigns the same number of bits per second to all parts of the video or sound. See also *VBR*.

CCD (charge-coupled device): An electronic device used in scanners and digital cameras to capture an image as a set of voltages that are then sent to an ADC where they are translated into binary data.

CD-DA (CD-Digital Audio): Optical storage standard developed by Philips/Sony in 1982 to hold 74 minutes of high-fidelity digital audio. Some later audio CDs can store 80 minutes of music depending on the configuration of the track.

CD-R (CD-Recordable): A standard for discs that can be written to by a computer. CD-R discs are coated with a layer of photoreactive dye. A laser light in the drive alters the molecular structure of the dye to store data. CD-R discs can support multisession recording, but cannot be erased to store new data.

CD-ROM (CD-Read Only Memory): An optical disc standard for the storage of computer data. Developed in 1984, CD-ROM holds approximately 650 to 680 MB of data stored in pits and lands.

CD-RW (CD-Rewritable): A compact disc that can be read, erased, and recorded. CD-RW requires a disc with a special layer of phase-change substance that alters its crystalline structure when heated by a laser light. The CD-RW drive has two intensities of laser light. A stronger light beam will erase and write data. A less intense light is used to read the data.

Color gamut: The range of available colors.

Color indexing: The process of defining a color palette based on an analysis of the colors in an image and/or the conditions of human perception.

Color palette: The set of colors available to a computer at any given time.

Color resolution: A measure of the number of different colors that can be represented by an individual pixel. Color resolution is determined by bit depth.

Command-line interface: A method for users to interact with an operating system by entering commands based on a specific syntax. MS-DOS and UNIX are common operating systems that have a command-line interface.

Command-based digital encoding: A method of encoding digital media that uses program instructions to re-create the media. MIDI is an example of command-based media encoding. See also *description-based digital encoding*.

Compact Disc (CD): Optical storage media first developed in early 1980s to hold high-fidelity sound. The CD standard was subsequently extended to include computer data and became an important distribution medium for multimedia applications and other software.

Compiler: Software that converts the entire source code (high-level program) into a machine-level program. The result is an executable file that runs on a specific computer system.

Component color: A technique for producing color in which each color component—red, green, and blue—is represented in a separate color channel.

Composite color: A technique for producing color in which luminance (brightness) and chrominance (color hue) are mixed and transmitted in a single signal.

Compression: A process of reencoding data to reduce storage or transmission requirements. See also *lossless compression* and *lossy compression*.

Computer platform: A category of computer defined by the combination of CPU and operating system used. Applications are written for specific platforms such as Windows/PC or Macintosh.

Computer system: An integrated set of hardware and software designed to process data and produce a meaningful result.

Condensed text: Text in which the width of all characters is narrowed.

Conditional: A navigational structure in a multimedia application that is based on the user's responses or progress in the application.

Content expert: A person who knows the subject matter of the multimedia project. The content expert is frequently the client. Responsibilities include determining the project objectives, target audience, and user needs; providing the content materials; providing additional resources; and providing feedback on content, design, and interactivity development in relation to the subject matter.

Content inventory list: A document that identifies the required media for a multimedia project.

Content Scrambling System (CSS): A form of encryption used by the motion picture industry to protect DVDs from digital piracy.

Contone (continuous tone): An image made up of continuous areas of color, such as an analog photograph. See also *line art*.

Control unit (CU): The set of transistors in the CPU that directs the flow of data and instructions within the processor and electronic memory.

Convention: Standard or agreed-upon procedures.

Copyright: A form of legal protection given to creators of original works.

CPU (central processing unit): A complex set of transistors that execute program instructions and manipulate data.

Creative Commons: An alternative to traditional copyright practices that gives the owner a method to define how others may use his or her works. Managed and supported by the nonprofit Creative Commons organization: <http://creativecommons.org/>

Cross-platform compatibility: The ability of an application to run on different hardware and operating systems.

CRT (cathode ray tube): A monitor that displays output by scanning the back of a phosphor-coated screen with an electron beam.

Cycle: A series of images that can be reused to extend repetitive action in traditional animation.

D1: Original high-resolution format used in expensive cameras and editing systems for the production of broadcast-quality TV using 19mm tape. More recent formats for broadcast TV include D5 and D10-MPEG IMX.

DAC (digital-to-analog converter): An electronic device that converts a series of discrete digital values to an analog signal.

Data: Facts that can be organized and grouped in meaningful ways.

Data bus: Electronic pathway that carries data between memory and the CPU.

Data file: See *file*.

Database: A collection of integrated and related files.

Debugger: A utility to track the execution of program code and assist developers in locating coding errors.

Decibel (dB): A measure of sound amplitude. Each 10-dB increase roughly doubles the perceived volume of a sound.

Descender: The portion of a letter written below the line. Letters such as *p*, *g*, and *j* have descenders.

Description-based digital encoding: A method of encoding digital media that stores a digital representation of the media element. A bitmapped image stores each picture element in the image. See also *command-based digital encoding*.

Development plan: A structured procedure to create a multimedia project that includes all the steps that will lead to successful completion of the product. Development plans address three essential tasks: definition, design, and production.

Effective procedure: A step-by-step process guaranteed to produce a particular result. Computer programs are effective procedures. Also called an *algorithm*.

Efficient code: A code that represents each desired data item without wasting storage, processing, or transmission resources.

Encoding: The process of assigning bits to a data item.

End user license agreement (EULA): A license to use the product in certain ways specified in a contract. Commonly used in software programs and becoming a common means to control the uses of digital media.

Engelbart, Douglas: A scientist at the Stanford Research Institute (SRI) where he proposed *computer-human interaction* as a research project. His team developed hypertext, the first mouse, the GUI interface, and researched the power of computer networks. At SRI, Engelbart was instrumental in ARPAnet, the precursor of the Internet.

ENIAC: Electronic Numerical Integrator and Computer. The first general-purpose electronic computer. Built between 1943 and 1945 for over \$500,000, it was used to calculate military firing tables.

EPS (Encapsulated PostScript): A file format to deliver graphic images between software programs and computer platforms.

Ethernet: A popular network protocol for local area networks first developed at Xerox PARC in 1976.

Expert systems: A form of artificial intelligence (AI). Expert systems are software applications that utilize a knowledge base to make decisions from “rules” stored in an “inference engine.”

Extended ASCII: An addition to the 7-bit ASCII standard, made by using 8 bits to generate 256 characters, thus increasing the range of letters, symbols, diacritics, and special characters.

Extended text: Text in which the width of all characters is increased.

Extrusion: The process of generating a 3-D shape by extending the lines of a 2-D object through space. For example, a 2-D rectangle extended vertically produces a cube.

Fair use: An exception to copyright protection intended to support important social goals such as a free and open press, education, research, and scholarship.

Field: In video, the partial image created by scanning every other line of a TV screen. Two fields are combined to form a complete video frame.

File: A container for data and programs.

File compatibility: Describes the interoperability of data and program files between operating systems and/or applications.

File conversion: The process of changing a file format from one convention to another. A common example is to convert a Photoshop file format into a JPEG file format using the *Save As* option.

File extension: One or more letters following the filename separated by a period. The extension may designate the program that created the file (.psd is Photoshop) or the type of file (.html is a web page).

Frame (animation, film, video): The individual images that are rapidly displayed to produce the illusion of motion.

Frame (authoring application): One instance of content in a timeline-based authoring application. Each frame contains all the media for a single unit of time in the animated sequence, as in frames per second.

Frame (CD storage): The basic unit of information on a CD. Frames define the physical format of data.

Frame-by-frame animation: An animation technique that requires each individual frame to be created manually.

Frame rate: The speed at which frames are displayed in animation, film, and video.

Frequency: The rate at which a sound wave completes a cycle from lowest to highest amplitude. Different frequencies are perceived as variations in pitch.

Frequency modulation (FM): In synthesized sound, a method for producing audio output from a synthesizer. FM synthesis produces different sounds by using one signal to modulate the frequency of another signal.

Functional specification: A document in a multimedia development plan that specifies the media elements and performance of the multimedia project.

Generation decay: In analog media reproduction, the degradation in the quality of sound or video recordings as copies are made from previous copies.

GIF (graphics interchange file): A cross-platform file format for graphics frequently used for images on the Web. GIF images use lossless compression and are limited to 8-bit color resolution.

Gigabyte: Approximately a billion bytes. More precisely 2^{30} , or 1,073,741,824 bytes.

Graphics tablet: An input device that facilitates freehand image creation using a flat surface and a stylus pen.

Graphics text: Letters and symbols created in a graphics application as an image. This method is widely used for creating artistic logos or word images designed for visual impact.

Grayscale: A digital image composed of pixels representing white, black, and shades of gray.

GUI (graphical user interface): A method of controlling operating system functions through display of intuitive icons that the user manipulates using a pointing device such as a mouse or trackball. Initially suggested by Douglas Engelbart at SRI and further developed by Xerox, the GUI was first made popular by Apple Computer in 1984 with the introduction of the Macintosh computer.

Halftone: A print image composed of dots of black or white.

Handles: Control points on vector graphic images that can be moved to produce changes in shape.

Hard disk: Rigid platters mounted on a spindle in a sealed container. Hard-disk locations are addressed by tracks, sectors, and cylinders.

Interlacing (monitor): In monitor display, the technique of generating an image by scanning alternate image lines on successive passes.

Internet: A network of networks. First developed by ARPA in 1969 to share research data and computers across the United States, the Internet evolved into a worldwide information resource.

Interpreter: Software that translates high-level languages into machine code by converting one line, executing that line, then moving to the next line in the program to repeat the process.

Intraframe compression: A form of digital video compression that reencodes information within frames but preserves all the individual frames of the video.

Intuitive interface: A method of interacting with the content on the screen that is immediately understood by the user.

Inverse kinematics (IK): An animation technique in which the motion of one body part produces related motions in other body parts. IK presupposes basic anatomical knowledge. See also *kinematics* and *forward kinematics*.

Iterative: Repetitive or recurrent. The multimedia development plan is an iterative process in which earlier stages are reshaped or reformulated as the development progresses.

Jaggies: The stair-step effect on the rounded edges and diagonal lines of letters, numbers, and other images displayed on a monitor or printer. A common method to reduce jaggies is anti-aliasing.

Jobs, Steve: (1955–2011) Cofounder and CEO of Apple Computer. In the early 1980s Jobs recognized the future of multimedia computing and incorporated the mouse, GUI, and built-in audio in the Macintosh computer.

JPEG (Joint Photographics Experts Group): A file format for photo-quality bitmapped images. JPEG provides varying degrees of lossy compression and supports 24-bit color. Widely used on the Web and in digital cameras.

Justification: Adjusting lines of text to produce straight edges at the left and right margin. Often, extra space is added between words or letters to stretch the line out evenly to the right margin.

Kay, Alan: Computer scientist who developed the concept computer called the Dynabook, which resembles today's laptop. He was one of the founders of object-oriented programming language and a key developer of the GUI environment.

Kerning: Adjusting the space between specific pairs of letters. The appearance of paired letters such as *A* and *W* benefits from kerning because it produces a spacing that is more consistent with other letters.

Key frames: The images drawn by principal artists in traditional animation, usually the start and finish of an animated sequence. Other artists would create the frames between these two major points. Digital applications define the parameters and attributes of a start and end key frame. The software automatically creates subsequent frames by interpolating changes to the image between these frames. See also *in-between frames*.

Kilo: 2^{10} , or 1024, i.e., *approximately* one thousand.

Kilobit (Kb): 2^{10} , or 1024, bits, i.e., *approximately* 1000 bits.

Kilobyte (KB): 2^{10} , or 1024, bytes, i.e., *approximately* 1000 bytes.

Kinematics: The study of how the parts of bodies move in relation to each other. For example, the motion of an arm generates related motion in the shoulder, elbow, wrist, and fingers. See also *forward kinematics* and *inverse kinematics*.

Kiosk: A freestanding multimedia information system. Frequently has a touch screen for user input.

LAN (local area network): A series of computers connected within an organization. The communication links are maintained by the organization.

Land: The flat surface on an optical disc that directly reflects light to a light-sensing diode in a CD or DVD drive.

Laser (light amplification by stimulated emission of radiation): An amplified light focused into a single wavelength.

Laser printer: A nonimpact printer that uses copierlike technology to fuse an image to the paper.

Lathing: In 3-D graphics, the process of generating a 3-D object by rotating a 2-D line on an axis. For example, lathing can rotate the profile of half a bowl through 360 degrees to “sweep out” the full 3-D shape.

Layers: In graphics, the planes on which different parts of an image are drawn. Layers can be thought of as stacks of image elements, each of which can be separately edited. Combining layers, called *grouping*, locks elements together, while *flattening* merges layers to a single plane.

LCD (liquid crystal display): A display technology used on small portable devices, computers, and televisions. Lightweight and requiring little power, LCDs contain liquid crystal molecules that are controlled by transistors. When the molecule is altered to let light through, a pixel of the image is displayed.

Leading: The spacing between lines of text. The term derives from the practice of adding strips of lead beneath the characters on a printing press to increase line height.

LED (light-emitting diode): Method of backlighting any computer display device that uses TFT technology. Compared to LCD, the LED screen is much brighter, uses less power, and can be viewed from any angle with the row of diodes providing the back light to the display.

Leica reel: A working draft of the complete animation used in filmed animation production. A leica reel includes preliminary animated stills arranged with recorded audio. Derived from a German camera called a Leica originally used to develop these filmed storyboards.

Line art: An image drawn only as lines without color filling or shading. Line art uses 1-bit color depth to produce just two colors (usually black and white). See also *contone*.

Linear: A navigational structure that organizes the content for the user along a sequential path.

Lines per inch (lpi): A measure of spatial resolution for print images.

Media utilities: Programs, generally free or shareware, that support a specific function in creating or editing media. For example, utility programs can provide visual effects, color management, compression, image screen grab, or font creation.

Media-specific application: Software used to create and edit a specific media type such as sound, video, or images.

Mega: 2^{20} , or 1,048,576, i.e. *approximately* one million.

Megabyte (MB): 2^{20} , or 1,048,576, bytes, approximately a million bytes.

Megapixel (MP): A measure of spatial resolution of digital imaging devices such as a scanner or camera. Approximately one million pixels.

Memex: A theoretical information-processing machine described by Vannevar Bush. The Memex would store large volumes of multimedia data and organize that data based on associations created by the user.

Memex II: A theoretical machine envisioned by Vannevar Bush that built on features first defined in the Memex. Based on new technology, the Memex II would store data on magnetic tape and combine with a digital computer to efficiently organize the growing mass of information.

Memory card: A solid-state storage device for digital cameras, cell phones, game consoles, and portable data storage.

Message: In synthesized sound, a MIDI command.

Metaball modeling: A 3-D modeling technique that creates objects by combining elements called *blobs*. Building an object with metaballs is similar to working with lumps of clay. This technique is useful for creating objects with soft edges.

Metafile: A file format that can encode both bitmapped and vector graphics.

Metamedium: A term Alan Kay used to describe the Dynabook. This concept computer was to embody any medium; thus the Dynabook itself was a metamedium.

Metaphor: The use of one thing to represent or suggest another. In multimedia authoring, metaphors are often used to relate unfamiliar content or processes to familiar objects or operations, as in the use of VCR-like controls to play and pause animations.

Microcode: A programming technique for implementing the instruction set of a processor.

Microcomputer: A computer based on a microprocessor and designed to support a single user. Microcomputers appeared in the early 1970s after the introduction of the 4004, the first commercial microprocessor by Intel.

Microelectronics: Miniature integrated circuits often found on silicon chips.

Microprocessor: A single silicon chip that contains all the elements of a central processing unit. Its development in the early 1970s by Intel led to the microcomputer revolution.

MIDI (Musical Instrument Digital Interface): A standard method of connecting and playing musical instruments, synthesizers, and other digital devices.

Mixing: The process of combining two or more audio signals into a single sound track.

M-JPEG (Motion JPEG): A video codec based on JPEG image compression. M-JPEG uses intraframe but not interframe compression. See also *Motion JPEG 2000*.

Mobile computing platform: The result of the continuing miniaturization of computers and the merger of computing and telephone technologies. Mobile computing devices include lighter personal computers, special purpose e-readers and tablet computers, as well as smartphones networked through Wi-Fi or 3G/4G technologies.

Modeler: In 3-D graphics, software that creates shapes directly rather than building them from more basic objects. Common types of modelers include polygon, spline, metaball, and formula.

Modeless: An ideal computing environment advocated by Alan Kay where the user could switch easily from one mode of activity to another.

Modeling: The process of specifying the shape of objects in 3-D graphics.

Monospaced font: A typeface that assigns the same space to all letters. Courier is a monospaced typeface.

Morphing: An animation technique that transforms one shape into another over time.

Motion capture: The animation technique of recording the motions of actual objects and mapping these motions to a computer-generated animated character.

Motion JPEG 2000: A variant of JPEG 2000 that uses a new form of compression (wavelet) to produce smaller files at higher quality than the original JPEG standard. Motion JPEG 2000 can deliver mathematically lossless compression as well as compression that is either visually lossless or lossy. Motion JPEG 2000 files use either the .mj2 or .mjp2 extensions. See also *M-JPEG*.

Motion tween: A digital animation procedure that interpolates the position of an object from one location on the scene to another based on the position of the start and end key frames.

MP3: A lossy codec that maintains near-CD-quality sound files.

MP3 player: Originally created to store and play MP3 compressed music files, some players can also store data files. Players may use flash memory or have minihard drives to hold music and data.

MPEG (Motion Picture Experts Group): A codec specifically designed for video that uses both intraframe and interframe compression to produce small files.

Multicore: CPU chip architecture that combines two or more logic cores on a single integrated circuit to execute more tasks and improve overall system performance. See *dual-core processor*.

Multifunction printer (MFP): An output device that combines printer, fax, copier, scanner, and often a memory card reader in one unit. This combination of peripheral devices conserves the desk space that would be used by multiple devices.

Multimedia: The development, integration, and delivery of any combination of text, graphics, animation, sound, or video through a digital processing device.

Multiprocessing: Combining multiple processors to execute instructions simultaneously. The Apple G5 computer has dual processor capability; many PCs have a math or video coprocessor.

Multitasking: A method controlled by the operating system to share the computer processor with more than one program. Each program is allotted its own space in RAM and its own peripherals, but they share the processor concurrently. Often called *event driven* because processor sharing is based on events that take place in the program.

Multitimbral: Capable of playing multiple instruments at the same time. MIDI systems are multitimbral—they simultaneously process the information for multiple instruments in different channels.

Multitouch: A method of input that allows one or multiple fingers to manipulate the interface of a digital device.

Nanotechnology: An industry focused on shrinking the size of microelectronic components to nanometer size. A nanometer is one-billionth of a meter. Nanotechnology will dramatically reduce the size and increase the speed of processors by working with components that are the size of individual atoms.

Native file format: Coding conventions used by specific applications for their data files. For instance, .psd is the native file format for Photoshop.

Nelson, Ted: Early multimedia theorist who coined the term *hypertext* in 1963. Nelson conceived Project Xanadu, a large information base connected by networks with a simple user interface. While Xanadu never succeeded, it is considered the inspiration for the Web.

Network: A collection of computers connected through a communication link to share hardware, data, and applications.

Networked: A navigational structure that allows the user to freely explore content, often based on hyperlinks to related material.

Nodes: In hypertext and hypermedia, the content items that are linked together.

Noninteractive multimedia: A form of multimedia that integrates digital media into a single application but does not give the user control over the sequence or display of the information.

Nonprocedural programming: Method of developing software applications that makes use of preconstructed modules to improve the overall productivity of the programming process. See also *procedural programming*.

Notepad: An ASCII text editor provided as a utility program in the Windows operating system.

NTSC (National Television Standards Committee): The analog TV standard developed for the United States in 1952.

NUI (natural user interface): Interface design strategy that allows direct input to the operating system without an intervening tool such as a mouse or stylus pen. Multitouch screens are an example of a NUI.

NURB (Non-Uniform Rational B-spline): A technique for defining the shape of a 3-D object. A NURB defines an image using mathematical formulas that can be adjusted to vary its size and shape.

Object-oriented programming language (OOP): A language that uses self-contained elements (objects). Each object holds the data and instructions related to that element.

Objects interact with each other by passing messages or commands to various components. Because each object does not require recoding each time it is used, this language is generally more efficient than traditional procedural languages.

OCR (optical character recognition): The process of converting printed text into digital files that can be edited in a word processing application. Requires a scanner and specialized OCR software.

Onionskinning: An animation technique to draw an image in reference to the previous one. Using thin paper or a light table, the traditional animation artist could reference the preceding images to locate and draw the current image. Digital applications simulate onionskinning by displaying grayed-out preceding frames in the animated sequence.

Opaquers: In traditional animation, opaquers are the artists who apply the colors to the drawn image on a celluloid sheet.

Open Source Initiative: A standards body that promotes the collaborative development of software applications by making the source code available to the programming community. Examples of OSI software include Mozilla Firefox, Apache, Linux, Gimp, Blender, Drupal, and numerous other programs. See <http://opensource.org/>.

Operating System (OS): Software that manages the user interface and computer hardware and controls program execution.

Optical photo conductor (OPC): The light-sensitive coating on the surface of the drum in a laser printer.

Optical storage: A method to store binary data using laser technology. Data is represented through various techniques that either reflect or absorb light emitted from a laser diode.

OS utility program: Software that provides tools to optimize the basic functions of an operating system. Disk management tools, accessibility options, and text editors are examples of OS utilities.

Outline font: A technique for displaying text through a monitor or printer by storing a description of the letter shape. Outline fonts such as TrueType are scaled by changing the dimensions of the basic description to produce an accurate display of the resized character.

Output resolution: The screen resolution that matches the capabilities of the output medium. A developer can reduce the output resolution of a video window to improve the color and motion of the video as it is displayed on less powerful computers or on lower-bandwidth networks.

Over-the-shoulder shot: An angle for shooting video that includes the subject as well as others observing the subject.

Oversampling: In sampled sound, recording at a higher sample rate than that required to capture the desired frequency range. Oversampling is often done to avoid sound aliasing. Once captured, oversampled sounds are often downsampled to reduce file size.

Overscanning: Producing a screen image that is larger than the display device. NTSC TV uses overscanning. This ensures that the televised image will completely fill a TV screen.

Personal computer (PC): A system that uses a microprocessor to provide computing for a single user. Other labels include *microcomputer*, *desktop computer*, and *laptop computer*. In popular usage, PC also designates an IBM-compatible microcomputer using the Windows operating system.

Photo printer: A color printer especially designed to produce photos.

Pica: A standard unit of text measurement predominately found on typewriters. A pica is 12 points; 6 picas equal 1 inch.

PICT: An image file format developed by Apple and widely used in Macintosh graphics applications. PICT is a metafile format; it can store both bitmapped and vector graphics.

Pipelining: A method of increasing processor speed by processing data in a sequence of stages, each stage providing input to the next task prior to the completion of the full fetch/execute cycle.

Pit: An indentation on an optical disc that scatters reflected light, thus reducing the reflection detected by a light-sensing diode in a CD or DVD drive.

Pitch: The psychological perception of sound frequency.

Pixel: A digital picture element.

Pixels per inch (ppi): A measure of spatial resolution for the display of computer graphics.

Platform: The combination of computer hardware and the operating system.

Player: A small program used to present media on a computer. Players include general purpose programs, such as the QuickTime player or RealPlayer, that display a category of media (graphics, audio, video) as well as specialized programs, such as the Flash player, that present content developed through a specific authoring application.

Plug and play (PnP): A feature of modern operating systems that automatically identifies and installs peripheral devices.

PNG (portable network graphic): A bitmapped graphics file format developed to replace GIF. PNG supports 48-bit color and provides lossless compression.

Point: A measure of the size of type from the ascender to the descender of the letter. One point is approximately 1/72 of an inch; 12 points is 1/6 of an inch.

Polygon modeling: The process of creating a 3-D graphic shape as a combination of straight line figures, usually triangles or quadrilaterals.

Polyphonic: Capable of playing more than one note simultaneously.

Postproduction: A phase in media creation for a multimedia project where content is edited using specialized software to achieve desired effects.

PPI: See *pixels per inch*.

Preemptive multitasking: The operating system controls program access to the CPU by assigning "time slices" for each task in a multitasking environment. This process replaced program control of the CPU, which often led to system crashes when a program would not release sufficient time slices for other running tasks.

Progressive scan: The technique of producing a screen image by scanning each line on each pass, rather than every other line as in an interlaced scan. Progressive scanning is used on computer monitors and in some HDTV formats.

Project designer: A member of a multimedia team who is responsible for the overall structure of the project's content as well as the look and feel of the user interface.

Project manager: The person responsible for planning and managing all the human and technological elements of a multimedia project, from concept to completion. The responsibilities include meeting with the content expert or client; planning, budgeting, and preparation; managing concept design and user research; overseeing the content, creative, and technical development; supervising site testing, release, and evaluation; bringing the project to completion within the time frame and budget; and trouble shooting.

Proportional font: A typeface that adjusts the width between letters based on letter shape. For example, Times New Roman typeface allows less space for the *i* and more for the *o* shape.

Protocol: A set of rules or conventions that govern the exchange of data between computers. Common protocols include TCP, IP, FTP, MIME, and HTTP.

Prototype: An incomplete working model of the final multimedia project. It includes some finished media and many of the major functions for the operation of the application.

Psychoacoustics: The interplay between the psychological conditions of human perception and the properties of sound. Psychoacoustics is used in developing effective sound compression strategies, such as MP3.

Public domain: The status of creative products (works of "original authorship") that are not protected under copyright.

Pure tones: Tones (such as the notes produced by tuning forks) that can be represented as simple waves that regularly repeat a smooth transition from high to low pressure (a sine wave).

Quantization: The process of rounding off a sample to the closest available value in the digital code being used. May produce distortion of the original data.

QuickTime: A cross-platform file format principally intended for dynamic data (animation, sound, and video) developed by Apple Computer. QuickTime uses the .mov extension.

Random access: A method of locating data or programs in which all items can be accessed in an equivalent amount of time. The opposite of sequential access, in which the time required to access data depends on its location on the medium. Videotape, for example, is sequential access.

Random access memory (RAM): A component of primary memory consisting of addressable storage locations for data and instructions in electronic format. RAM is volatile storage—when power is interrupted, all contents are cleared from memory.

Raster scan (monitor): The process that creates an image on a CRT by illuminating a grid of picture elements (pixels) with an electron-scanning beam. The beam draws the display horizontally across the screen one parallel line at a time.

Rasterize: The process of converting text or images into a matrix of pixels, or bitmap, for display on a screen or printed page.

Ray tracing: Advanced technique used in computer-generated graphics to create image properties that are controlled by light sources (rays) such as shadow, color, and shading. Ray tracing requires large amounts of CPU processing time.

Read-only memory (ROM): Nonvolatile storage on the system board that contains critical programs and settings that manage the initial configuration and booting of the operating system. The contents of ROM can be read, but not altered or erased.

RealAudio: A streaming audio technology for the Internet from RealNetworks. Released in 1995, the .ra file format is used by many Internet radio programs.

RealVideo: A file format for streaming video developed by RealNetworks.

Registers: High-speed electronic memory locations on the CPU. Registers support the basic fetch/execute function of the CPU by storing data, instructions, and addresses for immediate access by the control unit or ALU.

Remedies (copyright): A legally established sanction that applies to a violation of copyright protection.

Rendering: In 3-D graphics, animation, and video, the process through which the computer generates the finished images as specified by the artist or editor through modeling, surface definition, and scene composition.

Resampling: The process of increasing or decreasing the number of samples described in the file. See also *downsampling* and *upsampling*.

Resolution: The number of addressable pixels that can be illuminated in a CRT, LCD, or other display device. Settings in the operating system can alter the resolution of a monitor from 800 × 600, for example, to 1024 × 768 pixels.

RGB: Red, green, blue color model for computer displays. Each color is represented separately, which generates a nearly limitless range of pure colors.

RISC (reduced instruction set computing): A processor design strategy to make the CPU more efficient by using a smaller and simpler set of instructions and executing them faster.

RLE (run length encoding): A form of lossless compression. RLE replaces sequences of repeated data with a single description for the length of the run. RLE is useful in images with large areas having the same color.

Rotoscoping: The process of producing traditional animation by tracing the individual frames of a film or video. Rotoscoping can also be carried out using a digital draw or paint program.

Router: A network device to route (or transfer) data packets from one location to another along a network using IP addressing.

RS232C: An industry standard for serial data communication between devices such as printers, terminals, and modems. Often abbreviated as COM on the interface port.

RTF (rich text format): A text file format developed by Microsoft for cross-platform, cross-application compatibility. RTF includes ASCII text code and additional code to define the formatting characteristics of the text.

Surface definition: The stage in 3-D graphics that specifies the textures that are applied to the model's surface.

S-VHS (super VHS [video home system]): An enhanced version of VHS that provides greater screen resolution and improved color.

S-Video (separated video): An analog video standard that uses separate signals to transmit luminance and chrominance information. This technique, known as Y/C, is a variant of component color that results in an improved TV signal as compared to the composite signal used in NTSC transmission. See also Y/C.

SVG (scalable vector graphics): The newest of the general-purpose vector formats. SVG is a language for describing 2-D graphics and graphical applications in XML.

Symbol: A representation of something else.

Synthesis: The combination of separate elements to form a whole. Sound synthesis occurs when computer software sends commands to generate notes from a synthesizer. Speech synthesis occurs when the computer software sends commands to form spoken words based on written text.

Synthesized sound: Sound generated (or synthesized, "put together") by the computer. A file for synthesized sound contains instructions that the computer uses to produce a sound.

Synthesizer: A device that creates sounds electronically based on commands, most commonly MIDI instructions.

System board: The main circuit board on a microcomputer. The system board provides the bottom plane of circuitry to connect other component parts to one another. Also known as the motherboard.

System bus: The electronic pathway between the CPU and memory.

System unit: Contains the electronic components to process and store data. This includes CPU, electronic memory, system board circuitry, expansion slots, and all the interface ports on a microcomputer. Often is used to refer to the "box" that contains these components and other peripheral devices.

TCP/IP (Transmission Control Protocol/Internet Protocol): A series of standards that controls data transmission between network computers as a series of addressed data packets. The TCP standard breaks sending data into packets, adds error detection, and reassembles packets at the destination host. The IP standard delivers the data packets to various network systems through routers that direct the packets to the correct host computer based on an IP address. The protocols were originally developed in the 1970s by ARPA (Advanced Research Projects Agency) to create a fault-tolerant network system in the United States.

Terabyte: Approximately a trillion bytes. More precisely 2^{40} , or 1,099,511,627,776, bytes.

Thin film transistor (TFT): Flat-panel display technology in which each pixel is controlled by one to four separate transistors. Although expensive, TFTs provide the best resolution quality for flat-panel computer screens.

Thunderbolt: Hardware interface standard developed by Intel and introduced by Apple that combines video and data ports for simultaneous transfer on a single bidirectional cable at 10 Gbps.

TIFF (tagged image file format): A cross-platform bitmapped format often used in scanning and for wide distribution of images.

Time code: In video, a record of the time when each frame is shot. Time code is stored on each frame in the form of hours: minutes: seconds: frames. The time code serves as the frame's address.

Timeline (video editing software): Place to assemble video clips that shows the duration of the video. A timeline displays multiple tracks for both motion and audio components of the video.

Timeline metaphor: A multimedia authoring metaphor that organizes media content and interactivity as sequences of frames. This metaphor is appropriate for dynamic media such as video or sound that change over time.

Timesharing: A method controlled by the operating system to share the computer processor with multiple users simultaneously. Each user is given a slice of the processor's cycle for program execution. Sometimes referred to as a multiuser system because more than one person is using the computer for different tasks.

Track: A path on disk storage where data is stored and accessed. Tracks on a hard disk are concentric bands, while on an optical disc the tracks form a spiral from the inside of the disc to the outside edge.

Track table of contents (TTOC): An index of every track and its contents on a CD disc. Single session CDs have one TTOC, while multisession discs have a separate index for each session.

Tracking: A technique to adjust the spacing between all letters in a text passage. Tracking is distinct from kerning, which adjusts spacing only between specific pairs of letters.

Trails: A pattern of associations described by Vannevar Bush in his 1945 article, "As We May Think." Trails were a means to organize information based on associations that could then be preserved, copied, shared, modified, and linked to other trails. This theoretical description of information associations became a reality in today's hyperlinked text on the WWW. See also *Memex*.

Transfer rate: The speed at which data moves from secondary storage into RAM or from RAM onto secondary storage. Transfer rates are measured in bytes/second.

Transitions: Video effects used to move into or out of a clip. Cut, fades, and dissolves are common transitions applied to video sequences.

Trimming: The process of removing unwanted frames from the beginning and/or end of a video clip.

TrueType: Outline font technology developed in 1991 by Microsoft and Apple and incorporated in all Macintosh and PC computers. It displaced Postscript outline technology for microcomputer use.

Turing, Alan: (1912–1954) A British mathematician, logician, and computer scientist. Turing helped develop the Colossus used to break the German Enigma code in WWII. In 1936 he wrote a theoretical description of the modern digital computer in a paper titled, “On Computable Numbers with an Application to the Entscheidungsproblem.” His description of an effective procedure became known as a “Turing machine,” an imaginary special-purpose device to solve a single task. See also *Universal Turing machine*.

Turing test: An exercise proposed by Alan Turing to demonstrate that a computer can think. Proposed in a 1950 paper, “Computing Machinery and Intelligence,” the test consists of an interrogator communicating via teletype with a person in one room and with a computer in another. If the interrogator cannot determine which of his interlocutors is the person and which is the computer, the computer is said to be thinking.

Tween animation: A computer animation technique in which the animator creates key frames and the computer automatically generates the tweens. See also *tweens*.

Tweens: In traditional cel animation, a sequence of drawings to represent an object’s change of position between one extreme and another extreme. Tweens were frequently drawn by apprentice animators, while the extremes were created by accomplished artists. See also *key frames*.

Typeface: A family of letters that share the same design. Common categories include serif, sans serif, and script. Typeface includes all the styles, cases, and sizes of each letter. New York, Times, and Courier are examples of typefaces.

Underscan: The technique of producing a display image that is smaller than the screen of the display device. This ensures that all screen content will appear on the display screen.

Unicode: A binary coding scheme using 16 bits to encode text from any alphabet system. The first 128 characters of Unicode are identical to ASCII coded data.

Universal Turing machine: A Turing machine is a theoretical device envisioned by Alan Turing to carry out an effective procedure. In 1936, Turing demonstrated that a particular type of Turing machine, called a *Universal Turing Machine*, could carry out any effective procedure. This was a theoretical model of the modern computer.

Upsampling: Adding samples to increase the spatial resolution of a bitmapped graphic file. Upsampling usually degrades the quality of the image. See also *downsampling* and *resampling*.


URL (uniform resource locator): The address scheme used in WWW protocols to hyperlink from one resource (web page or data file) to another. The URL syntax contains the HTTP protocol, the host computer name, domain, and a path to a particular resource on the Internet, for example: <http://yahoo.com/animation.html>.

USB (Universal Serial Bus): An input/output bus standard published in 1996 to connect peripheral devices to the system board. USB supports 127 devices daisy-chained together to one system port. Each device is hot swappable; that is, they can be connected and disconnected randomly without interrupting service to other devices.

USB 3: Upgrade to the USB interface standard that delivers up to 4.8 Gbps transfer speed.



Index



A

- access point (AP), [73](#)
- access time, 51
- acquisitions specialist, 231
- active matrix, [68](#)
- additive color, [125](#)
- address bus. *See* bus
- AIFF. *See* sound file format
- alias, [110](#)
- aliasing, 157
- alignment. *See* text
- alpha version, 237
- Altair, [41](#)
- amplitude, 153
- analog data. *See* data
- analog hole. *See* digital watermark
- analog to digital converter (ADC)
 - hardware device, [62](#)
 - sound, 155
 - video, [287](#)
- analog video, [172](#), 283
- animated GIFs, [201](#)
- animating with physics, 206
- animation, 193–208
 - 2-D animation, 201–204
 - 3-D animation, 204–207
 - cutouts, [201](#)
 - cycles, 197
 - defined, 96
 - ease-in/ease-out, 197
 - holds, 197
 - overlapping motions, [198](#)
 - overshoot, 197
 - shooting on twos, 197
 - stretch/squash, [198](#)
 - traditional animation, 196–200
- animation application, 96
- animation specialist, 230
- [anti-aliasing](#), [110](#)
- API (Application Programming Interface), [207](#)
- application software, [91](#)
- archived digital data, [35](#)
 - emulation and, [35](#)
 - migration and, [35](#)
- archiving (development process), 238
- arithmetic logic unit (ALU), [43](#)
- artificial intelligence (AI), [8](#)
- ascender. *See* point size
- ASCII (American Standard Code for Information Interchange)
 - [ASCII-8](#) (extended ASCII), [22](#)
 - defined, [22](#)

- ASCII (continued)
 - computer text, [108](#)
 - aspect ratio, [176](#)
 - assembler, [89](#)
 - assembly language, [89](#)
 - attenuation, [144](#)
 - AU. *See* sound file format
 - authoring application, [97–98](#), [115](#), [212](#)
 - authoring multimedia, [212–223](#)
 - defined, [212](#)
 - process, [215–218](#)
 - autotracing, [138](#)
 - AVCHD (advanced video coding high definition). *See* video file format
- B**
- background layer, [213](#)
 - backward compatibility, [56](#)
 - bandwidth, [34](#)
 - batch capture, [184](#)
 - Berners-Lee, Tim, [13](#)
 - beta version, [237](#)
 - binary
 - code, [23](#)
 - encoding, [21](#)
 - bit, [21](#)
 - bit depth
 - color bitmap images and, [127](#)
 - color resolution and, [131](#)
 - sample resolution and, [27](#)
 - scanning and, [63](#)
 - bitmap, [126](#)
 - bitmapped
 - fonts, [109](#)
 - graphics, [125–137](#)
 - image, [28](#)
 - bitmapped file formats
 - general purpose, [135](#)
 - metafiles, [135](#)
 - native, [135](#)
 - [bitmapping](#), [126](#)
 - blob, [142](#)
 - block, [55](#)
 - Blu-ray disc (BD), [61](#)
 - bluetooth, [74](#)
 - BMP. *See* graphic file format
 - browser, [14](#), [113](#)
 - bump map, [144](#)
 - bus
 - address bus, [45](#)
 - data bus, [45](#)
 - defined, [45](#)
 - system bus, [45](#)
 - width, [45](#)
 - Bush, Vannevar, [5](#)
 - byte, [22](#)
- C**
- cache, [44](#), [48](#)
 - level 2, [48](#)
 - primary, [48](#)
 - card metaphor, [213](#)
 - Cascading Style Sheets (CSS), [114](#)
 - case. *See* text
 - CD data format, [54](#)
 - cel
 - animation, [198–200](#)
 - defined, [198](#)
 - charge-coupled device (CCD)
 - scanner, [62](#)
 - video camera, [178](#)
 - checkers, [199](#)
 - chrominance, [284](#)
 - client computer, [14](#), [73](#)
 - client/server network model, [73](#)
 - clip art, [135](#)
 - clipping, [156](#)
 - clock speed, [44](#)
 - cloud storage, [62](#)
 - cluster, [85](#)
 - CMYK color palette, [125](#)
 - code of ethics, [244](#)
 - codec
 - defined, [29](#)
 - sound, [159](#)
 - video, [173](#), [187](#)
 - color banding, [132](#)
 - color gamut, [286](#)
 - color indexing, [133](#)
 - adaptive indexing, [133](#)

- perceptual indexing, [133](#)
 - color lookup table (CLUT), [127](#)
 - color palette, [127](#)
 - color resolution
 - CRT, [68](#)
 - image quality and, [131–133](#)
 - scanning [and](#), [63](#)
 - command-based. *See* digital encoding
 - command line interface, [81](#)
 - compact disc (CD), [54–58](#)
 - compact disc formats. *See also*
 - Appendix A
 - CD-DA, [56](#)
 - CD-R, [56](#)
 - CD-ROM, [56](#)
 - CD-RW, [56](#)
 - compiler, [89](#)
 - component color, [284](#)
 - composite color, [284](#)
 - compression
 - defined, [29](#)
 - lossless, [30](#)
 - lossy, [30](#)
 - condensed text. *See* text
 - constant angular velocity (CAV), [58](#)
 - constant bit rate encoding (CBR), [175](#)
 - constant linear velocity (CLV), [57](#)
 - content experts, [228](#)
 - content inventory list, [235](#)
 - content scrambling system (CSS), [252](#)
 - DeCSS, [253](#)
 - contone image, [123](#)
 - control unit (CU), [43](#)
 - convention, [20](#)
 - copyright, [247–251](#)
 - fixed form, [248](#)
 - infringement, [249](#)
 - protections, [248](#)
 - remedies, [249](#)
 - U.S. Copyright Law, [248](#)
 - CPU (central processing unit), [43](#)
 - Creative Commons, [260](#)
 - cross-platform compatibility
 - computer platforms, [42](#)
 - file compatibility, [24](#)
 - image file formats and, [136](#)
 - installed fonts and, [111](#)
 - CRT (cathode ray tube), [67, 284](#)
 - cutout. *See* animation
 - cycles. *See* animation
- ## D
- D1. *See* video file format
 - data
 - analog data, [20](#)
 - archived, [34](#)
 - bus, [45](#)
 - defined, [20](#)
 - digital, [20](#)
 - file, [24](#)
 - database, [219](#)
 - debugger, [220](#)
 - decibel, [153](#)
 - descender. *See* point size
 - description-based. *See* digital encoding
 - development plan, [232–238](#)
 - definition phase, [232](#)
 - design phase, [234](#)
 - production phase, [237](#)
 - device drivers, [83](#)
 - device-dependent graphics, [129](#)
 - device-independent graphics, [138](#)
 - digit, [21](#)
 - digital, [20](#)
 - digital-analog converter (DAC), [69](#)
 - sound capture and, [155](#)
 - digital camera, [64, 134](#)
 - digital data. *See* data
 - digital encoding
 - command-based, [28](#)
 - defined, [21](#)
 - description-based, [28](#)
 - effective code, [22](#)
 - efficient code, [22](#)
 - digital enlargement, [178](#)
 - Digital Millennium Copyright Act (DMCA), [254–256](#)
 - fair use and, [255](#)
 - Internet Service Provider (ISP) and, [254](#)

- digital rights management (DRM), 251–261
 - eBooks, 252
 - first generation DRM, 256
 - second generation DRM, 258
 - digital signal processor (DSP), 64
 - digital video camera, 65, 177–180
 - digital watermark, 257
 - analog hole and, 258
 - orphan copyrights and 258
 - digital zoom, 66
 - digitization, 26
 - Direct3D, 207
 - directory, 86
 - disc, 53
 - disk fragmentation, 85
 - display devices, 67–69
 - dithering color, 133
 - dot matrix. *See* printer
 - downloaded audio, 166
 - downsampling
 - image resolution, 129
 - sound resolution, 157
 - DPI (dots per inch), 128
 - draw program, 92, 137
 - DV. *See* video file format
 - DVD (digital versatile disc), 58–61
 - DVD formats, 59
 - DVD video. *See* video file format
 - dye-sublimation, 71
 - Dynabook, 11
- E**
- ease-in/ease-out. *See* animation
 - editable text, 110
 - effective procedure, 9
 - 8mm video, 285
 - eight-to-fourteen modulation (EFM), 54, 267
 - emulation. *See* archived digital data
 - end user license agreements (EULAs), 252
 - Englebart, Douglas, 10
 - EPS (encapsulated postscript). *See* graphic file format
 - error correction code (ECC), 54
 - error detection code (EDC), 54
 - ethernet, 73
 - expert system, 8
 - extension. *See* file
 - extrusion, 143
- F**
- fair use, 249
 - FairPlay, 253
 - Field, 176, 284
 - file, 23–25
 - compatibility, 24
 - conversion, 25
 - defined, 23, 85
 - extension, 23, 85
 - format, 23
 - incompatible formats, 34
 - native format, 24
 - system, 85
 - file maintenance, 25
 - categorization, 25
 - identification, 25
 - preservation, 25
 - file management, 85– 86
 - FireWire port, 49
 - first sale doctrine, 251
 - fixed form. *See* copyright
 - flash drive, 61
 - flash memory, 61
 - control gate, 61
 - floating gate, 61
 - Flash Video. *See* video file format
 - flipbook, 196
 - flowchart, 233
 - flowline, 214
 - font
 - bitmapped, 109
 - defined, 105
 - leading, 110
 - monospaced, 105
 - outline, 105
 - proportional, 105
 - sans serif, 104
 - serif, 104

technologies, 109
 foreground layer, 213
 formatting disk storage, [85](#)
 formula modeling. *See* modeling
 forward kinematics. *See* kinematics
 frame
 animation, 201–202
 authoring software, [215](#)
 optical storage, 55
 frame-by-frame animation, [202](#)
 frame rate
 digital video, [173](#)
 NTSC video, 284
 frequency, 153
 frequency modulation, 164
 functional specification, 234

G

generation decay
 defined, [32](#)
 sound quality, 165
 GIF (graphics interchange file). *See*
 graphic file format
 gigabyte, [23](#)
 gold master, 237
 graphic application, 94
 graphic file format
 BMP, [136](#)
 EPS, [139](#)
 GIF, [136](#)
 JPEG, [136](#)
 PICT, [136](#)
 PDF, [139](#)
 PNG, [137](#)
 SVG, [139](#)
 TIFF, [136](#)
 graphic specialist, 229
 graphic suites, [93](#)
 graphics, 121–147
 2-D computer graphics, 125–140
 3-D computer graphics, 140–146
 bitmapped, [125](#)
 bitmapping, [126](#)
 file formats, 136–137, [139](#)
 traditional graphics, 123–125
 vector, [137](#)
 graphics tablet, [66](#)
 graphics text, 112
 grayscale images, 123, [126](#)
 GUI (graphical user interface), [11](#), 81

H

halftone, 124
 handles, [138](#)
 hard drive, 52
 hardware, 39–74
 interface ports, 48
 memory, 47–48
 platform, [42](#)
 processor, 43–47
 system, [40](#)
 HDTV (high definition TV). *See* video file
 format
 HDV. *See* video file format
 hertz, [44](#), 153
 Hi8 video, 285
 Hierarchical File System Plus (HFS Plus),
 [85](#)
 holds. *See* animation
 HSB color (hue/saturation/brightness),
 [127](#)
 HTML (hypertext markup language), 113
 HyperCard, [13](#)
 hyperlinks, [73](#)
 navigation structure, 217
 hypermedia, [3](#), [10](#), [113](#)
 hypertext, [10](#), 113

I

Icon
 defined, 214
 metaphor, 214
 programming, 219
 IEEE 1394 (FireWire), [49](#)
 illegal colors (NTSC), 286
 image map
 graphics, [144](#)
 navigation structure, 217
[imagineering](#), [6](#), [15](#)
 impact printer, [69](#)

- information, [20](#)
 - inkers, [199](#)
 - ink-jet printer. *See* printer
 - instruction set, [46](#)
 - interactive (multimedia development), [226](#)
 - interface ports, [48](#)
 - interframe compression, [174](#)
 - B-frame, [175](#)
 - I-frame, [175](#)
 - P-frame, [175](#)
 - interlaced scan, [176](#), [284](#)
 - interlacing
 - graphics, [136](#)
 - NTSC video, [284](#)
 - Internet, [73](#)
 - interpreter, [89](#)
 - intraframe compression, [174](#)
 - intuitive interface, [236](#)
 - inverse kinematics. *See* kinematics
 - iterative (multimedia development), [226](#)
- J**
- jaggies
 - image quality and, [29](#)
 - text quality and, [110](#)
 - Jobs, Steve, [12](#)
 - on DRM, [254](#)
 - JPEG (Joint Photographic Experts Group). *See* graphic file format
 - Justification. *See* text
- K**
- Kay, Alan, [11](#)
 - Kerning letters, [105](#)
 - key frame, [199](#), [202](#)
 - kilobyte, [23](#)
 - kinematics
 - defined, [205](#)
 - forward kinematics, [205–206](#)
 - inverse kinematics, [206](#)
 - kiosk, [3](#)
- L**
- LAN (local area network), [73](#)
 - land, [54](#)
 - laser printer. *See* printer
 - laser, [54](#)
 - lathing, [143](#)
 - layers
 - animation, [202](#)
 - authoring applications, [213](#)
 - vector graphic, [138](#)
 - LCD (liquid crystal display), [68](#)
 - native resolution and, [68](#)
 - leading. *See* text
 - LED (light emitting diode), [68](#)
 - Leica reel, [200](#)
 - lighting (3-D graphics)
 - directional, [144](#)
 - omni, [144](#)
 - spot, [144](#)
 - volumetric, [144](#)
 - line art, [123](#), [126](#)
 - lines per inch (lpi), [123](#)
 - linescreen, [123](#)
 - link anchor (hypertext), [113](#)
 - link markers (hypertext), [113](#)
 - lossless compression
 - image compression, [135](#)
 - RLE and, [30](#)
 - lossy compression
 - image compression, [135](#)
 - intraframe compression and, [174](#)
 - MP3 and, [30](#)
 - sound compression, [159](#)
 - luminance, [284](#)
 - lux, [180](#)
- M**
- machine code, [88](#)
 - machine cycle, [44](#)
 - Macintosh computer, [12](#)
 - macro, [91](#)
 - Magnatune, [259](#)
 - magnetic storage, [52](#)
 - mainframe computer, [41](#)
 - Manhunt, [242](#)
 - mashup, [15](#)
 - master video, [184](#)

media specialists, 229–232
 media-specific application, [91](#)
 media utility programs, [97](#)
 megabyte, [23](#)
 megapixel, [134](#)
 Memex, [5](#)
 Cyclops camera and, [6](#)
 trail and, [6](#)
 Vocoder and, [6](#)
 Memex II, [7](#)
 memory card (digital camera), [64](#)
 memory management, [82](#)
 messages (MIDI commands), 160
 metaball. *See* modeling
 metafile, *See* bitmapped file format
 metamedium (Dynabook), [12](#)
 metaphor
 authoring languages, 213
 multimedia development, 236
 microcode, [46](#)
 microcomputer, [41](#)
 microprocessor, [41](#)
 MIDI (Musical Instrument Digital Interface), 160
 migration. *See* archived digital data
 mixing (sound tracks), 156
 mobile computing platforms, [42](#)
 modeler (3D images), [141](#)
 modeless (Dynabook), [12](#)
 modeling (3D graphics), 141–143
 formula, [143](#)
 metaball, [142](#)
 polygon, [141](#)
 spline, [142](#)
 morphing. *See* tween animation
 motion capture (performance animation), [205](#)
 motion graphics, [194](#)
 motion tween. *See* tween animation
 M-JPEG (Motion JPEG), 174
 Motion JPEG 2000. *See* video file format
 MP3 ([MPEG-1](#), audio player [3](#)), [30](#), [160](#)
 MPEG (Motion Picture Experts Group), 174
 multicore technology, [46](#)

multifunction printer. *See* printer
 multimedia
 adaptive (intellimedia), [4](#)
 basic, [3](#)
 defined, [2](#)
 immersive, [4](#)
 interactive, [3](#)
 noninteractive, [3](#)
 multimedia development, 226–238
 multimedia development team, 226–232
 multiprocessing, [46](#)
 multisession CDs, 55
 multitasking, [47](#), [82](#)
 multitimbral, 161
 multitouch, [86](#)
 multiuser system, [82](#)

N

nanotechnology, [47](#)
 navigation structures
 conditional, 217
 hierarchical, 217
 hyperlink, 217
 linear, 217
 networked, 217
 Nelson, Theodore, [10](#)
 network, [72](#)
 nodes (hypertext), 113
 nonimpact printer, [70](#)
 non-uniform rational B-spline (NURB), [142](#)
 Notepad, [91](#), [108](#)
 NTSC (National Television Standards Committee), 283–284
 NUI (natural user interface), 81

O

object-oriented language, [90](#)
 onionskinning
 animation software, [202](#)
 defined, [196](#)
 traditional animation, 199
 oNLineSystem, [10](#)
 opaquers, 199
 OpenGL, [207](#)

- Open Source Initiative, 260
 - operating system, [80](#)
 - optical character recognition (OCR), [63](#)
 - scanning text and, 116
 - optical drive, [57](#)
 - optical photo conductor (OPC), [71](#)
 - optical storage, 53. *See also* compact disc
 - DVD storage and, [58](#)
 - OS utility programs, [82](#), [84](#)
 - OS X, [80](#), [85](#)
 - output resolution (video), [173](#)
 - oversample (sound wave), 157
 - overscanning (NTSC video), 284
- P**
- paint program, [92](#), [133](#)
 - PAL (phase alternate line), 284
 - palette flashing, [133](#)
 - parallel data transmission, 48
 - parallel processing, [46](#)
 - parity bit, [31](#)
 - even parity, [31](#)
 - odd parity, [31](#)
 - patent, 248
 - path-based animation. *See* tween animation
 - pathname, [86](#)
 - PDF (portable document format). *See* graphic file format
 - PDF vector file format, [139](#)
 - pencil test, 200
 - performance animation. *See* motion capture
 - peripheral devices, [43](#), 50–72
 - persistence of vision
 - animation, 195
 - video, [172](#)
 - personal computer (PC), [41](#)
 - photo printer. *See* printer
 - pica, 104
 - PICT. *See* graphic file format
 - pipelining, [45](#)
 - pit, [54](#)
 - pitch, 153
 - pixel
 - bitmapped graphics, [125](#)
 - defined, [26](#)
 - digital camera resolution, [134](#)
 - monitor resolution, [67](#)
 - scanner resolution, [65](#)
 - pixel per inch (ppi), [128](#)
 - platform, [23](#)
 - player program, 221
 - plug and play (PnP), [83](#)
 - PNG (portable network graphic). *See* graphic file format
 - podcasting, 152
 - point size, 104
 - ascender, 104
 - descender, 104
 - polygon. *See* modeling
 - polyphonic, 161
 - postproduction and media creation, 235
 - PostScript, 110
 - praxinoscope, [196](#)
 - preemptive multitasking, [82](#)
 - preliminary proposal, 233
 - preproduction and media creation, 235
 - prerendering
 - animation, [207](#)
 - graphics, [145](#)
 - primary memory, [47](#)
 - primitives (3D graphics), [141](#)
 - constructive solid geometry, [141](#)
 - parametric, [141](#)
 - printer, 69–72
 - dot matrix, [69](#)
 - ink-jet, [70](#)
 - laser, [71](#)
 - multifunction, [72](#)
 - photo, [71](#)
 - product goal, 232
 - production. *See* development plan
 - production and media creation, 235
 - profession, 243
 - program, [80](#)
 - program file, 24
 - programmed animation, 203–204
 - programmer, 231

- programming approaches
 - nonprocedural, [90](#)
 - procedural, [90](#)
 - programming multimedia, [212](#), [218](#)
 - programming language, [88](#)
 - high-level language, [88](#)
 - low-level language, [89](#)
 - progressive downloading, [166](#)
 - progressive scan, [285](#)
 - project designer, [227](#)
 - project manager, [227](#)
 - protocols, [73](#)
 - prototype
 - defined, [234](#)
 - in design phase, [236](#)
 - psychoacoustics, [159](#)
 - public domain, [249](#)
 - pure tones, [153](#)
- Q**
- quantization
 - defined, [27](#)
 - image quality, [131](#)
 - sound quality, [155](#)
 - QuickTime, [84](#), [166](#), [176](#), [222](#)
- R**
- [radiosity](#), [145](#)
 - RAM (random access memory), [47](#)
 - random access, [57](#)
 - raster scanning, [67](#)
 - rasterize, [138](#)
 - RAW image format, [137](#)
 - ray tracing, [145](#)
 - RealAudio. *See* sound file format
 - real-time rendering
 - animation, [207](#)
 - graphics, [145](#)
 - RealVideo. *See* video file format
 - Recording Industry Association of America (RIAA), [256](#)
 - registers, [44](#)
 - registration (animation), [196](#)
 - rendering
 - 3-D graphic, [145](#)
 - animation, [207](#)
 - digital video, [187](#)
 - engines, [145](#)
 - resampling graphics, [129](#)–[131](#)
 - resolution
 - bitmapped image quality, [128](#)–[133](#)
 - digital camera, [64](#)
 - digital video quality and, [173](#)
 - LCD native, [68](#)
 - monitor, [67](#)
 - NTSC video, [283](#)
 - printer, [70](#)
 - sample. *See* sample resolution
 - scanner, [64](#)
 - spatial. *See* spatial resolution
 - RGB (red green blue), [178](#), [284](#)
 - RISC (reduced instruction set computing), [45](#)
 - RLE (run length encoding), [30](#)
 - ROM (read-only memory), [47](#)
 - rotoscoping, [201](#)
 - router, [73](#)
 - RTF (rich text format), [108](#)
 - rule of thirds, [180](#)
- S**
- safe action area, [286](#)
 - safe title area, [286](#)
 - sample rate
 - defined, [28](#)
 - sound boards and, [69](#)
 - sound quality and, [156](#)
 - sample resolution
 - defined, [27](#)
 - sound and, [155](#)
 - sample size
 - sound boards and, [69](#)
 - sampled sound, [28](#), [94](#), [154](#)
 - sampling, [26](#)
 - sans serif, [104](#)
 - scalable compression, [174](#)
 - scanner, [62](#)–[64](#)
 - scanning process, [271](#)–[273](#)
 - scene composition, [144](#)
 - scene detection, [184](#)
 - scratch track, [200](#)

- screen grab, 135
- screen resolution. *See* resolution
- script (authoring programs), 218
- scripting (programming languages), [91](#)
- SECAM (*Sequential Couleur Avec Memoire*), 284
- secondary storage, 50
 - devices, 52–62
 - performance, 51
 - uses, 51–52
- sector
 - CD storage unit, 55
 - magnetic storage unit, 52
- sequencer (MIDI data), 161
- serial data transmission, 48
- serif, 104
- server, [73](#)
- session (CD recording), 55
- shader (3-D graphics)
 - defined, [145](#)
 - flat, [145](#)
 - smooth, [145](#)
- shooting on twos. *See* animation
- shooting to record, 177
- shooting to edit, 177
- sine waves, 153
- size tweening. *See* tween animation
- Software Engineering Code of Ethics, 244, 275–282
- software, 79–98
 - applications, 91–97
 - defined, [80](#)
 - operating systems, 80–88
 - programming languages, 88–91
- solid-state storage, [61](#)
- Sony BMG, 253
- sound, 151–167
- sound application, 94
- sound capture, [66](#)
- sound file format, 159–160
 - AAC (advanced audio coding), 160
 - AIFF (audio interchange file format), 159
 - AU, 160
 - MP3, 160
 - RealAudio, 160
 - WAV, 159
 - WMA (Windows Media Audio), 160
- sound specialist, 239
- source video, 184
- spatial resolution
 - bitmapped graphics, [128](#)
 - CRT, [67](#)
 - defined, [28](#)
 - device dependence and, [129](#)
 - digital camera, [65](#)
 - resampling and, [129](#)
 - scanner, [62](#)
- speaker system, [69](#)
- speech recognition, 112
- speech synthesis, 112
- spline. *See* modeling
- splitting. *See* video editing
- stamping (optical storage), [54](#)
- storage capacity, 51
- standard definition TV (SDTV). *See* video
 - file format
- storyboard
 - animation, 199
 - authoring process, [215](#)
 - product proposal, 233
 - video editing, 183
- streaming audio, 160, 166
- stretch/squash. *See* animation
- style. *See* text
- subtractive color, [125](#)
- supercomputer, [41](#)
- surface definition, [144](#)
- SVG (scalable vector graphic). *See*
 - graphic file format
- S-Video, 287
- symbol, [20](#)
- synchronization (authoring), [216](#)
- synthesized sound, [29](#), [95](#), [154](#)
- synthesizer, [69](#), [95](#), 160
- system board, 48
- system unit, [43](#)
- systematic archiving, 238

T

TCP/IP (transmission control protocol/
internet protocol), [73](#)

terabyte, [23](#)

text, 101–117

alignment, [106](#)

case (lower and upper), [105](#)

computer codes, 107–109

condensed vs extended, [106](#)

editable, 111

editor, [92](#)

extended, [121](#)

font, [105](#)

graphics, 112

HTML, 113

justification, [106](#)

hypertext, 113

kerning, [105](#)

leading, [106](#)

point, 104

style, 104

tracking, [105](#)

typeface, [103](#)

weight, [105](#)

thaumatrope, 195

3-D animation. *See* animation

3-D graphic. *See* graphics

3-D imaging program, [92](#)

thin film transistor (TFT), [68](#)

Thunderbolt, [49](#)

TIFF (tagged image file format). *See*
graphic file format

time code, 181

timeline

animation, [201](#)

authoring metaphor, [215](#)

video editing, 183

timesharing, [82](#)

touchscreen and user interface, 81

track

disk storage, 52

optical storage, 55

track table of contents (TOC), 55

tracking. *See* text

transfer rate, 51

transitions. *See* video editing

trimming. *See* video editing

TrueType fonts, 110

Turing, Alan, [8](#)

Turing machine, [8](#)

Turing Test, [9](#)

universal Turing machine, [9](#)

tween animation, 202–203

alpha tween, 203

motion tween, [202](#)

path-based animation, [202](#)

shape tweening, (morphing), [202](#)

size tweening, 203

tweens, [202](#)

2-D animation. *See* animation

typeface. *See* text

U

underscanning, 286

Unicode, [22](#), [108](#)

upper case. *See* text

[upsampling](#), [129](#)

URL (uniform resource locator), [73](#)

USB (universal serial bus), [49](#)

USB [3.0](#), [49](#)

user interface

command line interface, 81

defined, [80](#)

graphical user interface (GUI), 81

multimedia development and, 235

natural user interface (NUI), 81

V

variable bit rate (VBR)

sound, 159

video, 175

VCR tape format

8mm, 285

Hi8, 285

S-VHS, 285

VHS, 285

vector, [137](#)

vector drawn graphic, 137–140

- video applications, [95](#)
 - video, 172–188
 - video data rate, 188
 - video editing, 183–186
 - splitting, 185
 - transitions, 185
 - trimming, 185
 - video file format (digital)
 - AVCHD (advanced video coding high definition), 176
 - D1, 176
 - DV, 176
 - DVD-Video, 176
 - Flash Video, 176
 - HDTV, 176
 - HDV, 176
 - Motion JPEG 2000, 176
 - QuickTime, 176
 - RealVideo, 176
 - SDTV, 176
 - Windows Media Video, 176
 - video specialist, 230
 - virtual memory, [83](#)
 - virtual reality, [4](#)
 - visual programming, [90](#)
 - volume, 153
- W**
- WAN (wide area network), [73](#)
 - WAV. *See* sound file format
 - wavetable synthesis, 164
 - web-safe palette, [133](#)
 - Weed, 259
 - weight. *See* text
 - white balancing, 181
 - Wi-Fi (wireless fidelity), [74](#)
 - Windows Explorer, [87](#)
 - Windows Media Video. *See* video file format
 - wire frame rendering, [145](#)
 - word processor, [92](#)
 - word size, [44](#)
 - works for hire, 249
 - World Intellectual Property Organization (WIPO), 254
 - Wozniak, Steve, [12](#)
 - writer, 228
 - WWW (World Wide Web), 13–14, [73](#)
- X**
- Xanadu, [11](#)
 - XHTML (extensible hypertext markup language), 114
 - XML (extensible markup language), 114
- Z**
- zip disk, 52
 - zoetrope, [196](#)